

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	MACON	106	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
** 05-00525-00SW				

### SUMMARY OF QUANTITIES

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CITY OF DECATUR	MILLIKIN UNIVERSITY
* 89501300	RELOCATE EXISTING MAST ARM ASSEMBLY AND POLE	EACH	1	1	
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	7314	7314	
* 89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1	1	
* XX007301	LUMINAIRE, METAL HALIDE, POST MOUNT, 250 WATT (ARCHITECTURAL)	EACH	32	32	
* XX007302	LIGHT POLE, DECORATIVE, 30' M.H., DUAL MAST ARM, SPECIAL	EACH	4	4	
* XX007303	LIGHT POLE, DECORATIVE, 30' M.H., MAST ARM, SPECIAL	EACH	20	20	
* XX007304	DECORATIVE POLES 10'	EACH	4	4	
* XX007305	DECORATIVE POLES 12'	EACH	6	6	
* XX007306	DECORATIVE POLES 14'	EACH	6	6	
* XX007307	CANOPIES 53'-6" LONG	EACH	2	2	
* XX007308	CANOPIES 67'-3" LONG	EACH	2	2	
XX001607	RETAINING WALL, SPECIAL	SQ FT	80	80	
XX003000	CLASS SICONCRETE STEPS	CU YD	1.5	1.5	
XX003219	UNIT PAVERS	SQ FT	4665	4665	
* XX005238	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	CU YD	100	100	
XX005907	INTERLOCKING BRICK PAVERS	SQ FT	42031	42031	
XX005908	CONCRETE CURB (SPECIAL)	FOOT	171	171	
X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	4522	4522	
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	867	515	352
X0322924	RETAINING WALL REMOVAL	SQ FT	88	88	
X0323444	DECORATIVE STEEL RAILING	FOOT	802	802	
X0325825	PAVEMENT REPLACEMENT	SQ YD	200	200	
X0350800	BOLLARDS	EACH	46	46	
XX007309	BOLLARDS, QUICK RELEASE	EACH	4	4	
* X0597100	CLEANING AND PAINTING EXISTING STRUCTURES	L SUM	1	1	
* X0945500	PAINT EXISTING POLE COMPLETE	EACH	2	2	
* X8210405	LUMINAIRE SHIELD	EACH	22	22	
* X8510250	PAINT EXISTING POLE, POST OR CONTROLLER COMPLETE	EACH	2	2	
X8780100	CONCRETE FOUNDATIONS (SPECIAL)	CU YD	74.3	74.3	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
* XX007310	TREE, ACER X FREEMAN II ARMSTRONG (ARMSTRONG FREEMAN MAPLE), 2-1/2" CALIPER BALLED AND BURLAPPED	EACH	5	5	
* XX007311	TREE, ACER SACCHARUM (GREEN MOUNTAIN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CITY OF DECATUR	MILLIKIN UNIVERSITY
* A2005520	TREE, NYSSA SYLVATICA (BLACK TUPELO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	3	
* A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8	8	
* XX007312	SHRUB, JUNIPERUS SABINA (BUFFALO JUNIPER), 3 GALLON CONTAINER	EACH	37	37	
* C2007224	SHRUB, ROSA KNOCKOUT (KNOCKOUT ROSE), 24" HEIGHT, CONTAINER	EACH	118	118	
* XX007315	SHRUB, TAXUS X MEDIA DENSIFORMIS (SPREADING YEW), 5 GALLON CONTAINER	EACH	29	29	
* XX005186	HEMEROCALLIS 'STELLA D'ORO' (IGAL)	EACH	170	170	
* XX007313	LIROPE SPICATA (CREEPING LILYTURF) 1 GALLON CONTAINER	EACH	1547	1547	
* X0030428	PERENNIAL PLANTS, SPOROBOLUS HETEROLEPIS, (PRAIRIE DROPSSEED), 1-GALLON	EACH	1174	1174	
* XX007314	SEDUM SPECTABILE, 1 GALLON CONTAINER	EACH	102	102	
* XX004529	RUDBECKIA FULGIDA 'GOLDSTRUM', 1 GALLON	EACH	102	102	
* XX007316	MULCH EXISTING TREES	EACH	3	3	

\* SPECIALTY ITEMS

REV. NO.	DESCRIPTION	BY	DATE	APPROVED
SUMMARY OF QUANTITIES				
DESIGN BWC	WEST MAIN STREET PHASE II CITY OF DECATUR			SCALE
DATE				BWC PROJECT NO. 009-0605
DRAWN	<b>BWC</b> BLANK, WESSELINK, COOK & ASSOCIATES, INC.			DATE
DATE				SHEET 3 OF 3
CHECKED	ARCHITECTS      ENGINEERS			
APPROVED	2623 EAST PERSHING ROAD DECATUR, IL 62524 (217) 428-0913 FAX (217) 428-8934			
DATE				