

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	MACON	106	18	
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
** 05-00525-00SW				

DECORATIVE POLES 10'

STATION	OFFSET	EACH
999+41	LT	2
2001+64	LT	2
		4

DECORATIVE POLES 12'

STATION	OFFSET	EACH
998+57	RT	2
998+90	LT	2
999+08	RT	2
		6

DECORATIVE POLES 14'

STATION	OFFSET	EACH
2002+15	RT	2
2002+31	LT	2
2002+82	RT	2
		6

RETAINING WALL, SPECIAL

STATION	TO STATION	OFFSET	SQ FT
32+45.00	32+85.00	LT	80

CLASS SI CONCRETE STEPS

STATION	OFFSET	CU YD
30+76.50	LT	0.42
31+10.00	LT	0.23
31+57.00	LT	0.81
		1.5

UNIT PAVERS

STATION	TO STATION	OFFSET	SQ FT
23+80	23+96	RT	75
23+84	23+98	LT	50
24+94	25+13	LT	113
24+96	25+08	RT	47
30+35	30+51	-	92
30+43	30+52	LT	36
30+43	30+52	RT	36
30+65	30+74	LT	36
30+65	30+74	RT	36
30+65	30+81	-	92
986+96	987+10	LT	51
986+97	987+09	RT	43
988+19	988+33	LT	61
988+19	988+33	RT	49
991+74	991+83	LT	95
991+74	991+83	RT	64
991+74	991+83	RT	82
991+94	992+03	LT	95
991+94	992+03	RT	63
991+94	992+03	RT	80
994+43	994+52	LT	31
994+43	994+52	LT	119
994+43	994+52	RT	126
994+63	994+72	LT	31
994+63	994+72	LT	117
994+63	994+72	RT	132
998+04	1000+24	RT	674
998+13	998+58	RT	86
998+24	1000+04	LT	550
998+94	999+45	RT	100
998+75	999+57	LT	115
1000+06	1000+36	LT	370
2000+59	2002+45	LT	610
2001+36	2001+66	LT	57
2002+00	2002+95	RT	186
2002+74	2003+02	RT	65
			4665

INTERLOCKING BRICK PAVERS

STATION	TO STATION	OFFSET	SQ FT
988+20.00	988+97.73	LT	2542
988+97.73	989+97.73	LT	2500
989+97.73	991+31.73	LT	2010
991+31.73	991+83.72	LT	572
988+20.00	991+65.00	RT	7107
991+65.00	991+83.72	RT	206
991+93.72	994+52.12	LT&RT	5685
994+62.12	996+44.77	LT&RT	4018
996+44.77	998+70.00	LT	4144
998+70.00	1000+23.00	LT	4177
999+43.00	1000+30.00	LT	762
996+44.77	1000+23.00	RT	4161
1000+23.00	1000+87.00	LT&RT	4147
			42031

CONCRETE CURB (SPECIAL)

STATION	TO STATION	OFFSET	FOOT
988+19.00	988+20.00	LT&RT	74
1000+22.00	1000+31.00	LT	11
1999+59.00	1999+60.00	LT&RT	40
2000+39.00	2000+40.00	LT&RT	35
2000+54.00	2000+61.00	LT	11
			171

SAW CUTTING, (FULL DEPTH)

STATION	TO STATION	OFFSET	FOOT
987+08.00	987+22.67	RT	24
987+08.63	987+26.73	LT	26
988+04.08	991+65.00	RT	372
988+04.09	992+00.00	LT	405
992+00.00	999+43.17	LT	745
991+65.00	1000+02.52	RT	840
999+43.17	1000+22.29	LT	95
1000+02.00	1000+38.00	LT	117
24+95.00	32+85.00	RT	795
24+95.00	32+85.00	LT	794
29+82.40	31+34.45	RT&LT	309
			4522

SEGMENTAL CONCRETE BLOCK WALL

STATION	TO STATION	OFFSET	SQ FT
W. MAIN ST. & FAIRVIEW SW QUADRANT			103
W. MAIN ST. & FAIRVIEW SE QUADRANT			126
996+57.00	998+46.00	RT	189
999+06.00	1000+03.00	RT	97
W. MAIN ST. & OAKLAND NW QUADRANT			352
			867

RETAINING WALL REMOVAL

STATION	TO STATION	OFFSET	SQ FT
32+45.00	32+85.00	LT	88

DECORATIVE STEEL RAILING

STATION	TO STATION	OFFSET	FOOT
23+83	23+90	RT	10
23+86	23+94	LT	10
25+00	25+11	LT	15
25+00	25+07	RT	10
30+40	30+50	LT	10
30+40	30+50	RT	10
30+67	30+77	LT	10
30+67	30+77	RT	10
986+97	987+04	LT	10
986+98	987+05	RT	10
988+23	988+31	LT	10
988+24	988+32	RT	10
991+61	991+81	LT	20
991+61	991+81	RT	20
991+96	992+16	LT	20
991+96	992+16	RT	20
992+04	994+42	LT	240
994+30	994+50	LT	20
994+30	994+50	RT	20
994+64	994+84	LT	20
994+64	996+34	RT	172
994+72	995+75	LT	105
996+07	996+27	LT	20
			802

BOLLARDS

STATION	OFFSET	EACH
23+82	RT	1
23+86	LT	1
23+90	RT	1
23+94	LT	1
24+99	LT	1
24+99	RT	1
25+08	RT	1
25+11	LT	1
30+51	LT	1
30+51	RT	1
30+65	LT	1
30+65	RT	1
986+96	LT	1
986+97	RT	1
987+05	LT	1
987+06	RT	1
988+22	LT	1
988+23	RT	1
988+32	LT	1
988+32	RT	1
991+53	LT	1
991+60	LT	1
991+60	RT	1
991+75	LT	1
991+83	LT	1
991+83	RT	1
991+95	LT	1
991+95	RT	1
992+03	LT	1
992+17	LT	1
992+17	RT	1
994+29	LT	1
994+29	RT	1
994+43	LT	1
994+51	LT	1
994+51	RT	1
994+63	LT	1
994+63	RT	1
994+71	LT	1
994+85	LT	1
995+76	LT	1
996+06	LT	1
996+28	LT	1
996+35	RT	1
1000+02	LT	1
2000+61	LT	1
		46

BOLLARDS, QUICK RELEASE

STATION	OFFSET	EACH
23+99	RT	1
24+02	LT	1
24+90	LT	1
24+92	RT	1
		4

REV. NO.	DESCRIPTION	BY	DATE	APPROVED
SCHEDULE OF QUANTITIES				
DESIGN BWC	WEST MAIN STREET PHASE II CITY OF DECATUR	SCALE		
DATE 4/06		BWC PROJECT NO.		
DRAWN RJC		009-0605		
DATE 4/06		DATE		
CHECKED	<b>BWC</b> BLANK, WESSELINK, COOK & ASSOCIATES, INC.	01/09/08		
DATE		ARCHITECTS ENGINEERS		
APPROVED		2623 EAST PERSHING ROAD DECATUR, IL 62524 (217) 428-0973 FAX (217) 428-8934		
DATE	4 OF 5			