

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9103	05-00046-01-PV	MADISON	25	6
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97339

**PATCHING SCHEDULE**

LOCATION	LENGTH (FOOT)	CLASS C PATCHES, 8"		CLASS B PATCHES, 8"			DOWEL BARS 1/2" DIA. (EACH)	TIE BARS 1/4" DIA. (EACH)	TIE BARS 3/4" DIA. (EACH)
		TYPE I (SQ YD)	TYPE II (SQ YD)	TYPE II (SQ YD)	TYPE III (SQ YD)	TYPE IV (SQ YD)			
WAYNE LANTER AVENUE									
STA. 10+68.58 TO STA. 10+74.55	6.0				21.1		30	30	
STA. 11+31.52 TO STA. 11+51.35	19.74 - 7.12					36.0	30	30	
STA. 12+17.50 TO STA. 12+22.39	4.9		6.5						
STA. 12+69.98 TO STA. 12+77.51	7.5			9.9			10	10	
STA. 13+67.32 TO STA. 13+69.97	2.7	3.5							
STA. 14+69.74 TO STA. 14+73.29	3.6	2.4							
STA. 15+54.59 TO STA. 15+63.32	8.7					30.9	30	30	
STA. 18+64.66 TO STA. 18+72.90	8.3			11.0			10	10	
STA. 18+68.33 TO STA. 18+72.89	3.4	4.6 - 2.6							
STA. 19+16.94 TO STA. 19+23.26	6.3			8.4			10	10	
STA. 19+67.43 TO STA. 19+73.23	5.8		7.7						
STA. 20+65.84 TO STA. 20+70.21	4.3		5.8						
STA. 21+76.65 TO STA. 21+80.43	3.8		10.0						
STA. 22+20.00 TO STA. 22+23.01	3.0	2.1							
STA. 22+79.30 TO STA. 23+02.95	23.6 - 9.9					47.0	20	20	24
STA. 23+16.71 TO STA. 23+20.44	3.6		8.0						
STA. 23+67.05 TO STA. 23+77.64	10.4			11.9			10	10	
STA. 23+69.75 TO STA. 23+74.53	4.7 - 3.7		11.2						
STA. 24+69.71 TO STA. 24+73.09	3.4	4.5							
STA. 25+16.35 TO STA. 25+22.41	6.1			8.0			10	10	
STA. 26+69.61 TO STA. 27+02.12	32.5					43.9	10	10	34
STA. 27+66.05 TO STA. 27+72.05	6.0			8.1			10	10	
STA. 28+19.88 TO STA. 28+21.53	1.7	2.3							
STA. 28+67.53 TO STA. 28+69.98	2.5	1.3							
STA. 28+69.96 TO STA. 28+74.02	4.1		5.4						
STA. 29+13.21 TO STA. 29+27.67	14.4					32.2	20	20	
STA. 29+81.03 TO STA. 29+85.57	4.5		12.2						
STA. 30+79.34 TO STA. 30+84.96	5.6		6.2						
STA. 30+69.29 TO STA. 30+86.46	17.2 - 7.2					32.6	20	20	
STA. 33+38.51 TO STA. 33+42.14	3.6		12.9						
STA. 34+83.00 TO STA. 34+89.43	6.4				22.8		30	30	
STA. 35+90.07 TO STA. 35+94.96	4.9	4.4							
STA. 35+94.83 TO STA. 36+01.25	6.5				17.1		20	20	
STA. 38+06.23 TO STA. 38+13.65	7.5			10.0			10	10	
STA. 39+75.96 TO STA. 39+85.07	9.0			11.9			10	10	
STA. 39+75.96 TO STA. 39+81.61	5.6 - 4.1		11.2						
STA. 40+76.34 TO STA. 40+83.43	7.1					25.3	30	30	
STA. 41+10.35 TO STA. 41+20.48	10.1			9.0			10	10	
STA. 41+64.36 TO STA. 41+82.92	18.6					65.8	30	30	
TOTAL		21	97	88	61	314	360	360	58

**PAVEMENT MARKING SCHEDULE**

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKINGS			
		4" YELLOW (FOOT)	4" WHITE (FOOT)	6" WHITE (FOOT)	12" WHITE (FOOT)
WAYNE LANTER AVENUE					
STA. 10+00.00 TO STA. 42+12.99	SKIP-DASH 10'-30'	861			
	CROSSWALK			548	
	STOP BAR				195
	LANE LINE		2593		
TOTAL		861	2593	548	195

**PAVING SCHEDULE**

LOCATION	BITUMINOUS MATERIAL PR CT (GALLON)	AGGREGATE PR CT (TON)	HOT-MIX ASPHALT SURF CSE, MIX C, N70 (TON)	LEVELING BINDER (MACHINE METHOD) N70 (TON)
WAYNE LANTER AVENUE				
STA. 10+00.00 TO STA. 42+12.99	1037.8	38.1	1577.0	720.0
TOTAL	1038	38	1577	720

**SIDEWALK SCHEDULE**

LOCATION	SIDEWALK 4 INCH (SQ FT)
WAYNE LANTER AVENUE	
STA. 16+43.52 - 35.90' RT TO STA. 16+51.67 - 41.62' RT	36.3
STA. 16+88.50 - 41.73' RT TO STA. 16+99.44 - 25.13' RT	65.1
STA. 19+37.17 - 23.95' LT TO STA. 19+81.07 - 28.64' LT	213.64
STA. 23+59.08 - 31.00' LT TO STA. 23+70.90 - 24.28' LT	76.31
STA. 30+79.74 - 24.31' LT TO STA. 30+88.81 - 31.26' LT	45.0
STA. 31+23.21 - 33.56' LT TO STA. 31+34.52 - 23.46' LT	75.15
STA. 36+35.69 - 23.94' LT TO STA. 36+46.52 - 36.84' LT	82.10
STA. 36+83.07 - 33.95' LT TO STA. 36+94.01 - 23.94' LT	71.3
STA. 41+12.72 - 24.34' LT TO STA. 41+23.38 - 29.41' LT	54.21
TOTAL	719

**DETECTABLE WARNING SCHEDULE**

LOCATION	DETECTABLE WARNINGS (SQ FT)
WAYNE LANTER AVENUE	
STA. 16+46.09 - 36.40' RT TO STA. 16+49.90 - 40.40' RT	8.7
STA. 16+89.84 - 40.40' RT TO STA. 16+93.41 - 36.40' RT	8.5
STA. 16+94.73 - 30.76' RT TO STA. 16+98.15 - 29.76' RT	11.01
STA. 23+61.64 - 29.64' LT TO STA. 23+69.92 - 24.76' LT	15.53
STA. 30+80.54 - 24.81' LT TO STA. 30+87.11 - 30.03' LT	13.2
STA. 31+24.45 - 33.60' LT TO STA. 31+30.80 - 25.95' LT	19.76
STA. 36+36.91 - 24.45' LT TO STA. 36+43.74 - 29.98' LT	14.82
STA. 36+86.08 - 29.24' LT TO STA. 36+92.87 - 24.44' LT	12.5
TOTAL	104

DATE	BY
SURVEYED	
PLOTTED	
TEMPLATE	
AREAS CHECKED	
FINAL SURVEY NOTE BOOK NO.	

DATE	BY
SURVEYED	
PLOTTED	
TEMPLATE	
AREAS CHECKED	
ORIGINAL SURVEY NOTE BOOK NO.	

**Juneau Associates, Inc. P.C.**  
CONSULTING ENGINEERS AND LAND SURVEYORS  
2100 State Street, P.O. Box 1325  
Ottawa, Illinois 62450  
Phone: (314) 387-1400 / (314) 387-4525  
Fax: (314) 387-5541

**QUANTITY SCHEDULES**  
**WAYNE LANTER AVENUE**  
**MADISON, ILLINOIS**  
**SECTION 05-00046-01-PV**

NO.		DATE	BY	REVISIONS	REMARKS
SCALE: N.T.S.					
DSN. BY:	BFK	DATE:	02/08/08	SHEET	
DWN. BY:	DAN	DATE:	02/08/08	6	
CHK'D:	BFK	DATE:	02/08/08		
DWG. NO.	JOB NO. E071005			DGN. NAME:	COMBSCHD OF 25 SHTS