



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2014

SUBJECT: Various Routes
Section D3 GRVD PVMT MRK RPR 14-48
Various Counties
Contract No. 46317
Item No. 1, April 25, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised the Table of Contents to the Special Provisions
3. Added page 29 to the Special Provisions
4. Revised sheet 3 of the plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Paul A. Loete, Region 2, District 3;; Tim Kell; Estimates

MS/kp

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 46317

State Job # - C-60-053-14

County Name - VARIOUS- -

Code - 0 - -

District - 0 - -

Section Number - D3 GRVD PVMT MRK RPR 14-48

Project Number
 *REVISED: APRIL 11, 2014

Route
 VARIOUS

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|-------------|---|------------|---|-------------|
| *ADD X7010410 | SPEED DISPLAY TRAILER | CAL MO | 1.000 | | | | |
| X7800815 | HS THPL PM LN 4 | FOOT | 350,000.000 | | | | |
| X7800835 | HS THPL PM LN 6 | FOOT | 50,000.000 | | | | |
| X7800845 | HS THPL PM LN 8 | FOOT | 15,000.000 | | | | |
| X7830068 | GRV RCSD PVT LT N SYM | SQ FT | 3,000.000 | | | | |
| X7830070 | GRV RCSD PVT MRKG 5 | FOOT | 100,000.000 | | | | |
| X7830074 | GRV RCSD PVT MRKG 7 | FOOT | 20,000.000 | | | | |
| X7830076 | GRV RCSD PVT MRKG 9 | FOOT | 15,000.000 | | | | |
| X7830078 | GRV RCSD PVT MRKG 13 | FOOT | 3,200.000 | | | | |
| Z0008758 | AERIAL SPEED CHK MK | FOOT | 200.000 | | | | |
| 78000100 | THPL PVT MK LTR & SYM | SQ FT | 1,800.000 | | | | |
| 78000200 | THPL PVT MK LINE 4 | FOOT | 5,000.000 | | | | |
| 78000400 | THPL PVT MK LINE 6 | FOOT | 1,000.000 | | | | |
| 78000500 | THPL PVT MK LINE 8 | FOOT | 2,000.000 | | | | |
| 78000600 | THPL PVT MK LINE 12 | FOOT | 2,000.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

46317

State Job # - C-60-053-14

Project Number
 *REVISED: APRIL 11, 2014

Route
 VARIOUS

County Name - VARIOUS- -

Code - 0 - -

District - 0 - -

Section Number - D3 GRVD PVMT MRK RPR 14-48

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|-------------|---|------------|---|-------------|
| 78000650 | THPL PVT MK LINE 24 | FOOT | 1,200.000 | | | | |
| 78003130 | PREF PL PM TB LINE 6 | FOOT | 10,000.000 | | | | |
| 78005100 | EPOXY PVT MK LTR-SYM | SQ FT | 500.000 | | | | |
| 78005110 | EPOXY PVT MK LINE 4 | FOOT | 175,000.000 | | | | |
| 78005130 | EPOXY PVT MK LINE 6 | FOOT | 8,000.000 | | | | |
| 78005140 | EPOXY PVT MK LINE 8 | FOOT | 15,000.000 | | | | |
| 78005150 | EPOXY PVT MK LINE 12 | FOOT | 1,000.000 | | | | |
| 78005180 | EPOXY PVT MK LINE 24 | FOOT | 1,000.000 | | | | |
| 78008210 | POLYUREA PM T1 LN 4 | FOOT | 80,000.000 | | | | |
| 78008230 | POLYUREA PM T1 LN 6 | FOOT | 3,000.000 | | | | |
| 78008240 | POLYUREA PM T1 LN 8 | FOOT | 7,200.000 | | | | |
| 78009000 | MOD URETH PM LTR-SYM | SQ FT | 2,000.000 | | | | |
| 78009004 | MOD URETH PM LINE 4 | FOOT | 995,000.000 | | | | |
| 78009006 | MOD URETH PM LINE 6 | FOOT | 225,000.000 | | | | |
| 78009008 | MOD URETH PM LINE 8 | FOOT | 45,000.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 46317

State Job # - C-60-053-14

Project Number

Route

County Name - VARIOUS--

*REVISED: APRIL 11, 2014

VARIOUS

Code - 0 - -

District - 0 - -

Section Number - D3 GRVD PVMT MRK RPR 14-48

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|----------------------|--------------------|------------|---|------------|---|-------------|
| 78009012 | MOD URETH PM LINE 12 | FOOT | 10,000.000 | | | | |
| 78009024 | MOD URETH PM LINE 24 | FOOT | 1,200.000 | | | | |
| 78300100 | PAVT MARKING REMOVAL | SQ FT | 500.000 | | | | |

TABLE OF CONTENTS

| | |
|--|----|
| LOCATION OF IMPROVEMENT | 1 |
| COMPLETION DATE..... | 1 |
| DESCRIPTION OF IMPROVEMENTS | 1 |
| TRAFFIC CONTROL PLAN..... | 1 |
| CHANGEABLE MESSAGE SIGN..... | 2 |
| WORK ORDERS | 2 |
| FAILURE TO COMPLETE A WORK ORDER ON TIME..... | 3 |
| QUANTITIES | 3 |
| FINAL CLEAN UP..... | 4 |
| FINAL INSPECTION AND PAYMENT | 4 |
| 45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING | 4 |
| CONTRACT CLAIMS (BDE)..... | 14 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... | 15 |
| PAYROLLS AND PAYROLL RECORDS (BDE) | 25 |
| PROGRESS PAYMENTS (BDE)..... | 27 |
| WEEKLY DBE TRUCKING REPORTS (BDE)..... | 27 |
| SPEED DISPLAY TRAILER (BDE)..... | 29 |

Revised 04/14/2014

SPEED DISPLAY TRAILER (BDE)

Effective: April 2, 2014

Add the following to Article 701.15(l) of the Standard Specifications:

“(l) Speed Display Trailer. A speed display trailer shall be utilized on freeways and expressways as part of Highway Standard 701400. The trailer shall be placed on the right hand side of the roadway adjacent to, or within 100 ft (30 m) beyond, the first work zone speed limit sign.

Whenever the speed display trailer is not in use, it shall be considered non-operating equipment and shall be stored according to Article 701.11.”

Add the following to Article 701.20 of the Standard Specifications:

“(k) Speed Display Trailer will be paid for at the contract unit price per calendar month or fraction thereof for each trailer as SPEED DISPLAY TRAILER.”

Add the following to Article 1106.02 of the Standard Specifications:

“(o) Speed Display Trailer. The speed display trailer shall consist of a LED speed indicator display with self-contained, one-direction radar mounted on an orange see-through trailer. The height of the display and radar shall be such that it will function and be visible when located behind concrete barrier.

The speed measurement shall be by radar and provide a minimum detection distance of 1000 ft (300 m). The radar shall have an accuracy of ± 1 mile per hour.

The speed indicator display shall face approaching traffic and shall have a sign legend of “YOUR SPEED” immediately above or below the speed display. The digital speed display shall show two digits (00 to 99) in mph. The color of the changeable message legend shall be a yellow legend on a black background. The minimum height of the numerals shall be 18 in. (450 mm), and the nominal legibility distance shall be at least 750 ft (250 m).

The speed indicator display shall be equipped with a violation alert that flashes the displayed detected speed when the posted limit is exceeded. The speed indicator shall have a maximum speed cutoff. The display shall include automatic dimming for nighttime operation.

The speed indicator measurement and display functions shall be equipped with the power supply capable of providing 24 hours of uninterrupted service.”

Added 04/14/2014

Various Routes
 D3 GRVD PVMT MRK RPR 14-48
 Various Counties
 Sheet 3 of 5
 Contract No. 46317
100% STATE
9021
 7,200

| | | | |
|----------|--|-------|---------|
| 78008240 | POLYUREA PAVEMENT MARKING TYPE I - LINE 8" | FOOT | 7,200 |
| 78009000 | MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 2,000 |
| 78009004 | MODIFIED URETHANE PAVEMENT MARKING - LINE 4" | FOOT | 995,000 |
| 78009006 | MODIFIED URETHANE PAVEMENT MARKING - LINE 6" | FOOT | 225,000 |
| 78009008 | MODIFIED URETHANE PAVEMENT MARKING - LINE 8" | FOOT | 45,000 |
| 78009012 | MODIFIED URETHANE PAVEMENT MARKING - LINE 12" | FOOT | 10,000 |
| 78009024 | MODIFIED URETHANE PAVEMENT MARKING - LINE 24" | FOOT | 1,200 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 500 |
| X7800815 | HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH | FOOT | 350,000 |
| X7800835 | HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 6 INCH | FOOT | 50,000 |
| X7800845 | HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 8 INCH | FOOT | 15,000 |
| X7830068 | GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS | SQ FT | 3,000 |
| X7830070 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | FOOT | 100,000 |
| X7830074 | GROOVING FOR RECESSED PAVEMENT MARKING 7" | FOOT | 20,000 |
| X7830076 | GROOVING FOR RECESSED PAVEMENT MARKING 9" | FOOT | 15,000 |
| X7830078 | GROOVING FOR RECESSED PAVEMENT MARKING 13" | FOOT | 3,200 |
| Z0008758 | AERIAL SPEED CHECK MARKING | FOOT | 200 |

17 X7010410 SPEED DISPLAY TRAILER CAL MO 1 

A Rev 4-11-14