

PAVEMENT REMOVAL			
FROM STA	TO STA	OFFSET	SQUARE YARDS
109+00	110+00	LT	268
109+00	110+00	RT	268
110+00	115+50	LT	1,474
110+00	115+50	RT	1,473
115+50	121+50	LT	1,604
115+50	121+50	RT	1,598
121+50	124+94	LT	900
121+50	124+75	RT	852
125+07	127+00	LT	515
124+88	127+00	RT	568
127+00	132+50	LT	1,485
127+00	132+50	RT	1,701
132+50	133+50	LT	269
132+50	133+13	RT	252
134+04	134+39	LT	101
INTERSECTION			1,865
134+61	138+00	RT	957
134+90	138+00	LT	1,202
138+00	139+60	LT	458
138+00	139+60	RT	612
50+30	51+96	LT+RT	769
53+94	55+23	LT+RT	503
TEMPORARY PAVEMENT			10,960
200+00	200+30		29
TOTAL			30,682

COMBINATION CURB AND GUTTER REMOVAL				
FROM STA	TO STA	OFFSET	OFFSET	FOOT
103+81	104+50	LT	9	70
103+81	104+50	RT	9	69
104+50	110+00	LT	9	550
104+50	110+00	RT	9	550
109+00	110+00	LT	33	100
109+00	110+00	RT	33	100
110+00	115+50	LT	9	550
110+00	115+50	RT	9	550
110+00	115+50	LT	33	550
110+00	115+50	RT	33	550
115+50	121+50	LT	9	600
115+50	121+50	RT	9	600
115+50	121+50	LT	33	600
115+50	121+50	RT	33	600
121+50	124+57	LT	9	307
121+50	124+57	RT	9	307
121+50	124+94	LT	33	344
121+50	124+64	RT	33	314
125+23	127+00	LT	9	177
125+22	127+00	RT	9	179
125+15	127+00	LT	33	185
124+88	127+00	RT	33	212
127+00	130+57	LT	9	357
127+00	130+57	RT	9	359
127+00	132+50	LT	33	550
127+00	132+50	RT	33	550
132+50	134+05	LT	33	204
132+50	133+53	RT	33	145
134+38	138+00	LT	33	412
133+99	138+00	RT	33	437
138+00	139+60	LT	33	160
138+00	139+60	RT	33	160
50+30	51+77	LT	21	148
50+30	51+96	RT	23	166
53+94	55+23	LT	17	142
53+97	55+31	RT	17	149
51+10	51+25	RT	40	31
51+58	51+73	RT	40	30
TOTAL				12,064

SIDEWALK REMOVAL			
FROM STA	TO STA	OFFSET	SQUARE FOOT
99+53	104+50	LT	2,450
104+50	110+00	LT	2,693
110+00	115+50	LT	2,721
115+50	121+50	LT	3,021
121+50	127+00	LT	2,273
127+00	132+50	LT	2,677
132+50	133+95	LT	996
134+49	138+00	LT	1,964
138+00	141+21	LT	1,592
133+28	133+36	RT	222
134+12	134+61	RT	467
50+30	51+72	LT	699
50+30	51+21	RT	453
51+61	52+03	RT	189
53+93	55+20	LT	618
53+97	55+25	RT	769
TOTAL			23,804

DRIVEWAY PAVEMENT REMOVAL		
STATION	OFFSET	SQUARE YARDS
113+50	RT	75
122+74	RT	58
123+59	LT	151
51+41	RT	119
TOTAL		403

BIKE PATH REMOVAL			
FROM STA	TO STA	OFFSET	SO YD
115+74	121+50	RT	623
121+50	127+00	RT	482
127+00	132+50	RT	576
132+50	133+36	RT	84
134+35	135+28	RT	74
TOTAL			1,840

MEDIAN REMOVAL		
FROM STA	TO STA	SO FT
101+50	103+81	1,815
124+58	124+84	398
124+98	125+22	359
130+56	132+50	1,663
132+50	133+50	571
134+61	138+00	1,862
138+00	141+21	1,793
TOTAL		8,461

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24			
STATION		OFFSET	FEET
FROM	TO		
103+82	104+50	4 LT	70.5
103+82	104+50	9 RT	69.0
104+50	110+00	9 LT	550.0
104+50	110+00	9 RT	550.0
109+00	110+00	9 LT	100.0
109+00	110+00	9 RT	100.0
110+00	115+50	9 LT	550.0
110+00	115+50	33 LT	550.0
110+00	115+50	9 RT	550.0
110+00	115+18	33 RT	519.0
115+18	115+50	33 RT	32.0
115+50	121+50	9 LT	600.0
115+50	116+50	33 LT	100.0
115+50	121+50	9 RT	600.0
121+50	122+42	9 LT	92.5
121+50	122+34	9 RT	84.5
125+61	127+00	9 LT	128.5
125+53	127+00	9 RT	147.0
127+00	129+76	9 LT	275.5
127+00	129+76	9 RT	276.5
130+90	132+50	9 RT	160.5
131+89	132+50	33 LT	61.5
132+50	133+70	33 LT	70.0
132+50	132+90	33 RT	40.0
133+20	133+55	33 LT	35.0
INTERSECTION			
NORTHWEST			80.5
SOUTHWEST			101.0
NORTHEAST			81.5
SOUTHEAST			114.5
134+62	138+00	33 RT	312.0
134+88	138+00	33 LT	338.0
138+00	139+60	33 LT	160.0
138+00	139+60	33 RT	160.0
50+30	51+83	24 LT	153.0
50+30	51+83	24 RT	153.0
53+87	55+23	17 LT	149.0
53+87	55+30	17 RT	159.0
TOTAL			8,274

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		
FROM STA	TO STA	SQUARE YARDS
50+26	50+30	35
55+23	55+27	17
TOTAL		53

CURB REMOVAL AND REPLACEMENT		
LOCATION	FOOT	
SHARED-USE TRAIL AT FRONTENAC	20	
TOTAL		20

FILE NAME = Q:\DOT_25368367_US_34.ctb CN Ph2Drawings\Roadway\General\DI6R06-Sht-Sched.Ldgn



USER NAME = URS	DESIGNED - MB	REVISED -
DRAWN - KJB	REVISIONS -	
PLOT SCALE = 1/8" = 1'	CHECKED - SPF	REVISIONS -
PLOT DATE = 02/28/2014	DATE - 02/28/2014	REVISIONS -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 1 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A		383	31
CONTRACT NO. 60R06			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	