

STORM SEWER REMOVAL 12"					
FROM		TO		LEN FT	TBF CU YD
STA	OFFSET	STA	OFFSET		
110+89	-0.5	110+92	-3.7	4.5	0.9
110+92	32.3	110+93	-31.0	63.3	18.5
112+31	36.0	112+34	-28.9	65	19.0
112+35	-33.7	112+38	-37.6	5.2	2.1
113+67	3.4	113+71	-0.4	6	1.4
113+70	38.3	113+72	-25.0	63.3	9.3
114+84	39.9	114+85	-23.2	63.1	9.1
114+84	5.3	114+99	9.7	15.3	3.9
114+86	-27.9	114+89	-30.9	4.6	0.9
115+02	-27.4	115+06	-30.2	4.5	0.9
115+08	-27.8	115+13	40.4	68.3	11.0
115+14	45.2	115+16	54.0	9	0.7
115+66	-29.5	116+28	-25.4	62.3	16.1
116+31	-22.8	116+32	40.4	63.1	13.4
116+31	3.4	116+40	7.1	9.2	2.6
117+61	-22.7	117+61	42.1	64.8	20.8
118+96	4.2	119+08	7.1	12.6	2.9
120+42	40.4	120+45	-24.4	64.9	6.7
121+75	-31.3	121+82	-39.8	11.1	3.0
121+81	4.5	121+88	7.5	7.3	2.5
121+82	45.6	121+82	54.0	8.3	1.2
123+19	-32.5	123+24	-27.2	7.3	1.6
123+21	54.8	123+21	45.6	9.2	0.8
123+21	40.6	123+25	-22.4	63.2	10.5
124+17	-35.9	124+25	-47.4	13.7	2.1
124+18	-32.8	124+23	-27.2	7.8	2.2
124+25	-22.8	124+27	16.4	39.3	7.0
125+08	16.6	125+29	9.6	22.2	3.6
125+24	-23.1	125+52	7.3	41.5	7.8
125+34	9.6	125+51	9.5	17.4	4.5
125+50	40.8	125+54	11.7	29.3	5.1
125+50	45.8	125+51	56.7	11	0.7
126+01	-22.8	126+01	9.1	32	5.5
127+52	5.5	127+54	-37.1	42.7	5.3
128+41	40.4	128+42	7.2	33.2	7.6
128+42	-22.7	128+42	7.2	29.9	6.2
129+61	-22.6	129+61	4.0	26.6	6.9
129+61	9.0	129+61	40.5	31.5	8.3
130+91	-22.7	130+91	5.3	28	4.8
130+91	5.2	130+92	40.6	35.4	5.5
132+20	2.4	132+21	-22.5	24.9	6.8
132+20	7.4	132+21	40.5	33.1	8.6
133+06	58.3	133+29	54.8	23.2	1.5
133+32	51.7	133+39	6.6	45.5	13.0
133+62	-27.2	133+69	-36.6	11.5	3.6
134+12	75.7	134+15	76.4	3.1	0.6

STORM SEWER REMOVAL 12"					
FROM		TO		LEN FT	TBF CU YD
STA	OFFSET	STA	OFFSET		
134+12	75.7	134+15	76.4	3.1	0.6
134+18	52.7	134+18	74.5	21.8	4.2
134+98	-32.3	135+03	-27.9	6.9	1.7
135+07	41.8	135+18	41.7	11.6	2.0
135+13	-34.3	135+19	-28.7	8.5	1.7
135+19	52.7	135+20	44.3	8.5	1.0
135+20	-23.7	135+21	39.4	63	10.3
136+36	-37.4	136+40	-31.2	7.5	1.8
136+41	-26.2	136+41	38.4	64.6	12.6
137+55	-39.2	137+59	-34.1	6.3	1.6
137+60	-29.3	137+61	35.3	64.5	9.8
138+77	-40.9	138+80	-35.6	5.9	1.5
50+43	-21.3	50+46	20.7	42.1	2.2
50+48	25.0	50+54	32.4	9.4	1.7
50+57	33.9	52+27	30.5	169.3	38.7
52+28	24.6	52+29	27.7	3.1	0.6
54+17	19.8	54+18	36.4	16.6	5.3
54+19	-18.0	54+17	14.8	32.9	5.3
TOTAL				1881	379

STORM SEWER REMOVAL 15"					
FROM		TO		LEN FT	TBF CU YD
STA	OFFSET	STA	OFFSET		
113+74	-29.1	113+77	-32.4	4.2	1.0
116+76	-22.7	116+76	55.8	78.5	24.4
118+91	-25.8	119+01	40.4	66.9	22.9
118+93	-28.1	118+98	-26.1	5.4	1.4
121+75	-28.5	121+80	-26.0	5.6	2.3
121+76	-29.9	124+13	-34.1	238	78.4
121+81	-24.0	121+82	40.6	64.7	16.0
133+47	-45.9	133+68	-39.7	21.9	5.2
133+73	-38.5	134+55	-52.7	83.4	31.4
134+60	-53.5	134+78	-49.6	18.9	6.4
TOTAL				587	189.4

STORM SEWER REMOVAL 18"					
FROM		TO		LEN FT	TBF CU YD
STA	OFFSET	STA	OFFSET		
112+04	68.8	112+61	-36.1	119	69
113+81	-33.0	115+05	-30.3	125	31.5
115+10	-30.2	115+61	-29.7	51	13.2
115+66	-30.6	115+91	-43.0	28.6	8.1
116+40	-36.3	116+56	-31.0	17.2	13.4
116+64	-29.7	116+73	-26.5	9.8	6.7
134+20	50.4	134+79	43.0	59	13.2
134+81	-31.0	134+82	40.0	71	27.5
TOTAL				481	182.6

STORM SEWER REMOVAL 24"					
FROM		TO		LEN FT	TBF CU YD
STA	OFFSET	STA	OFFSET		
125+56	9.4	127+50	8.1	193	87.3
133+41	3.2	134+78	-33.1	142	59.7
134+80	-46.3	134+81	-36.0	10.3	3.5
137+56	-40.9	139+20	-40.7	163	59
TOTAL				509	209.5

STORM SEWER REMOVAL 30"					
FROM		TO		LEN FT	TBF CU YD
STA	OFFSET	STA	OFFSET		
118+93	-28.3	121+71	-29.3	278	167.9
127+55	7.8	129+58	6.4	204	113.2
134+83	-33.7	137+51	-40.8	268	104.4
138+81	-30.7	138+82	33.8	64.5	12.8
TOTAL				814	398.3

STORM SEWER REMOVAL 36"					
FROM		TO		LEN FT	TBF CU YD
STA	OFFSET	STA	OFFSET		
116+64	-30.5	118+88	-28.5	224	181.5
129+63	6.1	132+18	4.4	254	136.8
132+23	5.0	133+37	4.0	114	54.9
TOTAL				592	373.2

FILE NAME = Q:\DOT_25368367_US_34.ctb CN Ph2\Drawings\Roadway\General\1616106-Sht-Sched.dgn



USER NAME = URS	DESIGNED - MB	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN - KJB	REVISED -
PLOT DATE = 02/28/2014	CHECKED - SPF	REVISED -
	DATE - 02/28/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 5 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A		383	35
CONTRACT NO. 60R06			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	