

EARTHWORK SCHEDULE

PRE-STAGE						
LOCATION		TOPSOIL (CUT)	EARTH EXCAVATION (CUT)	EXCAVATION TO BE USED IN EMBANKMENT (CUT) *	EMBANKMENT (FILL)	EARTHWORK BALANCE, WASTE(+) OR SHORTAGE(-)
FROM	TO	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
100+00.00	100+50.00	0.0	5.7	4.8	0.0	4.8
100+50.00	101+00.00	0.0	5.6	4.8	0.0	4.8
101+00.00	101+50.00	0.0	5.8	5.0	0.0	5.0
101+50.00	102+00.00	0.0	6.2	5.2	0.0	5.2
102+00.00	102+50.00	0.0	11.4	9.6	0.0	9.6
102+50.00	103+00.00	0.0	20.8	17.7	0.0	17.7
103+00.00	103+50.00	0.0	30.2	25.7	0.0	25.7
103+50.00	104+00.00	4.6	31.4	26.7	0.0	31.3
104+00.00	104+50.00	10.5	30.4	25.8	0.0	36.3
104+50.00	105+00.00	12.1	31.8	27.0	0.0	39.1
105+00.00	105+50.00	12.4	30.1	25.6	0.0	37.9
105+50.00	106+00.00	12.4	30.3	25.7	0.0	38.1
106+00.00	106+50.00	12.2	30.9	26.3	0.0	38.5
106+50.00	107+00.00	12.0	31.5	26.8	0.0	38.8
107+00.00	107+50.00	12.0	32.3	27.4	0.0	39.4
107+50.00	108+00.00	12.0	33.1	28.1	0.0	40.1
108+00.00	108+50.00	12.0	33.4	28.4	0.0	40.4
108+50.00	109+00.00	12.0	33.0	28.1	0.0	40.1
109+00.00	109+50.00	12.0	32.4	27.5	0.0	39.5
109+50.00	110+00.00	12.0	31.6	26.8	0.0	38.9
110+00.00	110+50.00	12.1	30.4	25.9	0.0	38.0
110+50.00	111+00.00	12.2	29.5	25.1	0.0	37.3
111+00.00	111+50.00	12.2	29.3	24.9	0.0	37.1
111+50.00	112+00.00	12.1	29.4	25.0	0.0	37.1
112+00.00	112+50.00	12.2	29.6	25.2	0.0	37.4
112+50.00	113+00.00	12.3	29.9	25.4	0.0	37.7
113+00.00	113+50.00	12.2	29.8	25.3	0.0	37.5
113+50.00	114+00.00	12.1	29.8	25.3	0.0	37.4
114+00.00	114+50.00	12.0	30.6	26.0	0.0	38.1
114+50.00	115+00.00	12.0	31.3	26.6	0.0	38.6
115+00.00	115+50.00	12.1	30.4	25.9	0.0	37.9
115+50.00	116+00.00	12.1	29.1	24.8	0.0	36.9
116+00.00	116+50.00	12.1	28.6	24.3	0.0	36.4
116+50.00	117+00.00	12.2	28.5	24.2	0.1	36.3
117+00.00	117+50.00	12.2	28.7	24.4	0.1	36.5
117+50.00	118+00.00	12.2	29.0	24.7	0.0	36.9
118+00.00	118+50.00	12.2	29.2	24.8	0.0	37.1
118+50.00	119+00.00	12.3	29.5	25.1	0.0	37.4
119+00.00	119+50.00	12.4	29.9	25.4	0.0	37.8
119+50.00	120+00.00	12.5	30.0	25.5	0.0	37.9
120+00.00	120+50.00	12.6	30.0	25.5	0.0	38.1
120+50.00	121+00.00	12.6	30.1	25.6	0.0	38.2
121+00.00	121+50.00	12.7	30.3	25.7	0.0	38.4
121+50.00	122+00.00	12.8	30.4	25.8	0.0	38.6
122+00.00	122+50.00	12.2	30.4	25.9	0.0	38.1
122+50.00	123+00.00	11.6	30.9	26.2	0.0	37.8
123+00.00	123+50.00	11.6	32.1	27.3	0.0	38.9
123+50.00	124+00.00	11.6	33.9	28.8	0.0	40.4

PRE-STAGE						
LOCATION		TOPSOIL (CUT)	EARTH EXCAVATION (CUT)	EXCAVATION TO BE USED IN EMBANKMENT (CUT) *	EMBANKMENT (FILL)	EARTHWORK BALANCE, WASTE(+) OR SHORTAGE(-)
FROM	TO	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
124+00.00	124+50.00	11.6	36.5	31.0	0.0	42.6
124+50.00	125+00.00	11.6	43.3	36.8	0.0	48.4
125+00.00	125+50.00	11.9	45.7	38.8	2.1	48.6
125+50.00	126+00.00	14.9	46.9	39.8	4.5	50.3
126+00.00	126+50.00	21.3	51.4	43.6	4.5	60.4
126+50.00	127+00.00	22.4	59.9	51.0	2.7	70.6
127+00.00	127+50.00	19.9	74.3	63.2	1.0	82.1
127+50.00	128+00.00	20.6	85.2	72.4	0.6	92.4
128+00.00	128+50.00	23.8	94.7	80.5	0.1	104.2
128+50.00	129+00.00	27.3	104.4	88.7	0.2	115.8
129+00.00	129+50.00	29.8	116.1	98.7	0.1	128.4
129+50.00	130+00.00	30.6	126.5	107.6	0.1	138.1
130+00.00	130+50.00	28.6	125.8	107.0	0.1	135.5
130+50.00	131+00.00	25.7	111.4	94.7	0.1	120.3
131+00.00	131+50.00	22.0	92.0	78.2	0.3	99.9
131+50.00	132+00.00	16.9	72.0	61.2	1.5	76.7
132+00.00	132+50.00	12.6	51.3	43.6	10.3	45.9
132+50.00	133+00.00	12.0	34.5	29.4	14.4	26.9
133+00.00	133+50.00	9.9	35.7	30.3	5.5	34.8
133+50.00	134+00.00	9.2	33.7	28.7	0.0	37.9
134+00.00	134+50.00	10.3	23.4	19.8	0.0	30.2
134+50.00	135+00.00	9.3	32.0	27.2	0.0	36.5
135+00.00	135+50.00	9.7	47.4	40.3	0.5	49.5
135+50.00	136+00.00	8.0	34.6	29.5	0.9	36.5
136+00.00	136+50.00	4.6	13.1	11.2	0.5	15.3
136+50.00	137+00.00	2.1	9.0	7.7	0.1	9.6
137+00.00	137+50.00	0.7	6.8	5.8	0.1	6.4
137+50.00	138+00.00	0.5	6.2	5.3	0.3	5.5
138+00.00	138+50.00	0.0	5.9	5.0	1.8	3.3
138+50.00	139+00.00	0.0	6.6	5.6	1.5	4.1
139+00.00	139+50.00	0.0	7.7	6.6	0.0	6.6
139+50.00	140+00.00	0.0	8.2	6.9	0.0	6.9
140+00.00	140+50.00	0.0	4.1	3.5	0.0	3.5
140+50.00	141+00.00	0.0	0.0	0.0	0.0	0.0
50+30.00	50+50.00	2.0	9.5	8.1	0.0	10.1
50+50.00	51+00.00	10.7	49.8	42.3	0.0	53.0
51+00.00	51+50.00	11.7	54.8	46.5	0.0	58.3
51+50.00	52+00.00	16.7	65.2	55.4	0.0	72.1
52+00.00	52+64.00	30.3	105.2	89.4	0.0	119.8
53+33.00	53+50.00	40.9	141.8	120.5	0.0	161.4
53+50.00	54+00.00	9.6	32.5	27.6	0.0	37.2
54+00.00	54+00.00	21.4	69.3	58.9	0.1	80.2
54+00.00	54+50.00	9.5	30.8	26.2	0.0	35.6
54+50.00	54+80.00	0.0	0.0	0.0	0.0	0.0
TOTAL		1,070.2	3,543.6	3,012.1	54.1	4,028.3

* ADJUSTED FOR SHRINKAGE (15%)

FILE NAME = Q:\DOT_25368367_US_34.ctb CN P:\Drawings\Roadway\General\1161806-Smt-Sched.dgn



USER NAME = URS	DESIGNED - MB	REVISED -
	DRAWN - KJB	REVISED -
PLOT SCALE = 1" = 40'	CHECKED - SPF	REVISED -
PLOT DATE = 02/28/2014	DATE - 02/28/2014	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 6 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A		383	36
CONTRACT NO. 60R06				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				