

# EARTHWORK SCHEDULE

SHARED USE TRAIL					
LOCATION		EARTH EXCAVATION ( CUT )	EXCAVATION TO BE USED IN EMBANKMENT ( CUT ) *	EMBANKMENT ( FILL )	EARTHWORK BALANCE, WASTE( + ) OR SHORTAGE( - )
FROM	TO	CU. YD.	CU. YD.	CU. YD.	CU. YD.
200+00.00	200+50.00	30.5	25.9	0.3	25.6
200+50.00	201+00.00	53.8	45.7	0.0	45.7
201+00.00	201+50.00	61.9	52.6	0.0	52.6
201+50.00	202+00.00	52.3	44.5	0.0	44.5
202+00.00	202+50.00	42.0	35.7	0.0	35.7
202+50.00	203+00.00	43.3	36.8	0.0	36.8
203+00.00	203+50.00	64.9	55.2	0.0	55.2
203+50.00	204+00.00	81.3	69.1	0.0	69.1
204+00.00	204+50.00	108.3	92.1	0.0	92.1
204+50.00	205+00.00	162.7	138.3	0.0	138.3
205+00.00	205+50.00	201.7	171.4	0.0	171.4
205+50.00	206+00.00	223.5	190.0	0.0	190.0
206+00.00	206+50.00	264.0	224.4	0.0	224.4
206+50.00	207+00.00	238.1	202.4	0.0	202.4
207+00.00	207+50.00	91.8	78.0	17.5	60.5
207+50.00	208+00.00	2.5	2.1	17.8	-15.7
208+00.00	208+50.00	11.2	9.5	0.3	9.2
208+50.00	209+00.00	18.8	16.0	0.0	16.0
209+00.00	209+50.00	18.0	15.3	0.1	15.2
209+50.00	210+00.00	18.0	15.3	0.1	15.2
210+00.00	210+50.00	20.0	17.0	0.0	17.0
210+50.00	211+00.00	19.5	16.6	0.0	16.6
211+00.00	211+50.00	13.1	11.1	0.5	10.6
211+50.00	212+00.00	10.8	9.2	0.6	8.7
TOTAL		1,851.9	1,574.2	37.0	1,537.1

\* ADJUSTED FOR SHRINKAGE ( 15% )

EARTHWORK SUMMARY ( BY STAGE )					
STAGE	TOPSOIL ( CUT )	EARTH EXCAVATION ( CUT )	EXCAVATION TO BE USED IN EMBANKMENT ( CUT ) *	EMBANKMENT ( FILL )	EARTHWORK BALANCE, WASTE( + ) OR SHORTAGE( - )
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
PRE-STAGE	1,070.2	3,543.6	3,012.1	54.1	4,028.3
STAGE 1	733.2	2,746.0	2,334.1	22,599.6	-19,532.4
STAGE 2	433.3	2,058.3	1,440.4	29,236.7	-27,363.1
TOTAL ( ROUNDED )	2,240	8,350	6,790	51,895	-42,870

\* ADJUSTED FOR SHRINKAGE ( 15% )

US ROUTE 34 SUMMARY	
DESCRIPTION	QUANTITY
EARTH EXCAVATION	8,350
FURNISHED EXCAVATION	42,870

SHARED-USE TRAIL SUMMARY	
DESCRIPTION	QUANTITY
EARTH EXCAVATION	1,855
FURNISHED EXCAVATION	0

FILE NAME = Q:\DOT\_25368367\_US\_34.ctb CN Ph2\Drawings\Roadway\General\DI6R06-Sht-Sched.dgn



USER NAME = URS	DESIGNED - MB	REVISED -
	DRAWN - KJB	REVISED -
PLOT SCALE = 1" = 40'	CHECKED - SPF	REVISED -
PLOT DATE = 02/28/2014	DATE - 02/28/2014	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. 9 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A	DUPAGE	383	39
CONTRACT NO. 60R06				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				