

FILE NAME = C:\1001_23368367_US_34.ctb P:\2\Drawings\Roadway\General\10162806_Sht-500.dgn

CONSTRUCTION CODE									
67% CANADIAN NATIONAL RAILROAD 33% STATE					67% CN 23% STATE 10% AURORA		80% STATE 20% FVPD +		100% AURORA
ROADWAY	BRIDGE	RETAINING WALLS				NOISE WALL	TRAFFIC SIGNALS	SHARED-USE TRAIL	
0001	0008	0040				0040	0021	0028	0043
URBAN	URBAN	URBAN				URBAN	URBAN	URBAN	URBAN
	S. N. 022-0512	S. N. 022-W068	S. N. 022-W069	S. N. 022-W070	S. N. 022-W071				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY								
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SO YD	3147	3147							
* 25000100	SEEDING, CLASS 1	ACRE	1.25	1.25							
* 25000300	SEEDING, CLASS 3	ACRE	1.00							1.00	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	292	292							
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	292	292							
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	292	292							
* 25000750	MOWING	ACRE	4.50	4.50							
* 25100115	MULCH, METHOD 2	ACRE	3.25	2.25						1.00	
* 25100630	EROSION CONTROL BLANKET	SO YD	6050	6050							
* 25200110	SODDING, SALT TOLERANT	SD YD	14427	14427							
* 25200200	SUPPLEMENTAL WATERING	UNIT	23	20						3	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	699	447						252	
28000305	TEMPORARY DITCH CHECKS	FOOT	300	300							
28000400	PERIMETER EROSION BARRIER	FOOT	2416	2416							

* SPECIALTY ITEM NP-100% STATE + FVPD = FOX VALLEY PARK DISTRICT CN = CANADIAN NATIONAL RAILROAD



USER NAME - URS	DESIGNED - MB	REVISED -
PLOT SCALE - 100,0000' / in.	DRAWN - KJB	REVISED -
PLOT DATE - 2/11/2014	CHECKED - SPF	REVISED -
	DATE - 2/11/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A		383	5
CONTRACT NO. 60R06			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	