

FILE NAME = D:\1101T-25360267-US-34.ctb CN Proj\Drawings\Roadway\General\01\01\01\01-50.dgn

				CONSTRUCTION CODE									
				67% CANADIAN NATIONAL RAILROAD 33% STATE					67% CN 23% STATE 10% AURORA	80% STATE 20% FVPD +	100% AURORA		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	RETAINING WALLS				NOISE WALL	TRAFFIC SIGNALS	SHARED-USE TRAIL	
				0001	0008	0040				0040	0021	0028	0043
				URBAN	URBAN	URBAN				URBAN	URBAN	URBAN	URBAN
				S. N. 022-0512	S. N. 022-W068	S. N. 022-W069	S. N. 022-W070	S. N. 022-W071					
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SO YD	15780	15780									
42001300	PROTECTIVE COAT	SO YD	21135	21128								7	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	1066	1066									
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	205	205									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	27329	27329									
42400800	DETECTABLE WARNINGS	SO FT	160	160									
44000100	PAVEMENT REMOVAL	SO YD	30682	30653								29	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	403	403									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	12064	12064									
44000600	SIDEWALK REMOVAL	SO FT	23804	23804									
44003100	MEDIAN REMOVAL	SO FT	8461	8461									
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SO YD	150	150									
44201684	CLASS D PATCHES, TYPE IV, 3 INCH	SO YD	301	301									
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	106	106									

* SPECIALTY ITEM + FVPD = FOX VALLEY PARK DISTRICT CN = CANADIAN NATIONAL RAILROAD



USER NAME - URS	DESIGNED - MB	REVISED -
DRAWN - KJB	CHECKED - SPF	REVISED -
DATE - 2/11/2014		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE. 311	SECTION 652-A	COUNTY DUPAGE	TOTAL SHEETS 383	SHEET NO. 7
CONTRACT NO. 60R06				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				