	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 67% CANADIAN NATIONAL RAILROAD 33% STATE — ROADWAY 0001 URBAN	BRIDGE 0008 URBAN S.N. 022-0512	RETAINING WALLS 0040 URBAN S.N. 022-W068	S.N. 022-W069	S.N. 022-W070	S.N. 022-W071	NOISE WALL 0040 URBAN	67 % CN 23% STATE 10% AURORA — TRAFFIC SIGNALS 0021 URBAN	80% STATE 20% FVPD + — SHARED-USE TRAIL 0028 URBAN	100 % AURORA 0043 URBAN
*	87700330	STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH	1								1		
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24								24		
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4								4		
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	35								35		
*	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21								21		
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8								8		
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2								2		
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2								2		
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2								2		
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4								4		
*	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2								2		
*	88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	10								10		
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	10								10		
*	88600700	PREFORMED DETECTOR LOOP	FOOT	942								942		

* SPECIALTY ITEM + FVPD = FOX VALLEY PARK DISTRICT CN = CANADIAN NATIONAL RAILROAD

FILE NAME = Q:\IDOT_25368367_US 34 at CN Ph2\Drawings\Roadway\General\0160R06-Sht-Sa0.dgn

URS

USER NAME = URS	DESIGNED - MB	REVISED -	
	DRAWN - KJB	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED - SPF	REVISED -	
PLOT DATE = 2/11/2014	DATE - 2/11/2014	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A	DUPAGE	383	17

CONTRACT NO. 60R06

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT