	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
					67% CANADIAN NATIONAL RAILROAD 33% STATE							67 % CN 23%STATE 10% AURORA	80% STATE 20% FVPD +	100 % AURORA
					ROADWAY	BRIDGE	RETAINING WALLS				NOISE WALL	TRAFFIC SIGNALS	SHARED-USE TRAIL	
					0001	0008	0040				0040	0021	0028	0043
					URBAN	URBAN	URBAN				URBAN	URBAN	URBAN	URBAN
						S. N. 022-0512	S. N. 022-W068	S. N. 022-W069	S. N. 022-W070	S. N. 022-W071				
*	B2006316	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10									
*	B2010070	TREE, CLADRASTIS KENTUCKEA (AMERICAN YELLOWWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9									
*	D2002472	EVERGREEN, PINUS FLEXILIS VANDERWOLF'S PYRAMID (VANDERWOLF'S PYRAMID LIMBER PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	15									15	
*	E2002006	VINE-CAMPSIS RADICANS (TRUMPET VINE), 1-GALLON POT	EACH	18	18									
*	E2021001	VINE-PARTHENOCISSUS QUINQUEFOLIA ENGEL MANNII (ENGELMANNII VIRGINIA CREEPER), 1-GALLON POT	EACH	2054	2054									
*	K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	25	20								5	
	X0301423	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ FT	42033							42033			
	X0321963	MICRO-PILES	EACH	92		92								
	X0323149	TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	20659			9084		11575					
	X0323433	MICROPILE PROOF LOAD TEST	EACH	2		2								
	X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	261			89	92	80					
*	X0325003	REMOVE EXISTING VALVE AND VAULT	EACH	2										2
	X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	1	1									
	X0327036	BIKE PATH REMOVAL	SQ YD	1840	1840									

* SPECIALTY ITEM

+ FVPD = FOX VALLEY PARK DISTRICT

CN = CANADIAN NATIONAL RAILROAD

FILE NAME : D:\1001-2536387-US 34 at CN Prj\Drawings\Roadway\General\0168R06-Sht-Sod.dgn

URS

USER NAME = URS	DESIGNED - MB	REVISED -
	DRAWN - KJB	REVISED -
PLOT SCALE = 100.0000 ' / in.	CHECKED - SPF	REVISED -
PLOT DATE = 2/11/2014	DATE - 2/11/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	652-A	DUPAGE	383	21
		CONTRACT NO. 60R06		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		