

### ROADWAY REMOVAL SCHEDULE

LOCATION	44000100	44000300	44000500	44000600	44003100	44004250	50102400	X4403800
	PAVEMENT REMOVAL SQ YD	CURB REMOVAL FOOT	COMB C&G REMOVAL FOOT	SIDEWALK REMOVAL SQ FT	MEDIAN REMOVAL SQ FT	PAVED SHOULDER REMOVAL SQ YD	CONCRETE REMOVAL CU YD	MEDIAN SURFACE REMOVAL SQ FT
US ROUTE 30								
259+00 TO 269+00	4,153	0	1,505	0	0	0	337	0
269+00 TO 280+00	7,695	801	4,584	124	307	0	481	1,901
280+50 TO 289+25	5,157	0	2,658	0	536	0	0	5,596
289+25 TO 301+00	6,049	0	2,774	0	1,318	0	0	4,710
SAUK TRAIL								
378+50 TO 387+00	1,500	0	790	0	0	175	0	0
<b>TOTALS</b>	<b>24,554</b>	<b>801</b>	<b>12,311</b>	<b>124</b>	<b>2,161</b>	<b>175</b>	<b>818</b>	<b>12,207</b>

### TRAFFIC BARRIER & GUARDRAIL SCHEDULE


LOCATION	63100085	63100167	63100169	78200410	78201000
	TRAFFIC BARRIER TERMINAL, TY 6 EACH	TRAFFIC BARRIER TERMINAL TY 1 (SPECIAL) TANGENT EACH	TRAFFIC BARRIER TERMINAL TY 1 (SPECIAL) FLARED EACH	GUARDRAIL MARKERS, TY A EACH	TERMINAL MARKER DIRECT APPLIED EACH
US ROUTE 30					
262+00 TO 276+00	1	2	0	6	2
276+00 TO 289+00	1	0	1	6	1
289+00 TO 300+20	0	0	0	0	0
<b>TOTALS</b>	<b>2</b>	<b>2</b>	<b>1</b>	<b>12</b>	<b>3</b>

### PROPOSED DRIVEWAY SCHEDULE

LOCATION	LT/RT	X4060110	40603335	42300200	42300400	60600605	60603800
		BIT MATR (PRIME COAT) POUND	HMA SURF CSE MIX D, N50 TON	PCC DRIVEWAY PAVEMENT, 6" SQ YD	PCC DRIVEWAY PAVEMENT, 8" SQ YD	CONC CURB TY B FOOT	COMB CONC C&G TY B-6.12 FOOT
US ROUTE 30							
261+80.45	RT	0	0	0	61	53	0
263+49.21	RT	0	0	0	48	41	0
265+44.66	RT	0	0	0	82	45	0
266+25.90	RT	0	0	0	100	48	0
266+29.25	LT	303	15.1	0	107	110	0
267+13.97	LT	0	0	0	85	40	0
268+81.02	LT	0	0	0	134	46	0
288+54.84	LT	0	0	0	20	0	0
291+73.62	LT	0	0	0	20	0	0
295+56.49	LT	0	0	0	19	0	0
297+32.17	LT	0	0	0	88	42	0
SAUK TRAIL							
383+12.00	LT	0	0	50	0	0	0
383+79.00	LT	0	0	66	0	0	0
WEST FRONTAGE ROAD NORTH							
100+96.29	LT	0	0	0	143	97	0
102+95.08	LT	1106	55.1	0	63	25	0
107+06.26	RT	0	0	0	261	0	114
WEST FRONTAGE ROAD SOUTH							
402+06.15	LT	0	0	0	247	77	0
403+09.00	LT	0	0	0	81	51	0
404+25.85	LT	0	0	0	64	61	0
404+92.02	LT	0	0	111	0	73	0
405+76.78	LT	0	0	104	0	81	0
406+54.56	LT	0	0	95	0	48	0
<b>TOTALS</b>		<b>1409</b>	<b>70</b>	<b>426</b>	<b>1,623</b>	<b>938</b>	<b>114</b>

### DRIVEWAY REMOVAL SCHEDULE

LOCATION	LT/RT	44000200
		DRV PVMNT REMOVAL SQ YD
US ROUTE 30		
STA. 261+80	RT	64.5
STA. 263+30	RT	47.7
STA. 265+49	RT	90.9
STA. 266+06	LT	111.6
STA. 266+26	RT	608.7
STA. 267+40	RT	345.8
STA. 268+72	LT	122.2
STA. 270+50	RT	646.8
STA. 273+00	LT	5,869.1
STA. 274+00	RT	275.3
STA. 278+50	RT	139.1
STA. 279+00	RT	114.1
STA. 280+50	RT	113.8
STA. 284+00	RT	203.7
STA. 285+00	RT	93.2
STA. 285+50	RT	75.7
STA. 286+50	RT	86.7
STA. 287+20	RT	109.3
STA. 288+75	RT	143.9
STA. 289+00	LT	70.7
STA. 289+00	LT	5,100.2
STA. 292+00	LT	161.0
STA. 295+25	LT	109.4
STA. 298+00	LT	82.1
SAUK TRAIL		
STA. 383+00	LT	57.0
STA. 384+00	LT	88.5
<b>TOTALS</b>		<b>14,932</b>



V3 Companies  
7325 Janes Avenue  
Woodridge, IL 60517  
630.724.9200 phone  
630.724.9202 fax  
www.v3co.com

USER NAME = dsherman  
DESIGNED - DSS  
DRAWN - DRP  
CHECKED - VJD  
DATE - 02/21/2014

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: N/A SHEET NO. 2 OF 9 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	11-Y-A	COOK	354	29
CONTRACT NO. 60R19				
ILLINOIS FED. AID PROJECT				