

PROPOSED PAVING SCHEDULE


LOCATION	30300112 AGGREGATE SUBGRADE IMPRV. 12" SQ YD	31101400 SUBGRADE GRAN MATR TYPE B, 6" SQ YD	31101810 SUBGRADE GRAN MATR TYPE B, 12" SQ YD	35101598 AGGREGATE BASE CRSE TYPE B, 3" SQ YD	35300500 PCC BASE CRSE 10" SQ YD	35400500 PCC BASE CRSE WIDENING 10" SQ YD	35501316 HMA BASE CRSE 8" SQ YD	X4060110 BIT MATR (PRIME COAT) POUND	40600982 HMA SURF REMOVAL BUTT JOINT SQ YD	40603085 HMA BIND CRSE IL-90, N70 TON
US ROUTE 30										
262+99.42 TO 276+00	12,016	1,150	614	0	0	0	953	2,841	0	0
276+00 TO 289+00	8,534	1,317	648	0	0	0	0	2,773	0	0
289+00 TO 302+00	11,346	922	189	0	0	0	0	2,075	0	0
SAUK TRAIL										
380+00 TO 386+75	3,377	233	0	0	249	60	0	724	133	84
WEST FRONTAGE ROAD NORTH										
100+00 TO 113+75.52	5,361	0	0	689	0	0	492	11,445	0	1,675
WEST FRONTAGE ROAD SOUTH										
401+10 TO 409+70	3,294	0	0	302	0	0	0	8,894	0	1,053
TOTALS	43,928	3,723	1,451	991	249	60	1,445	30,839	133	2,812

PROPOSED PAVING SCHEDULE

LOCATION	40603335 HMA SURF CRSE MIX "D", N50 TON	40603340 HMA SURF CRSE MIX "D", N70 TON	40701861 HMA PAVEMENT (FULL DEPTH), 9" SQ YD	40701861 HMA PAVEMENT 9 1/2" (JOINTED) SQ YD	42000501 PCC PAVEMENT 10" (JOINTED) SQ YD	42001300 PROTECTIVE COAT SQ YD	42001420 BRIDGE APPRCH PVMT CONNECTOR (PCC) SQ YD	42400200 PCC SIDEWALK 5" SQ FT	42400800 DETECTABLE WARNINGS SQ FT	44300200 STRIP REFLECTIVE CRACK CONTROL FOOT
US ROUTE 30										
262+99.42 TO 276+00	319	0	0	0	10,161	3,295	0	0	102	0
276+00 TO 289+00	243	0	0	0	4,587	2,687	800	0	0	0
289+00 TO 302+00	155	0	0	1,364	7,812	2,425	0	0	123	0
SAUK TRAIL										
380+00 TO 386+75	39	75	0	2,226	0	868	0	0	68	330
WEST FRONTAGE ROAD NORTH										
100+00 TO 113+75.52	0	0	4,237	0	0	41	0	5,931.4	0	0
WEST FRONTAGE ROAD SOUTH										
401+10 TO 409+70	0	0	3,294	0	0	45	0	3,420	0	0
TOTALS	757	75	8,304	3,590	22,560	10,847	800	9,352	293	330

PROPOSED PAVING SCHEDULE

LOCATION	48203021 HMA SHOULDERS 6" SQ YD	60603800 COMB CONC C&G TY B-6.12 FOOT	60605000 COMB CONC C&G TY B-6.24 FOOT	60605500 COMB CONC C&G B-6.24 (VAR WDH GTR FL) FOOT	60608600 COMB CONC C&G TY M-6.06 FOOT	60610400 COMB CONC C&G TY M-6.24 FOOT	60618320 CONCRETE MEDIAN SURF 6" SQ YD	60619600 CONCRETE MEDIAN TY SB-6.12 SQ FT	60620000 CONCRETE MEDIAN TY SB-6.24 SQ FT	60624600 CORRUGATED MEDIAN SQ FT	X6060200 CONCRETE MEDIAN TY SB-6.24 (MOD) SQ FT	X6060714 CONCRETE MEDIAN (SPECIAL) SQ YD	Z0073345 SLEEPER SLAB FOOT
US ROUTE 30													
262+99.42 TO 276+00	129	729	3,435	0	0	0	5,468	0	2,676	323	2,539	0	238
276+00 TO 289+00	70	0	2,022	0	0	0	5,303	2,553	1,496	0	1,377	0	0
289+00 TO 302+00	0	0	2,375	0	235	298	1,728	0	1,015	444	2,203	113	0
SAUK TRAIL													
380+00 TO 386+75	0	0	903	0	13	17	0	0	0	0	0	0	0
WEST FRONTAGE ROAD NORTH													
100+00 TO 113+75.52	0	2,235	91	421	0	0	0	0	0	0	0	0	0
WEST FRONTAGE ROAD SOUTH													
401+10 TO 409+70	0	1,574	42	351	0	0	0	0	0	0	0	0	0
TOTALS	199	4,538	8,868	772	248	315	12,499	2,554	5,188	768	6,120	113	238



USER NAME = dsherman
PLOT SCALE = 1'
PLOT DATE = 2/21/2014

DESIGNED - DSS
DRAWN - DRP
CHECKED - VJD
DATE - 02/21/2014

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. 3 OF 9 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	11-Y-A	COOK	354	30
CONTRACT NO. 60R19				
ILLINOIS FED. AID PROJECT				