

DRAINAGE AND UTILITY STRUCTURE SCHEDULE

LOCATION	54213657	54213660	54213669	54213675	60201105	60201310	60201340	60205040	60205310	60206600	60208210	60208240	60218400	60219300	60221100
	PRECAST RCP FES 12" EACH	PRECAST RCP FES 15" EACH	PRECAST RCP FES 24" EACH	PRECAST RCP FES 30" EACH	CATCH BASINS TYPE A, 4'-DIA TY 11 F&G EACH	CATCH BASINS TYPE A, 4'-DIA TY 20 F&G EACH	CATCH BASINS TYPE A, 4'-DIA TY 24 F&G EACH	CATCH BASINS TYPE A, 5'-DIA TY 24 F&G EACH	CATCH BASINS TYPE A, 6'-DIA TY 24 F&G EACH	CATCH BASINS TYPE B TY 7 GRATE EACH	CATCH BASINS TYPE C TY 20 F&G EACH	CATCH BASINS TYPE C TY 24 F&G EACH	MANHOLES TY A, 4'-DIA TY 1 F&CL EACH	MANHOLES TY A, 4'-DIA TY 1, F&G EACH	MANHOLES TY A, 5'-DIA TY 1, F&CL EACH
U. S. ROUTE 30															
260+00 TO 276+00	0	0	0	0	1	0	11	0	1	0	0	0	2	0	1
276+00 TO 289+00	2	1	1	0	0	3	1	0	0	0	4	0	5	0	3
289+00 TO 302+00	0	0	1	0	1	0	4	2	1	0	0	3	0	1	3
SAUK TRAIL															
380+00 TO 387+50	0	0	0	1	0	0	1	3	0	1	0	0	1	0	1
WEST FRONTAGE ROAD NORTH															
100+00 TO 113+75.52	0	0	0	0	0	0	2	3	0	1	0	5	1	0	2
WEST FRONTAGE ROAD SOUTH															
401+10 TO 409+70	0	0	2	0	0	0	7	1	0	3	0	0	0	0	7
TOTALS	2	1	4	1	2	3	26	9	2	5	4	8	9	1	17

DRAINAGE AND UTILITY STRUCTURE SCHEDULE

LOCATION	60223800	60224446	60224449	60224456	60224459	60224469	60224476	60236800	60237420	60237470	X6020096	
	MANHOLES TY A, 6'-DIA TY 1, F&CL EACH	MANHOLES TY A, 7'-DIA TY 1, F&CL EACH	MANHOLES TY A, 7'-DIA TY 24, F&G EACH	MANHOLES TY A, 8'-DIA TY 24, F&G EACH	MANHOLES TY A, 8'-DIA TY 1, F&CL EACH	MANHOLES TY A, 9'-DIA TY 1, F&CL EACH	MANHOLES TY A, 9'-DIA TY 24, F&G EACH	INLETS TYPE A TY 11, F&G EACH	INLETS TYPE A TY 20, F&G EACH	INLETS TYPE A TY 24, F&G EACH	MANHOLES, TYPE A 6' DIA, W/2 TY 1 F&CL RESTRICTOR PLATE EACH	MANHOLES, TYPE A 8' DIA, W/2 TY 1 F&CL RESTRICTOR PLATE EACH
US ROUTE 30												
260+00 TO 276+00	1	3	0	0	2	1	2	3	0	7	0	1
276+00 TO 289+00	0	0	0	0	0	0	0	0	1	3	2	0
289+00 TO 302+00	1	1	0	0	0	0	0	0	0	8	0	0
SAUK TRAIL												
380+00 TO 387+50	0	0	0	1	0	0	0	0	0	6	0	0
WEST FRONTAGE ROAD NORTH												
100+00 TO 113+75.52	1	0	1	1	3	1	0	0	0	8	0	0
WEST FRONTAGE ROAD SOUTH												
401+10 TO 409+70	1	2	0	0	1	0	0	1	0	8	1	0
TOTALS	4	6	1	2	6	2	2	4	1	40	3	1

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC			PREFORMED PLASTIC			POLYUREA						78100100 RAISED REF PVT MKR EACH	78100105 RAISED REF PVT MKR (BR) EACH		
	78000200	78000400	78000500	78004100	78004110	78004130	78008200	78008210	78008230	78008240	78008250	78008270				
	LINE 4" FOOT	LINE 6" FOOT	LINE 8" FOOT	TY C LTR & SYM SQ FT	TY C-LINE 4" FOOT	TY C-LINE 6" FOOT	TY 1 LTR & SYM SQ FT	TY 1-LINE 4" FOOT	TY 1-LINE 6" FOOT	TY 1-LINE 8" FOOT	TY 1-LINE 12" FOOT	TY 1-LINE 24" FOOT				
US ROUTE 30																
259+00 TO 269+00			242	0	0	0	19	4,215	684	0	6,176	60	83	0		
269+00 TO 280+50			0	0	0	0	0	5,145	115	0	0	0	63	0		
280+50 TO 289+25			0	0	0	0	30	3,866	239	0	0	0	43	10		
289+25 TO 301+00			0	0	0	74	730	228	113	2,329	1,240	254	669	91	76	0
SAUK TRAIL																
378+50 TO 387+00			463	38	31	0	0	0	86	830	304	710	949	31	51	0
TOTALS	705	38	31	74	730	228	248	16,386	2,583	965	7,794	182	316	10		



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = hshsh
DESIGNED - DSS
DRAWN - DRP
CHECKED - VJD
DATE - 08/14/2013
REVISOR -
REVISOR -
REVISOR -
REVISOR -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES
SCALE: N/A SHEET NO. 5 OF 9 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	11-Y-A	COOK	354	32
CONTRACT NO. 60R19				
ILLINOIS FED. AID PROJECT				