


MAINTENANCE OF TRAFFIC / EROSION CONTROL SCHEDULE

		70301000	78300100	28000250	28000400	28000500	28000510	28001100	X6028050
	LOCATION	WORK ZONE PVMT MRK REM	PVMT MRK REMOVAL	TEMP EROS CTRL SEED	PERIMETER EROS BAR	INLET & PIPE PROTECTION	INLET FILTERS	TEMP EROS CTRL BLKT	TEMP MANHOLE
		SQ FT	SQ FT	POUND	FOOT	EACH	EACH	SQ YD	EACH
PRE-STAGE	US ROUTE 30								
	257+00 TO 269+00	0	1,918	167	3,219	2	29	5,048	1
	269+00 TO 280+50	0	1,918	0	2,421	5	28	2,406	0
	280+50 TO 289+25	0	1,828	0	0	3	14	0	0
	289+25 TO 301+00	0	1,828	0	2,088	6	33	1,417	0
	SAUK TRAIL								
	378+50 TO 387+00	0	0	0	2,022	1	2	74	0
STAGES 1 & 2	US ROUTE 30								
	257+00 TO 269+00	5,744	0	0	786	0	3	11,906	0
	269+00 TO 280+50	5,278	0	992	4,089	1	13	12,01	0
	280+50 TO 289+25	4,087	0	91	2,928	3	7	7,550	0
	289+25 TO 301+00	7,665	0	39	2,316	0	12	3,215	0
	SAUK TRAIL								
	378+50 TO 387+00	0	0	0	0	0	0	0	0
STAGE 3	US ROUTE 30								
	257+00 TO 269+00	4,260	0	67	0	0	2	2,226	0
	269+00 TO 280+50	7,949	0	6	0	0	1	141	0
	280+50 TO 289+25	4,342	0	0	0	0	0	0	0
	289+25 TO 301+00	6,424	0	136	0	1	1	3,291	0
	SAUK TRAIL								
	378+50 TO 387+00	1,482	1,113	21	0	0	0	145	0
STAGE 4a	US ROUTE 30								
	257+00 TO 269+00	1,219	0	0	0	0	3	1,300	0
	269+00 TO 280+50	1,193	0	0	244	1	14	6,195	0
	280+50 TO 289+25	584	0	189	874	2	16	8,567	0
	289+25 TO 301+00	2,753	0	0	0	0	0	0	0
	SAUK TRAIL								
	378+50 TO 387+00	2,655	0	69	363	0	11	3,736	0
STAGE 4b	US ROUTE 30								
	257+00 TO 269+00	304	0	0	0	0	0	0	0
	269+00 TO 280+50	0	0	0	0	0	0	0	0
	280+50 TO 289+25	0	0	0	0	4	0	0	0
	289+25 TO 301+00	773	0	0	0	0	0	580	0
	SAUK TRAIL								
	378+50 TO 387+00	1,713	0	0	0	1	0	0	0
	TOTAL	58,427	8,605	1,775	21,791	30	189	69,800	1



USER NAME = hshh	DESIGNED - DSS	REVISED -
	DRAWN - DRP	REVISED -
PLOT SCALE = 1:8000' / 1"	CHECKED - VJD	REVISED -
PLOT DATE = 8/21/2013	DATE - 08/14/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. 7 OF 9 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	11-Y-A	COOK	354	34
CONTRACT NO. 60R19				
ILLINOIS FED. AID PROJECT				