


ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	78.5% CN / 21.5% STATE						80% STATE	80% STATE
				ROADWAY	CN RR BRIDGE	3-SIDED CULVERT	TRAFFIC SIGNALS	RETAINING WALLS	BIKEPATH	SIDEWALK	
				0003	0008	0008	0021	0040	0028	0021	
			<i>URBAN</i>								
25100630	EROSION CONTROL BLANKET	SQ YD	36,155	36,155							
25200110	SODDING, SALT TOLERANT	SQ YD	8,830	8,830							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,775	1,775							
28000400	PERIMETER EROSION BARRIER	FOOT	21,791	21,791							
28000500	INLET AND PIPE PROTECTION	EACH	30	30							
28000510	INLET FILTERS	EACH	189	189							
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	45,287	45,287							
28100105	STONE RIPRAP, CLASS A3	SQ YD	6	6							
28200200	FILTER FABRIC	SQ YD	6	6							
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	8949	786				8183			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	43,928	43,928							
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SO YD	3,723						3,723		
31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SO YD	1,451	1,451							
35101598	AGGREGATE BASE COURSE, TYPE B 3"	SO YD	991							991	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SO YD	7,904	7,904							
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	249	249							
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	60	60							
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	1,445	1,445							
<del>40600100</del>	<del>BITUMINOUS MATERIALS (PRIME COAT)</del>	<del>GALLON</del>	<del>7,212</del>	<del>5,393</del>					<del>1,819</del>		
<del>40600300</del>	<del>AGGREGATE (PRIME COAT)</del>	<del>TON</del>	<del>10</del>	<del>9</del>					<del>7</del>		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							

19  
• SPECIALTY ITEM

 V3 Companies 7325 Janes Avenue Woodridge, IL 60517 630.724.9200 phone 630.724.9202 fax www.v3co.com	USER NAME * hahoh	DESIGNED - DSS	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b> SCALE: N/A    SHEET NO. 2 OF 15 SHEETS			F.A.P. RTE. 353	SECTION 11-Y-A	COUNTY COOK	TOTAL SHEETS 354	SHEET NO. 5
	PLOT SCALE = 1/8" = 1'	CHECKED - VJD	REVISED -					CONTRACT NO. 60R19				
	PLOT DATE = 8/21/2013	DATE - 08/14/2013	REVISED -					ILLINOIS FED. AID PROJECT				
	<i>Rev.</i>											