


ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	78.5% CN / 21.5% STATE						80% STATE	80% STATE
				ROADWAY	CN RR BRIDGE	3-SIDED CULVERT	TRAFFIC SIGNALS		RETAINING WALLS	BIKEPATH	SIDEWALK
				0003	0008	0008	0021		0040	0020	0021
	<i>URBAN</i>										
• 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3,284				3,284				
• 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2,619				2,619				
• 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	335				335				
• 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,102				1,012				
• 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	1				1				
• 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	5				5				
• 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 18 FT.	EACH	1				1				
• 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1				1				
• 87702310	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 24 FT. AND 36 FT.	EACH	1				1				
• 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	28				28				
• 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4				4				
• 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	27				27				
• 88030012	SIGNAL HEAD, LED, 1-FACE, 1-SECTION, BRACKET MOUNTED	EACH	1				1				
• 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7				7				
• 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3				3				
• 88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2				2				
• 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4				4				
• 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	7				7				
• 88500100	INDUCTIVE LOOP DETECTOR	EACH	8				8				
• 88600700	PREFORMED DETECTOR LOOP	FOOT	430				430				
• 88700200	LIGHT DETECTOR	EACH	3				3				

• SPECIALTY ITEM 100% COST PAID BY THE VILLAGE OF LYNWOOD

 V3 Companies 7326 Janex Avenue Woodridge, IL 60517 630.724.9200 phone 630.724.9202 fax www.v3co.com	USER NAME : hahah	DESIGNED - DSS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 353	SECTION 11-Y-A	COUNTY COOK	TOTAL SHEETS 354	SHEET NO. 14	
	PLOT SCALE : 1/8" = 1'	CHECKED - VJD	REVISED -					SCALE: N/A SHEET NO. 11 OF 15 SHEETS				CONTRACT NO. 60R19	
	PLOT DATE : 8/21/2013	DATE - 08/14/2013	REVISED -					ILLINOIS FED. AID PROJECT					