

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				ROADWAY	BRIDGE	HIGHWAY LIGHTING
				0004 URBAN	0011 S. N. 016-1711	0021 URBAN
* X0370017	DRILL MANHOLE OR HANDHOLE CHICAGO	EACH	13			13
* X0370047	INSTALL LIGHT POLE, MAST ARM AND LUMINAIRE (CHICAGO)	EACH	6			6
* X0370049	UNDERGROUND CONDUIT, PVC, 2" DIA., SCHEDULE 80 (CDOT)	FOOT	165			165
* X0370068	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE (CDOT)	EACH	2			2
X0370069	COMBINED SEWER (EXTRA STRENGTH VITRIFIED CLAY PIPE) 8 INCH (CDOT)	FOOT	56	56		
<input checked="" type="checkbox"/> X0370070	COMBINED SEWER (WATER MAIN REQUIREMENTS), 8 INCH (CDOT)	FOOT	20	20		
X0370071	COMBINED SEWER, (WATER MAIN REQUIREMENTS), 12 INCH CDOT	FOOT	38	38		
* X0370074	RACKING CABLES IN MANHOLE OR HANDHOLE (CDOT)	EACH	3			3
* X0370075	UNDERGROUND CONDUIT, PVC, 4" DIA., SCHEDULE 80 (CDOT)	FOOT	930			930
<input type="checkbox"/> X0370076	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM (CDOT)	FOOT	125			125
X0370080	COMBINATION CURB AND GUTTER TYPE B V. 12 (CDOT)	FOOT	308.5	308.5		
X0370081	SAND CUSHION, 4 INCH, (CDOT)	50 FT	1819	1819		
<input type="checkbox"/> * X0370085	CLEAN MANHOLE OR HANDHOLE (CDOT)	EACH	3			3
X0370135	CONCRETE CURB, TYPE B (SPECIAL) (CDOT)	FOOT	235	235		
X0370164	MANHOLES TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1		
X0370168	COMBINED SEWER, CLASS A, TYPE 3, 60" (CDWM)	FOOT	16	16		

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

NP - 100% CDOT

Rev. 4-10-14

Rev.



DIGB071-sh1-500.dgn
 USER NAME: pmsarna
 PLOT SCALE: 2.0000 / 1"
 PLOT DATE: 12/23/2013

DESIGNED - OPS
 DRAWN - OPS
 CHECKED - DBM
 DATE - 12/06/13

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 13 OF 14 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	18

CONTRACT NO. 60W71
 ILLINOIS FED. AID PROJECT

FILE PATH: I:\13-123-VPRX\016071-sh1-500.dgn