

**REMOVAL SCHEDULE**

LOCATION	STATION	TO	STATION	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER)	TREE REMOVAL ( OVER 15 UNITS DIAMETER)	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4'	DRIVEWAY PAVEMENT REMOVAL	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	CONCRETE BARRIER REMOVAL	REMOVE EXISTING FLAGPOLE	APPROACH SLAB REMOVAL	FENCE REMOVAL	REMOVE GATE POSTS
				UNIT	UNIT	SO YD	SO YD	SO YD	FOOT	FOOT	SO FT	FOOT	EACH	SO YD	FOOT	EACH
HARRISON STREET				76	16	383	219	453	170	420	2392	-	1	527	116	2
I-90/94 NORTHBOUND				14	-	-	-	-	-	-	-	118	-	-	29	-
ROUNDED TOTAL				90	16	383	219	453	170	420	2392	118	1	527	145	2

FILE PATH = p:\388035\pmt\escomon\local\p\AECOM\0\Documents\01\_Americas\Transportation\6269938\_Circle\Phase\_1\000\_CAD\005\_Roadway\_Sheets\60W71\_Contract\0160W71-sht-Schedule-01.dgn



D160W71-sht-Schedule-01.dgn	DESIGNED - OPS	REVISED -
USER NAME = pimsarno	DRAWN - OPS	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED - DBM	REVISED -
PLOT DATE = 2/20/2014	DATE - 02/19/14	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET 1 OF 3 SHEETS	STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-036R	COOK	256	21
CONTRACT NO. 60W71				
ILLINOIS FED. AID PROJECT				