

EARTHWORK SCHEDULE - US RTE. 6 (159TH STREET)

| STATION | STATION | EARTH EXCAVATION (20200100) | EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE | EMBANKMENT | EARTHWORK BALANCE (+/-) (+)=WASTE (-)=SHORTAGE |
|---------------|-----------|-----------------------------|--|------------|--|
| | | CU YD | CU YD | CU YD | CU YD |
| 253+43.18 | 253+65.61 | 4 | 3 | 0 | 3 |
| 253+65.61 | 0+00.00 | 0 | 0 | 0 | 0 |
| 253+65.61 | 253+88.20 | 6 | 5 | 0 | 5 |
| 253+88.20 | 0+00.00 | 0 | 0 | 0 | 0 |
| 254+00.00 | 254+87.40 | 11 | 9 | 0 | 9 |
| 254+87.40 | 255+00.00 | 4 | 3 | 0 | 3 |
| 255+00.00 | 255+26.22 | 7 | 6 | 0 | 6 |
| 255+26.22 | 255+43.30 | 4 | 3 | 0 | 3 |
| 255+43.30 | 0+00.00 | 0 | 0 | 0 | 0 |
| 256+00.00 | 257+00.00 | 0 | 0 | 0 | 0 |
| 257+00.00 | 258+00.00 | 0 | 0 | 0 | 0 |
| 258+00.00 | 259+00.00 | 0 | 0 | 0 | 0 |
| US RT 6 TOTAL | | 36 | 29 | 0 | 29 |

NOTE: 15% SHRINKAGE FACTOR

EARTHWORK SCHEDULE - IL RTE. 83 (TORRENCE AVENUE)

| STATION | STATION | EARTH EXCAVATION (20200100) | EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE | EMBANKMENT | EARTHWORK BALANCE (+/-) (+)=WASTE (-)=SHORTAGE |
|----------------|----------|-----------------------------|--|------------|--|
| | | CU YD | CU YD | CU YD | CU YD |
| 8+96.77 | 9+00.00 | 1 | 1 | 0 | 1 |
| 9+00.00 | 9+18.00 | 3 | 3 | 0 | 3 |
| 9+18.00 | 0+00.00 | 0 | 0 | 0 | 0 |
| 9+18.00 | 9+50.54 | 7 | 6 | 0 | 6 |
| 9+50.54 | 0+00.00 | 0 | 0 | 0 | 0 |
| 10+00.00 | 10+50.26 | 4 | 3 | 0 | 3 |
| 10+50.26 | 10+74.40 | 4 | 3 | 0 | 3 |
| 10+74.40 | 0+00.00 | 0 | 0 | 0 | 0 |
| 10+74.40 | 11+00.00 | 7 | 6 | 0 | 6 |
| 11+00.00 | 12+00.00 | 29 | 25 | 0 | 25 |
| 12+00.00 | 13+00.00 | 29 | 25 | 0 | 25 |
| 13+00.00 | 14+00.00 | 29 | 25 | 0 | 25 |
| 14+00.00 | 14+75.26 | 22 | 19 | 0 | 19 |
| 14+75.26 | 15+00.00 | 6 | 5 | 0 | 5 |
| 15+00.00 | 16+00.00 | 15 | 13 | 0 | 13 |
| IL RT 83 TOTAL | | 156 | 134 | 0 | 134 |

NOTE: 15% SHRINKAGE FACTOR

EARTHWORK SUMMARY TABLE

| DESCRIPTION | QUANTITY | UNIT |
|----------------------|----------|-------|
| EARTH EXCAVATION | 192 | CU YD |
| FURNISHED EXCAVATION | 0 | CU YD |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

- EXTRA EXCAVATION TO BE PLACED ON SITE.

FILE NAME = \$FILEL\$