



LEGEND

- ↑ ARROW BOARD
- ▨ WORK AREA
- † SIGN
- TYPE II BARRICADE OR
- ⊞ TYPE III BARRICADE

- ① TEMPORARY PAVEMENT MARKING - LINE 24" (WHITE)
- ② TEMPORARY PAVEMENT MARKING - LINE 6" (WHITE)
- ③ TEMPORARY PAVEMENT MARKING - LINE 6" (2' LINE W/ 6' SPACE) (WHITE)
- ④ TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS
- ⑤ TEMPORARY PAVEMENT MARKING - LINE 4" (YELLOW)
- ⑥ TEMPORARY PAVEMENT MARKING - LINE 4" (10' LINE W/30' SPACE) (WHITE)

STAGE I

NOTES

1. PRIOR TO INSTALLING POST MOUNTED SIGNS, THE CONTRACTOR SHALL CONTACT J.U.L.I.E. AND MAKE ELECTRIC FOR LOCATES.
2. SEE STANDARD 701701 FOR ADDITIONAL INFORMATION.
3. SIGNS INCLUDED IN THE COST TRAFFIC CONTROL.

FILE NAME = \$FILEL\$

USER NAME = \$USER\$	DESIGNED - BFH	REVISED -
	DRAWN - BFH	REVISED -
PLOT SCALE = \$SCALE\$	CHECKED - BA	REVISED -
PLOT DATE = \$DATE\$	DATE - 1/31/14	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUGGESTED MAINTENANCE OF TRAFFIC - STAGE I
US RTE. 6 (159TH STREET) AND IL RTE. 83 (TORRENCE AVENUE)**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
351	539N-1	COOK	49	18
CONTRACT NO. 60W90				

SCALE: 1"=50' SHEET OF SHEETS STA. TO STA. 1 2 ILLINOIS FED. AID PROJECT