SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0044					
20200100	EARTH EXCAVATION	CU YD	205	205					
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	8	8					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1					
25200110	SODDING, SALT TOLERANT	SQ YD	75	75					
25200200	SUPPLEMENTAL WATERING	UNIT	1	1					
28000400	PERIMETER EROSION BARRIER	FOOT	248	248					
28100107	STONE RIPRAP, CLASS A4	SQ YD	65	65					
28200200	FILTER FABRIC	SQ YD	65	65					
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	30	30					
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	105	105					
55100500	STORM SEWER REMOVAL 12"	FOOT	105	105					
55101200	STORM SEWER REMOVAL 24"	FOOT	105	105					
55101300	STORM SEWER REMOVAL 27"	FOOT	30	30					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0044					
60224075	MANHOLES, TYPE A, 6'-DIAMETER	EACH	2	2					
60500040	REMOVING MANHOLES	EACH	2	2					
66400305	CHAIN LINK FENCE, 6'	FOOT	75	75					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	75	75					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					

FILE NAME =	USER NAME = dbeaver	DESIGNED -	REVISED -
c:\pw_work\pwidot\dbeaver\d0351874\D140715-sht-plan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/10/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1300	1922-T	COOK	9	3
		CONTRACT NO. 60W95		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		