

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0014				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0014				
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	0014				CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	0014				
50102400	CONCRETE REMOVAL	CU YD	58.2	58.2												
50300255	CONCRETE SUPERSTRUCTURE	CU YD	64.1	64.1												
50300300	PROTECTIVE COAT	SQ YD	247	247				* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	36.4	36.4				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16320	16320				* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3700	3700				
50800515	BAR SPLICERS	EACH	56	56				* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	75	75				
50900105	ALUMINUM RAILING, TYPE L	FOOT	40	40				* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	370	370				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	160	160				* 78100300	REPLACEMENT REFLECTOR	EACH	33	33				
59000200	EPOXY CRACK INJECTION	FOOT	10	10				* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	8	8				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				78300100	PAVEMENT MARKING REMOVAL	SQ FT	1700	1700				
67100100	MOBILIZATION	L SUM	1	1				X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3				X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	136.7	136.7				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2375	2375				X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	6100	6100				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	475	475				X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	405	405				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350	350				Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	36	36				
70600240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	8	8				Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	615	615				

*Specialty Item

FILE NAME :	USER NAME : Gorngau00	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0:\pwwork\1\p1\del\qorngau00\360667.DWG.dwg	DRAWN -	REVISED -	333					14X-1-3(13)	MCHENRY	29	3	
PLOT SCALE : 1000000' / 1"	CHECKED -	REVISED -	CONTRACT NO. 60X22									
PLOT DATE : 2/19/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									
				SCALE:		SHEET NO. OF SHEETS STA. TO STA.						