



INTERCONNECT SCHEDULE OF QUANTITIES

PAY ITEM	UNIT	QNTY.
ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
MOBILIZATION	L SUM	0.333
TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	0.333
TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	0.333
TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	0.333
CHANGEABLE MESSAGE SIGN	CAL MO	0.667
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1807
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5086
DRILL EXISTING HANDHOLE	EACH	4
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3637
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	5178
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1

ECON 106



USER NAME = jrt	DESIGNED - BRD	REVISED -
PLOT SCALE = 40.0000' / in.	DRAWN - MFB	REVISED -
PLOT DATE = 1/30/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

<b>INTERCONNECT SCHEMATIC</b>	
<b>IL ROUTE 59</b>	
NO SCALE	SHEET NO. 1 OF 1 SHEETS
STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	2013-062TS	DUPAGE	49	33
<b>CONTRACT NO. 60X34</b>				
<small>ILLINOIS FED. AID PROJECT</small>				