

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HSIP FUNDS			
				90% FEDERAL 10% STATE	100% CITY OF NAPERVILLE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				0021			
			TRAFFIC SIGNALS		LIGHTING		
			U.S. ROUTE 34/ IL ROUTE 59	EM. VEHICLE PREEMPTION	INTERCONNECT	U.S. ROUTE 34/ IL ROUTE 59	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2591	1409	1182		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4404	4404			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2557	2557			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	10047	10047			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	582	582			
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	2233	2233			
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2	2			
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	3	3			
87700150	STEEL MAST ARM ASSEMBLY AND POLE 22 FT.	EACH	1	1			
87700340	STEEL MAST ARM ASSEMBLY AND POLE 58 FT.	EACH	1	1			
87702830	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 20 FT.	EACH	1	1			
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1	1			

URBAN



USER NAME = jrs	DESIGNED - BRD	REVISED -
PLOT SCALE = 1/8" = 1'-0"	DRAWN - MFB	REVISED -
PLOT DATE = 1/30/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

NO SCALE SHEET NO. 5 OF 9 SHEETS STA. TO STA.

F.A.P. RTE. 331	SECTION 2013-062TS	COUNTY	TOTAL SHEETS 49	SHEET NO. 7
CONTRACT NO. 60X34			ILLINOIS FED. AID PROJECT	