

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				HSIP FUNDS			
				90% FEDERAL 10% STATE	100% CITY OF NAPERVILLE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				0021			
			TRAFFIC SIGNALS		LIGHTING		
			U.S. ROUTE 34/ IL ROUTE 59	EM. VEHICLE PREEMPTION	INTERCONNECT	U.S. ROUTE 34/ IL ROUTE 59	
89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	4	4			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9	9			
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	1182		1182		
X0326148	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	5				5
X0327349	TEMPORARY WOOD POLE, 40 FT., CLASS 4	EACH	3				3
X8210040	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	8				8
X8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	12				12
X8410103	REMOVE TEMPORARY LIGHTING SYSTEM	L SUM	1				1
** X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1	1			
X8600105	MASTER CONTROLLER (SPECIAL)	EACH	1	1			
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1	1			
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	5178			5178	

URBAN

** SUPER "R" CABINET



USER NAME = JJE	DESIGNED - BRD	REVISED -
PLOT SCALE = 48.0000' / 1" =	DRAWN - MFB	REVISED -
PLOT DATE = 1/30/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

NO SCALE SHEET NO. 8 OF 9 SHEETS STA. TO STA.

F.A.P. RTE. 311	SECTION 2013-062TS	COUNTY	TOTAL SHEETS 49	SHEET NO. 10
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60X34	