

CONSTRUCTION CODE

HSIP FUNDS

90% FEDERAL 5% STATE 5% ADDISON TWP	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% WOOD DALE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% CENTERPOINT	100% BENSENVILLE	90% FEDERAL 10% STATE
MS30L,01	MS30L,02	MS30L,01 ⁰³	MS30L,01 ⁰³	MS30L,03 ⁰⁴	07POL,01	MS30L,04 ⁰⁵

URBAN

0021

TRAFFIC SIGNALS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS						
				IL ROUTE 83 AT THIRD AVENUE/OAK MEADOWS DRIVE	IL ROUTE 83 AT GROVE AVENUE/SHERWOOD DRIVE	IL ROUTE 83 AT HILLSIDE DRIVE	IL ROUTE 83 AT FOSTER AVENUE	IL ROUTE 83 AT MARK STREET	EM. VEHICLE PREEMPTION	INTERCONNECT
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	97	28	21	22	7	19		
42001300	PROTECTIVE COAT	SO YD	107	28	24	22	9	24		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SO FT	847	238	189	195	61	164		
42400800	DETECTABLE WARNINGS	SO FT	125	27	34	27	12	25		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	48		13		10	25		
44000600	SIDEWALK REMOVAL	SO FT	259		76		36	147		
44003100	MEDIAN REMOVAL	SO FT	32	32						
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	52	16	11	13	6	6		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	48		13		10	25		
60624600	CORRUGATED MEDIAN	SO FT	10	10						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	1.5	1.5	1.5	1.5	1.5		1.5



USER NAME = jrt	DESIGNED - BRD	REVISED -
PLOT SCALE = 1/8" = 10'-0"	DRAWN - JRT	REVISED -
PLOT DATE = 1/30/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL SUMMARY OF QUANTITIES			
IL ROUTE 83			
THIRD AVENUE /OAK MEADOWS DRIVE TO MARK STREET			
NO SCALE	SHEET NO. 1 OF 10 SHEETS	STA.	TO STA.

F.A.P. RTE. 344	SECTION 2013-063TS	COUNTY DUPAGE	TOTAL SHEETS 68	SHEET NO. 3
ILLINOIS FED. AID PROJECT				

CONTRACT NO. 60X35