

CONSTRUCTION CODE

HSIP FUNDS

90% FEDERAL 5% STATE 5% ADDISON TWP	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% WOOD DALE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% CENTERPOINT	100% BENSENVILLE	90% FEDERAL 10% STATE
---	---	---	---	---	---------------------	--------------------------

URBAN

0021

TRAFFIC SIGNALS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS						
				IL ROUTE 83 AT THIRD AVENUE/ OAK MEADOWS DRIVE	IL ROUTE 83 AT GROVE AVENUE/ SHERWOOD DRIVE	IL ROUTE 83 AT HILLSIDE DRIVE	IL ROUTE 83 AT FOSTER AVENUE	IL ROUTE 83 AT MARK STREET	EM. VEHICLE PREEMPTION	INTERCONNECT
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	41					41		
78300100	PAVEMENT MARKING REMOVAL	SO FT	119		13	16	2	88		
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	5	1	1	1	1	1		
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	5218	737	629	536	771	536		2009
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	72	29	5	15	18	5		
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	565	129	100	121	119	96		
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	2595	500	476	511	543	565		
81400100	HANDHOLE	EACH	6	1	1		2	2		
81400200	HEAVY-DUTY HANDHOLE	EACH	22	5	4	5	6	2		
81400300	DOUBLE HANDHOLE	EACH	10	2	2	2	2	2		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3				1			2

* SPECIALTY ITEMS



USER NAME = jrs	DESIGNED - BRD	REVISED -
PLOT SCALE = 48,000 / 1"	DRAWN - JRT	REVISED -
PLOT DATE = 1/30/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL SUMMARY OF QUANTITIES

IL ROUTE 83
THIRD AVENUE /OAK MEADOWS DRIVE TO MARK STREET

NO SCALE SHEET NO. 3 OF 10 SHEETS STA. TO STA.

F.A.P. RTE. 344	SECTION 2013-063TS	COUNTY	TOTAL SHEETS 68	SHEET NO. 5
CONTRACT NO. 60X35			ILLINOIS FED. AID PROJECT	