

				CONSTRUCTION CODE						
				HSIP FUNDS						
				90% FEDERAL 5% STATE 5% ADDISON TWP	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% WOOD DALE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% CENTERPOINT	100% BENSENVILLE	90% FEDERAL 10% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0021						
				TRAFFIC SIGNALS						
				IL ROUTE 83 AT THIRD AVENUE/ OAK MEADOWS DRIVE	IL ROUTE 83 AT GROVE AVENUE/ SHERWOOD DRIVE	IL ROUTE 83 AT HILLSIDE DRIVE	IL ROUTE 83 AT FOSTER AVENUE	IL ROUTE 83 AT MARK STREET	EM. VEHICLE PREEMPTION	INTERCONNECT
86400100	TRANSCEIVER - FIBER OPTIC	EACH	5	1	1	1	1	1		
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	19423							19423
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2397	242	234	447	998	476		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	5636	256	251	461	1026	490	3152	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	18967	2764	3899	4341	3377	4586		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2771	1374	219		1178			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	10722	3926	1784	1499	1999	1514		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	321	146	46	29	46	54		
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	4244	928	760	828	878	850		
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1				1			
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2				2			

URBAN



USER NAME = jrt	DESIGNED - BRD	REVISED -
PLOT SCALE = 40,000.00' / in.	DRAWN - JRT	REVISED -
PLOT DATE = 1/30/2014	CHECKED - JJE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL SUMMARY OF QUANTITIES  
IL ROUTE 83  
THIRD AVENUE /OAK MEADOWS DRIVE TO MARK STREET

NO SCALE SHEET NO. 4 OF 10 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	2013-063TS	DUPAGE	68	6
CONTRACT NO. 60X35				
ILLINOIS FED. AID PROJECT				