

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				HSIP FUNDS						
				90% FEDERAL 5% STATE 5% ADDISON TWP	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% WOOD DALE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 5% BENSENVILLE	90% FEDERAL 5% STATE 2.5% BENSENVILLE 2.5% CENTERPOINT	100% BENSENVILLE	90% FEDERAL 10% STATE
				0021						
TRAFFIC SIGNALS							EM. VEHICLE PREEMPTION	INTERCONNECT		
IL ROUTE 83 AT THIRD AVENUE/ OAK MEADOWS DRIVE	IL ROUTE 83 AT GROVE AVENUE/ SHERWOOD DRIVE	IL ROUTE 83 AT HILLSIDE DRIVE	IL ROUTE 83 AT FOSTER AVENUE	IL ROUTE 83 AT MARK STREET						
87700310	STEEL MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1			1				
87700320	STEEL MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1				1			
87700330	STEEL MAST ARM ASSEMBLY AND POLE 56 FT.	EACH	1			1				
87700400	STEEL MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	1					1		
87700404	STEEL MAST ARM ASSEMBLY AND POLE 62 FT.	EACH	1		1					
87700418	STEEL MAST ARM ASSEMBLY AND POLE 68 FT.	EACH	1				1			
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	36	8	4	8	12	4		
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	20	4	4	4	4	4		
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	209	44	51	47	47	20		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	116	30	15	15	15	41		
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	88		21	21	25	21		

URBAN



USER NAME - jrt	DESIGNED - BRD	REVISED -
PLOT SCALE = 40,0000' / in.	DRAWN - JRT	REVISED -
PLOT DATE = 1/30/2014	CHECKED - JUE	REVISED -
	DATE - 01/30/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL SUMMARY OF QUANTITIES	
IL ROUTE 83	
THIRD AVENUE /OAK MEADOWS DRIVE TO MARK STREET	
NO SCALE	SHEET NO. 6 OF 10 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	2013-063TS	DUPAGE	68	8
CONTRACT NO. 60X35				
ILLINOIS FED. AID PROJECT				