



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2014

SUBJECT: FAI Route 80 (I-80)
Project ACHSIP-0080(403)
Section 2013-0711
Will County
Contract No. 60X48
Item No. 13, April 25, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised the Table of Contents to the Special Provision
3. Added page 38 to the Special Provision
4. Revised Sheet 3 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1;, Tim Kell; Estimates

MS/kp

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60X48

State Job # - C-91-113-14

County Name - WILL - -

Code - 197 - -

District - 1 - -

Section Number - 2013-0711

Project Number

ACHSIP-0080/403/

*REVISED: APRIL 11, 2014

Route

FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD X7010410	SPEED DISPLAY TRAILER	CAL MO	2.000				
X7011015	TR C-PROT EXPRESSWAYS	L SUM	1.000				
21101615	TOPSOIL F & P 4	SQ YD	1,011.000				
25000210	SEEDING CL 2A	ACRE	0.210				
25000400	NITROGEN FERT NUTR	POUND	19.000				
25000500	PHOSPHORUS FERT NUTR	POUND	19.000				
25000600	POTASSIUM FERT NUTR	POUND	19.000				
25100630	EROSION CONTR BLANKET	SQ YD	1,011.000				
28000400	PERIMETER EROS BAR	FOOT	1,845.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	1,737.500				
63100045	TRAF BAR TERM T2	EACH	6.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	5.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	9.000				
63200310	GUARDRAIL REMOV	FOOT	487.500				
63500105	DELINEATORS	EACH	50.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60X48

State Job # - C-91-113-14

County Name - WILL - -

Code - 197 - -

District - 1 - -

Section Number - 2013-0711

Project Number

ACHSIP-0080/403/

*REVISED: APRIL 11, 2014

Route

FAI 80

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63500310	REM & REIN DELINEATOR	EACH	180.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
78200410	GUARDRAIL MKR TYPE A	EACH	45.000				
78201000	TERMINAL MARKER - DA	EACH	14.000				

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS	2
STATUS OF UTILITIES TO BE ADJUSTED.....	2
PUBLIC CONVENIENCE AND SAFETY (DIST 1)	3
TRAFFIC CONTROL PLAN	3
NIGHTTIME WORK ZONE LIGHTING (DISTRICT ONE).....	4
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC.....	6
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC.....	8
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS).....	8
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	12
CONTRACT CLAIMS (BDE)	14
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	15
PAYROLLS AND PAYROLL RECORDS (BDE).....	25
PROGRESS PAYMENTS (BDE).....	27
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	28
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)	32
TRACKING THE USE OF PESTICIDES (BDE)	33
TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/EXPRESSWAY (BDE)	33
WEEKLY DBE TRUCKING REPORTS (BDE)	33
WORKING DAYS (BDE)	34
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	34
SPEED DISPLAY TRAILER (BDE)	38

Revised 04/14/2014

SPEED DISPLAY TRAILER (BDE)

Effective: April 2, 2014

Add the following to Article 701.15(l) of the Standard Specifications:

“(l) Speed Display Trailer. A speed display trailer shall be utilized on freeways and expressways as part of Highway Standard 701400. The trailer shall be placed on the right hand side of the roadway adjacent to, or within 100 ft (30 m) beyond, the first work zone speed limit sign.

Whenever the speed display trailer is not in use, it shall be considered non-operating equipment and shall be stored according to Article 701.11.”

Add the following to Article 701.20 of the Standard Specifications:

“(k) Speed Display Trailer will be paid for at the contract unit price per calendar month or fraction thereof for each trailer as SPEED DISPLAY TRAILER.”

Add the following to Article 1106.02 of the Standard Specifications:

“(o) Speed Display Trailer. The speed display trailer shall consist of a LED speed indicator display with self-contained, one-direction radar mounted on an orange see-through trailer. The height of the display and radar shall be such that it will function and be visible when located behind concrete barrier.

The speed measurement shall be by radar and provide a minimum detection distance of 1000 ft (300 m). The radar shall have an accuracy of ± 1 mile per hour.

The speed indicator display shall face approaching traffic and shall have a sign legend of “YOUR SPEED” immediately above or below the speed display. The digital speed display shall show two digits (00 to 99) in mph. The color of the changeable message legend shall be a yellow legend on a black background. The minimum height of the numerals shall be 18 in. (450 mm), and the nominal legibility distance shall be at least 750 ft (250 m).

The speed indicator display shall be equipped with a violation alert that flashes the displayed detected speed when the posted limit is exceeded. The speed indicator shall have a maximum speed cutoff. The display shall include automatic dimming for nighttime operation.

The speed indicator measurement and display functions shall be equipped with the power supply capable of providing 24 hours of uninterrupted service.”

Added 04/14/2014