

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED 10% STATE						
				0021						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	1011	1011						
25000210	SEEDING, CLASS 2A	ACRE	0.21	0.21						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	19	19						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	19	19						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	19	19						
25100630	EROSION CONTROL BLANKET	SO YD	1011	1011						
28000400	PERIMETER EROSION BARRIER	FOOT	1845	1845						
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1737.5	1737.5						
	6 FOOT POSTS									
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6						
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	5	5						
	(SPECIAL) TANGENT									
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	9	9						
	(SPECIAL) FLARED									
63200310	GUARDRAIL REMOVAL	FOOT	487.5	487.5						
63500105	DELINEATORS	EACH	50	50						
63500310	REMOVE AND REINSTALL DELINEATORS	EACH	180	180						

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED 10% STATE						
				0021						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6						
67100100	MOBILIZATION	L SUM	1	1						
78200410	GUARDRAIL MARKERS, TYPE A	EACH	45	45						
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	14	14						
X7011015	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1						
	(EXPRESSWAYS)									

FILE NAME : D:\p1\work\p1\1001\percip\0367985-011314-11-5004.dwg	USER NAME : PercipL	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**I-80 (GRUNDY COUNTY LINE TO HOUBOLT ROAD)  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 80	SECTION 2013-0711	COUNTY WILL	TOTAL SHEETS 19	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 60X48	

115

114

5