PATCHING SCHEDULE
FOR CLASS B PATCHES

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA TYPE I (sq. yd)	PATCH AREA TYPE II (sq. yd)	PATCH AREA TYPE III (sq. yd)	PATCH AREA TYPE IV (sq. yd)	DOWEL BARS 1 1/2" 44201299 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 1" 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
394+24.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
394+62.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
395+06.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
395+47.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
395+85.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
396+24.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
396+65.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
397+02.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
397+42.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
397+85.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
398+26.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
398+65.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
399+43.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
399+83.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
400+28.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
400+66.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
401+48.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
401+86.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
402+27.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
402+67.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
403+04.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
403+44.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
403+88.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
404+23.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
404+64.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
405+06.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
405+42.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
405+83.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
406+20.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
406+61.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
406+98.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
407+31.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
407+77.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
408+16.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
408+35.00	NB	PASS	23	17	0.0	0.0	0.0	43.4	32	97.0	12	43.4
408+94.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
409+34.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
409+74.00	NB	PASS	6	17	0.0	11.3	0.0	0.0	32	63.0	0	0.0
PASSING LANE TOTALS					0.0 (sq. yd)	418.1 (sq. yd)	0.0 (sq. yd)	43.4 (sq. yd)	1216 (Each)	2428 (ft)	12 (Each)	43.4 (sq. yd)

FILE NAME = c:\pw_work\pwidot\gorengautab\d0370719\D112414-sht-plan.dgn	USER NAME = Gorengautab	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -
Default	PLOT DATE = 2/3/2014	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERSTATE 55
BYPASS LANE PATCHING SCHEDULE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(99-1TWS-2)PP	WILL	16	5

CONTRACT NO. 60X53

ILLINOIS FED. AID PROJECT