

GENERAL NOTES

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1.	COVER SHEET
2.	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3.	SUMMARY OF QUANTITIES
4-6.	PATCHING SCHEDULE
7.	TYPICAL SECTION
8-9.	ROADWAY PLAN
10.	DETECTOR LOOP PLANS
11.	ENTRANCE RAMP AND CLOSURE DETAILS (TC-08)
12-13.	MULTI-LANE FREEWAY PAVEMENT MARKING (TC-12)
14.	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)
15.	TRAFFIC CONTROL FOR SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)
16.	SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS (TC-18)

STATE STANDARDS

STANDARD NO.	DESCRIPTION
420001-07	PAVEMENT JOINTS
420701-02	PAVEMENT FABRIC
442101-07	CLASS B PATCHES
701411-08	LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP FOR SPEEDS > 45 MPH
701428	TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/EXPRESSWAY
701901-03	TRAFFIC CONTROL DEVICES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, AND THE VILLAGE OF BOLINGBROOK.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

USE #8 EPOXY-COATED TIE BARS, CONFORMING TO ART. 1006.10 OF THE STANDARD SPECIFICATIONS, FOR ALL TIE BARS. USE THE "LONGITUDINAL CONSTRUCTION JOINT (TIE BAR GROUTED IN PLACE)" DETAIL SHOWN ON HIGHWAY STANDARD 420001 FOR ALL LONGITUDINAL JOINTS.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE EXPRESSWAYS TRAFFIC CONTROL SUPERVISOR AT (847)705-4155 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT THE SOUTH AREA TRAFFIC EXPRESSWAY ENGINEER, AT (847) 705-4153 A MINIMUM OF TWO WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

POLYUREA PAVEMENT MARKING APPLIES TO EXISTING PAVEMENT MARKING AFFECTED BY PATCHING.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE.

THE ENGINEER SHALL OBTAIN APPROVAL FROM THE DISTRICT ONE BUREAU CHIEF OF MAINTENANCE FOR ANY PROPOSED REVISIONS IN THE SCHEDULED PAVEMENT PATCHING LOCATIONS.

ANY DAMAGE TO THE ADJACENT GRASS AREAS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE DEPARTMENT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

DRILL AND GROUT SHALL BE INCLUDED IN THE COST OF TIE BAR.

FILE NAME : c:\p\work\psidot\gorengautab\0370719\012414-sht-plan.dgn	USER NAME : Gorengautab	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INTERSTATE 55 INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES			F.A.I. RTE. 55	SECTION (99-ITWS-2)PP	COUNTY WILL	TOTAL SHEETS 16	SHEET NO. 2
PLOT SCALE * 100.0000 / in.		DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60X53	
CHECKED -		CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
PLOT DATE * 2/3/2014		DATE -	REVISED -									