

PATCHING SCHEDULE
FOR CLASS B PATCHES

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS 1 1/2" 44201299 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 1" 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
1104+82	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1104+61	SB	RAMP	8	14	0.0	12.4	0.0	0.0	24	58.0	0	0.0
1104+47	SB	RAMP	15	14	0.0	0.0	23.3	0.0	24	72.0	8	23.3
1104+24	SB	RAMP	8	14	0.0	12.4	0.0	0.0	24	58.0	0	0.0
EXIT RAMP LANE (HMA) SUBTOTALS					0.0	34.2	23.3	0.0	96.0	242.0	8.0	23.3

Added Sheet 4-9-14

FILE NAME * c:\pwork\psidot\pyrzanowski\0837042	USER NAME * pyrzanowski	DESIGNED -	REVISIED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE EXIT RAMP TO WEIGH STATION (HMA)				F.A.J. RTE. 57	SECTION 199-2TWSIPP	COUNTY WILL	TOTAL SHEETS 18	SHEET NO. 4A
Default	VD112614-shit-plan.dgn	DRAWN -	REVISIED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60X55		
	PLOT SCALE * 100.0000' / in.	CHECKED -	REVISIED -		ILLINOIS FED. AID PROJECT								
	PLOT DATE * 3/28/2014	DATE -	REVISIED -										