

PATCHING SCHEDULE
FOR CLASS B PATCHES

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS 1 1/2" 44201299 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 1" 44213202 (Each)	PAYEMENT FABRIC 44213100 (sq. yd)
					TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
1076+59	SB	RAMP	6	24	0.0	0.0	16.0	0.0	44	84.0	0	16.0
1074+50	SB	RAMP	8	24	0.0	0.0	16.0	0.0	44	84.0	0	16.0
ENTRANCE RAMP LANE (HMA) SUBTOTALS					0.0 (sq. yd)	0.0 (sq. yd)	32.0 (sq. yd)	0.0 (sq. yd)	88.0 (Each)	168.0 (ft)	8.0 (Each)	32.0 (sq. yd)

Added Sheet 4-9-14

FILE NAME *	USER NAME * pyzranowski	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE ENTRANCE RAMP TO I-57 (HMA)				F.A.I. RTE. 57	SECTION 199-2T#SIPP	COUNTY WILL	TOTAL SHEETS 18	SHEET NO. 7A
c:\p\work\p\dot\pyzranowski\037042	DI12614-ent-plan.dgn	DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60X55		
Default	PLOT SCALE * 100.0000' / in.	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT								
	PLOT DATE * 3/20/2014	DATE -	REVISED -										