

PATCHING SCHEDULE
FOR CLASS B PATCHES

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS 1 1/2" 44201299 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 1" 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE I	TYPE II	TYPE III	TYPE IV				
					(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)				
1103+90	SB	RAMP	10	14	0.0	0.0	15.6	0.0	24	62.0	0	15.6
1100+20	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1099+90	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1099+29	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1098+84	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1098+29	SB	RAMP	6	20	0.0	13.3	0.0	0.0	36	72.0	0	0.0
1098+28	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1098+18	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1098+15	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1097+93	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1097+59	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
1097+44	SB	RAMP	8	30	0.0	0.0	0.0	26.7	56	106.0	0	26.7
1097+13	SB	RAMP	6	14	0.0	9.3	0.0	0.0	24	54.0	0	0.0
EXIT RAMP LANE (PCC) SUBTOTALS					0.0	106.7	15.6	26.7	356.0	780.0	0.0	42.2
					(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)	(Each)	(ft)	(Each)	(sq. yd)

FILE NAME =	USER NAME = pyrzanowskirb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE EXIT RAMP TO WEIGH STATION				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\pyrzanowskirb\0370428\DI12614-sht-plan.dgn	DI12614-sht-plan.dgn	DRAWN -	REVISED -		57	199-2TWSJPP	WILL	18	4				
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		CONTRACT NO. 60X55				ILLINOIS FED. AID PROJECT				
	PLOT DATE = 2/3/2014	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.			