

PATCHING SCHEDULE
FOR CLASS B PATCHES

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS 1 1/2" 44201299 (Each)	SAW CUTS 44213200 (ft)	TIE BARS 1" 44213202 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE I (sq. yd)	TYPE II (sq. yd)	TYPE III (sq. yd)	TYPE IV (sq. yd)				
1088+72	SB	SCALE	6	14	0.0	9.3	0.0	0.0	24	60.0	0	0.0
1087+00	SB	SCALE	6	14	0.0	9.3	0.0	0.0	24	60.0	0	0.0
1085+44	SB	SCALE	6	25	0.0	0.0	16.7	0.0	48	93.0	0	16.7
1085+72	SB	SCALE	6	17	0.0	11.3	0.0	0.0	32	69.0	0	0.0
1085+84	SB	SCALE	6	15	0.0	10.0	0.0	0.0	28	63.0	0	0.0
SCALE LANE SUBTOTALS					0.0 (sq. yd)	40.0 (sq. yd)	16.7 (sq. yd)	0.0 (sq. yd)	156.0 (Each)	345.0 (ft)	0.0 (Each)	16.7 (sq. yd)

FILE NAME =	USER NAME = pyrzanowskirb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE SCALE LANE				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\pyrzanowskirb\037042	ND112614-sht-plan.dgn	DRAWN -	REVISED -		57	199-2TWSJPP	WILL	18	6				
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 60X55				
	PLOT DATE = 2/3/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								