

URBAN  
100%  
STATE  
TOTAL  
QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE 0044					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0044					CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
42001300	PROTECTIVE COAT	SQ YD	709	709													
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	283	283													
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	52.5	52.5													
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	372.9	372.9													
44201299	DOREL BARS 1 1/2"	EACH	1200	1200													
44213100	PAYEMENT FABRIC	SQ YD	425.3	425.3													
44213200	SAW CUTS	FOOT	2832	2832													
44213202	TIE BARS 1"	EACH	169	169													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2													
67100100	MOBILIZATION	L SUM	1	1													
* 78008210	POLYUREA PAYEMENT MARKING TYPE I - LINE 4"	FOOT	396	396													
* 78008240	POLYUREA PAYEMENT MARKING TYPE I - LINE 8"	FOOT	390	390													
x7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1													
			* Specialty Item														

FILE NAME :	USER NAME : <i>pyromax16</i>	DESIGNED :	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
<i>0044_urban100%state100%00440044</i>	<i>pyromax16</i>	DRAWN -	REVISD -			57	199-27WSIPP	WILL	18	3
PLOT SCALE : 001000' = 1" IN	CHECKED -	REVISD -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
PLOT DATE : 2/3/2014	DATE -	REVISD -								CONTRACT NO. 60X55