



INDEX OF SHEETS

PAGE #	TS*	INTERSECTION NAME
1		COVER PAGE
2		INDEX OF SHEETS & GENERAL NOTES
3-4		LOCATION MAP
5		SDD HEADINGS
6-8		SDD SHEETS
9-15		IDOT TS DETAILS
16	195	US 6/IL 83/TORRENCE AVE @ 170TH ST
17	230	US 6/159TH ST @ GREENWOOD RD
18	345	US 6/IL 83/TORRENCE AVE @ RIVER OAKS SOUTH ENTR.*4
19	3480	IL 83/TORRENCE AVE @ MICHIGAN CITY RD
20	3980	127TH ST @ ASHLAND AVE
21	4015	127TH ST @ BISHOP ST
22	4410	BURNHAM AVE @ 152ND ST/MEMORIAL
23	4415	BURNHAM AVE @ 156TH ST
24	4425	BURNHAM AVE @ MICHIGAN CITY RD
25	4430	BURNHAM AVE @ PULASKI RD/154TH ST
26	4435	SIBLEY BLVD @ BURNHAM AVE
27	4440	154TH ST/PULASKI RD @ MICHIGAN CITY RD
28	4475	RIVER OAKS RD @ SCHRUM RD/WENTWORTH AVE
29	4480	IL 83/SIBLEY BLVD @ CLYDE AVE
30	4482	IL 83/SIBLEY BLVD @ MADISON AVE
31	4490	IL 83/SIBLEY BLVD @ YATES AVE
32	4495	IL 83/TORRENCE AVE @ 154TH ST
33	4500	TORRENCE AVE @ IL 83/147TH ST/SIBLEY BLVD
34	5820	TORRENCE AVE @ DOLTON/STATE RD
35	4420	BURNHAM AVE @ 163RD ST
36	1360	US 30/LINCOLN HWY @ COTTAGE GROVE AVE
37	1370	US 30/LINCOLN HWY @ FORD MOTOR PLANT ENTRANCE
38	1755	IL 1/HALSTED ST @ PARKSIDE CUTOFF
39	1780	IL 1/CHICAGO RD @ 26TH ST
40	1845	IL 1/HALSTED CUT OFF @ RIEGEL RD/CHICAGO RD
41	1850	IL 1/HALSTED ST @ JOE ORR RD
42	3740	26TH ST @ EAST END AVE
43	4335	IL 1/HALSTED @ 12TH ST
44	4340	HALSTED ST @ 13TH ST
45	4360	DIXIE HWY @ 10TH ST
46	4365	DIXIE HWY @ ASHLAND AVE
47	4370	DIXIE HWY @ VOLLMER RD
48	4375	JOE ORR RD @ ASHLAND AVE
49	4380	IL 1/HALSTED ST @ VOLLMER RD
50	5060	DIXIE HWY @ JOE ORR RD
51	9300	WESTERN AVE @ BEACON BLVD
52	1825	IL 1/HALSTED ST @ 171ST ST
53	11725	DIXIE HWY @ FLOSSMOOR RD/CAMBRIDGE DR
54	4930	CRAWFORD AVE/PULASKI RD @ VOLLMER RD
55	5055	DIXIE HWY @ HOLBROOK RD
56	5105	FLOSSMOOR RD @ WESTERN AVE
57	5180	GOVERNORS HWY @ FLOSSMOOR RD
58	5200	GOVERNORS HWY @ VOLLMER RD
59	5895	WESTERN AVE @ VOLLMER RD
60	1425	US 30/LINCOLN HWY @ WOODLAWN AVE
61	1437	US 30/LINCOLN HWY @ ACCESS RD/TRANSPORTATION DR
62	21605	US 30/LINCOLN HWY @ ELLIS ST
63	11865	NORTH MAIN ST/VINCENNES @ GLENWOOD DYER/MAIN ST
64	1835	IL 1 HALSTED @ HOLBROOK RD
65	5125	GLENWOOD DYER RD @ COTTAGE GROVE AVE
66	10845	168TH ST @ DIXIE HWY
67	10850	170TH ST @ DIXIE HWY
68	10855	170TH ST @ WOOD ST
69	4092	GOVERNORS HWY @ METRA LOT ENTRANCE
70	4095	183RD ST @ CRAWFORD AVE/PULASKI RD
71	45	DIXIE HWY @ I 80/TRI STATE TOLLWAY
72	48	171ST ST @ DIXIE HWY
73	5965	171ST ST @ WOOD ST
74	10860	175TH ST @ GOVERNORS HWY
75	5900	WESTERN AVE @ 16TH/ILLINOIS
76	9295	WESTERN AVE @ 26TH ST/NORWOOD BLVD
77	11715	WESTERN AVE @ SAUK TRAIL
78	11716	WESTERN AVE @ MAIN ST

GENERAL NOTES

ALL CONSTRUCTION SHALL CONFORM TO THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (SSRBC), AND SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS; ADOPTED JANUARY 1, 2014 BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION AND ALL AMENDMENTS THERETO; IN CASE OF CONFLICT, THE MORE RESTRICTIVE PROVISIONS SHALL APPLY. ANY REFERENCE TO STANDARDS IN THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT.

THE CONTRACTOR SHALL CHECK THE PROPOSED TRAFFIC SIGNAL EQUIPMENT LOCATIONS FOR OVERHEAD UTILITY CONFLICTS. THE CONTRACTOR SHALL COORDINATE ANY CONFLICTS WITH THE UTILITY COMPANIES AND THE RESIDENT ENGINEER BEFORE ORDERING MATERIALS.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LOCAL GOVERNMENT AGENCIES, AND IDOT.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OF UNSUITABLE MATERIALS CREATED AS A RESULT THEREOF.

THE CONTRACTOR SHALL NOTIFY THE IDOT ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE CONTRACTOR SHALL SOLELY BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES, AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ADJUTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT OR THE DIRECTION OF THE ENGINEER.

THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL AREAS AFFECTED BY EQUIPMENT OR LABORERS TO EXISTING CONDITIONS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROTECTING ALL NEW WORK UNTIL COMPLETION OF THIS CONTRACT.

RESTORATION OF WORK AREA: RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS SIGNAL POST, UNINTERRUPTIBLE POWER SUPPLY ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD IN ACCORDANCE TO STANDARD SPECIFICATIONS ARTICLE 252 WHICH SHALL INCLUDE THE REQUIRED WATERING PER ARTICLE 252.08. ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS ARTICLE 250 AND 251, RESPECTIVELY.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.

THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ORDERING ANY MATERIALS AND STARTING ANY WORK. FOR LOCATIONS OF UTILITIES, LOCALLY OWNED EQUIPMENT, LEASED ENFORCEMENT CAMERA SYSTEM FACILITIES, AND IDOT UNDERGROUND FACILITIES, CONTACT THE LOCAL COUNTIES, MUNICIPALITIES, AND IDOT FOR LOCATES. THE CONTRACTOR SHALL CALL 'JULIE' AT (800)892-0123 OR 811. IN THE CITY OF CHICAGO CONTACT DIGGER AT (312)744-7000 FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS NOTIFICATION REQUIRED).

AT LOCATIONS ON THE PLANS WHERE TRAFFIC SIGNAL POST REMOVAL AND NEW TRAFFIC SIGNAL POST INSTALLATIONS ARE SPECIFIED, THE CONTRACTOR SHALL INSPECT THE EXISTING POST FOUNDATIONS. PRIOR TO REMOVING THE EXISTING TRAFFIC SIGNAL POST TO BE REPLACED, THE CONTRACTOR SHALL VERIFY THAT THE EXISTING CONDITION OF THE ANCHOR BOLT IS ACCEPTABLE. IF THE EXISTING ANCHOR BOLT CONDITION IS NOT ACCEPTABLE, THE CONTRACTOR SHALL REPLACE ANCHOR BOLT AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL BE PAID FOR THE NUMBER OF TRAFFIC SIGNAL POSTS INSTALLED AND NO OTHER COMPENSATION WILL BE PROVIDED.

THE CONTRACTOR SHALL RELOCATE ANY EXISTING TRAFFIC SIGNAL HEADS, PEDESTRIAN SIGNAL HEADS, AND PEDESTRIAN PUSH-BUTTONS FROM PAINTED POSTS THAT ARE INDICATED FOR REPLACEMENT TO A NEW POST AS SHOWN ON THE PLANS, EXCEPT AS SHOWN TO BE REPLACED ON THE PLANS, OR AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL, RELOCATION, AND ANY NEW MOUNTING HARDWARE NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE TRAFFIC SIGNAL POST PAY ITEM OF THE LENGTH AS SPECIFIED IN THE PLANS.

THE CONTRACTOR SHALL RELOCATE ANY EXISTING SIGN PANELS, INCLUDING BLANK OUT SIGNS, FROM PAINTED POSTS THAT ARE INDICATED FOR REPLACEMENT TO A NEW POST AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL, RELOCATION, AND ANY NEW MOUNTING HARDWARE NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE PAY ITEM OF THE LENGTH AS SPECIFIED IN THE PLANS.

CONTRACTOR SHALL REPLACE ALL EXISTING METAL TRAFFIC SIGNAL AND PEDESTRIAN BRACKETS TO NEW POLYCARBONATE BRACKETS. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CORRESPONDING SIGNAL HEAD, LED, RETROFIT PAY ITEM OF THE TYPE AND NUMBER OF SIGNAL HEADS, FACES, AND SECTIONS AS SPECIFIED IN THE PLANS.

PARTIAL PAYMENT AS DESCRIBED IN ARTICLE 109.07(b) OF THE STANDARD SPECIFICATIONS WILL NOT BE ALLOWED FOR ITEMS INCLUDED IN THIS CONTRACT.

FOR TS 4425 AND TS 4500 LOCATIONS, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE CITY OF CALUMET CITY PRIOR TO THE START OF CONSTRUCTION. THE CITY OF CALUMET CITY SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

CITY OF CALUMET CITY
204 PULASKI ROAD
CALUMET CITY, IL 60409
(708) 891-8100

FOR TS 4370 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE CITY OF CHICAGO HEIGHTS PRIOR TO THE START OF CONSTRUCTION. THE CITY OF CHICAGO HEIGHTS SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

CITY OF CHICAGO HEIGHTS
1601 CHICAGO ROAD
CHICAGO HEIGHTS, IL 60411
(708) 756-5300

FOR TS 4380 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE CITY OF CHICAGO HEIGHTS AND SAFE SPEED, LLC PRIOR TO THE START OF CONSTRUCTION. THE CITY OF CHICAGO HEIGHTS OR SAFE SPEED, LLC SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

CITY OF CHICAGO HEIGHTS
1601 CHICAGO ROAD
CHICAGO HEIGHTS, IL 60411
(708) 756-5300

SAFE SPEED, LLC.
118 N. CLINTON, SUITE 200
CHICAGO, IL 60661
(877) 237-2331

FOR TS 1825 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE VILLAGE OF EAST HAZEL CREST PRIOR TO THE START OF CONSTRUCTION. THE VILLAGE OF EAST HAZEL CREST SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

VILLAGE OF EAST HAZEL CREST
1904 W. 174TH STREET
EAST HAZEL CREST, IL 60429
(708) 798-2186

FOR TS 5965 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE VILLAGE OF HAZEL CREST PRIOR TO THE START OF CONSTRUCTION. THE VILLAGE OF HAZEL CREST SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

VILLAGE OF HAZEL CREST
3000 W. 170TH PLACE
HAZEL CREST, IL 60429
(708) 335-9600

FILE NAME 0160164-shi-gennote.dgn	USER NAME Brian Scifera	DESIGNED BKS	REVISED DYS 9/10/19	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS AND GENERAL NOTES	F.A. RTE.	SECTION 2013-075TS	COUNTY COOK	TOTAL SHEETS 78	SHEET NO. 2
PLOT SCALE 1/40,000 1" = 1/4 mi.	CHECKED BKS	REVISIONS	CONTRACT NO. 60X64							
PLOT DATE 3/7/2019	DATE	SCALE	SHEET OF SHEETS STA. TO STA.							
Default			ILLINOIS FED. AID PROJECT							