



INDEX OF SHEETS

PAGE #	DESCRIPTION
1	COVER PAGE
2	INDEX OF SHEETS & GENERAL NOTES
3-4	LOCATION MAP
5	SOO HEADINGS
6-8	SOO SHEETS
9-15	IDOT TS DETAILS

PAGE #	TS#	INTERSECTION NAME
16	2580	IL 50/CICERO AVE @ 167TH ST
17	170	US 6/159TH ST @ IL 50/CICERO AVE
18	275	US 6/159TH ST @ RIDGELAND AVE
19	4075	147TH ST @ CENTRAL AVE
20	4076	147TH ST @ RIDGELAND AVE
21	2570	IL 50/CICERO AVE @ 151ST ST
22	2575	IL 50/CICERO AVE @ 155TH ST
23	2595	IL 50/CICERO AVE @ 166TH ST/FIELDCREST DR
24	205	US 6/159TH ST @ CENTRAL AVE
25	325	US 6/159TH ST @ LARAMIE AVE
26	9950	US 6/159TH ST @ OAK FOREST HOSPITAL
27	20365	US 6/159TH ST @ 91ST AVE/PARK HILL DR
28	1830	IL 43/HARLEM AVE @ 143RD ST DELETED
29	2210	IL 43/HARLEM AVE @ 151ST ST DELETED
30	21522	IL 7/143RD ST @ 100TH ST DELETED
31	190	US 6/159TH ST @ 94TH ST
32	165	US 6/159TH ST @ IL 43 HARLEM AVE
33	20401	US 6/159TH ST @ RAVENNA AVE DELETED
34	20560	US 6/WOLF RD @ 167TH ST
35	1911	131ST ST @ 16TH AVE
36	1920	IL 7/143RD ST @ 100TH AVE/WEST AVE
37	21520	IL 7/143RD ST @ IL 7/WOLF RD
38	163	IL 7/159TH ST @ WILL COOK RD DELETED
39	1905	IL 7/SOUTHWEST HWY @ 131ST ST
40-41	1910	IL 7/SOUTHWEST HWY @ 135TH ST
42-43	1915	IL 7/SOUTHWEST HWY @ 143RD ST
44	158	IL 7/WOLF RD @ 151ST ST
45	159	IL 7/WOLF RD @ 153RD ST
46	235	US 6/159TH ST @ 71ST ST DELETED
47	185	US 6/159TH ST @ 80TH AVE
48	160	US 6/159TH ST @ IL 7/WOLF RD NORTH JUNCTION DELETED
49	21920	US 6/159TH ST @ ORLAND TOWN CENTER/JEWEL
50	162	US 6/WOLF RD @ BROOKHILL DR
51	161	US 6/WOLF RD @ US 6/173RD ST-SOUTH JUNCTION
52	156	WOLF RD @ 179TH ST
53	330	US 6/159TH ST @ 88TH AVE
54	8920	IL 43/HARLEM AVE @ 171ST ST
55	2255	IL 43/HARLEM AVE @ 183RD ST
56	22263	IL 43/HARLEM AVE @ 191ST ST
57	7417	US 45/LA GRANGE RD @ 183RD ST
58	2256	183RD ST @ OAK PARK AVE
59	4108	183RD ST @ RIDGELAND AVE
60	11325	IL 43/HARLEM AVE @ 161ST ST
61	8910	IL 43/HARLEM AVE @ 167TH ST
62	8935	IL 43/HARLEM AVE @ BREMENTONNE/163RD ST
63	180	US 6/159TH ST @ 76TH AVE
64	240	US 6/159TH ST @ 84TH AVE
65	11330	US 6/159TH ST @ PARK CENTER

GENERAL NOTES

ALL CONSTRUCTION SHALL CONFORM TO THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (SSRBC), AND SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, ADOPTED JANUARY 1, 2014 BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION AND ALL AMENDMENTS THERETO; IN CASE OF CONFLICT, THE MORE RESTRICTIVE PROVISIONS SHALL APPLY. ANY REFERENCE TO STANDARDS IN THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT.

THE CONTRACTOR SHALL CHECK THE PROPOSED TRAFFIC SIGNAL EQUIPMENT LOCATIONS FOR OVERHEAD UTILITY CONFLICTS. THE CONTRACTOR SHALL COORDINATE ANY CONFLICTS WITH THE UTILITY COMPANIES AND THE RESIDENT ENGINEER BEFORE ORDERING MATERIALS.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LOCAL GOVERNMENT AGENCIES, AND IDOT.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL WILL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR'S FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OF UNSUITABLE MATERIALS CREATED AS A RESULT THEREOF.

THE CONTRACTOR SHALL NOTIFY THE IDOT ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE CONTRACTOR SHALL SOLELY BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ADEQUATE SIGNS, TRAFFIC CONTROL DEVICES, AND WARNING DEVICES TO INFORM AND PROTECT THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT OR THE DIRECTION OF THE ENGINEER.

THE CONTRACTOR IS RESPONSIBLE FOR RETURNING ALL AREAS AFFECTED BY EQUIPMENT OR LABORERS TO EXISTING CONDITIONS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR PROTECTING ALL NEW WORK UNTIL COMPLETION OF THIS CONTRACT.

RESTORATION OF WORK AREA: RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS SIGNAL POST, UNINTERRUPTIBLE POWER SUPPLY ETC. AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOO IN ACCORDANCE TO STANDARD SPECIFICATIONS ARTICLE 252 WHICH SHALL INCLUDE THE REQUIRED WATERING PER ARTICLE 252.08. ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS ARTICLE 250 AND 251, RESPECTIVELY.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION.

THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE ORDERING ANY MATERIALS AND STARTING ANY WORK. FOR LOCATIONS OF UTILITIES, LOCALLY OWNED EQUIPMENT, LEASED ENFORCEMENT CAMERA SYSTEM FACILITIES, AND IDOT UNDERGROUND FACILITIES. CONTACT THE LOCAL COUNTIES, MUNICIPALITIES, AND IDOT FOR LOCATES. THE CONTRACTOR SHALL CALL 'JULIE' AT (800)892-0123 OR 811. IN THE CITY OF CHICAGO CONTACT DIGGER AT (312)744-7000 FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS NOTIFICATION REQUIRED).

AT LOCATIONS ON THE PLANS WHERE TRAFFIC SIGNAL POST REMOVAL AND NEW TRAFFIC SIGNAL POST INSTALLATIONS ARE SPECIFIED, THE CONTRACTOR SHALL INSPECT THE EXISTING POST FOUNDATIONS, PRIOR TO REMOVING THE EXISTING TRAFFIC SIGNAL POST TO BE REPLACED, THE CONTRACTOR SHALL VERIFY THAT THE EXISTING CONDITION OF THE ANCHOR BOLT IS ACCEPTABLE. IF THE EXISTING ANCHOR BOLT CONDITION IS NOT ACCEPTABLE, THE CONTRACTOR SHALL REPLACE ANCHOR BOLT AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL BE PAID FOR THE NUMBER OF TRAFFIC SIGNAL POSTS INSTALLED AND NO OTHER COMPENSATION WILL BE PROVIDED.

THE CONTRACTOR SHALL RELOCATE ANY EXISTING TRAFFIC SIGNAL HEADS, PEDESTRIAN SIGNAL HEADS, AND PEDESTRIAN PUSH-BUTTONS FROM PAINTED POSTS THAT ARE INDICATED FOR REPLACEMENT TO A NEW POST AS SHOWN ON THE PLANS, EXCEPT AS SHOWN TO BE REPLACED ON THE PLANS, OR AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL, RELOCATION, AND ANY NEW MOUNTING HARDWARE NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE TRAFFIC SIGNAL POST PAY ITEM OF THE LENGTH AS SPECIFIED IN THE PLANS.

THE CONTRACTOR SHALL RELOCATE ANY EXISTING SIGN PANELS, INCLUDING BLANK OUT SIGNS, FROM PAINTED POSTS THAT ARE INDICATED FOR REPLACEMENT TO A NEW POST AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THE COST OF REMOVAL, RELOCATION, AND ANY NEW MOUNTING HARDWARE NECESSARY TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE PAY ITEM OF THE LENGTH AS SPECIFIED IN THE PLANS.

CONTRACTOR SHALL REPLACE ALL EXISTING METAL TRAFFIC SIGNAL AND PEDESTRIAN BRACKETS TO NEW POLYCARBONATE BRACKETS. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CORRESPONDING SIGNAL HEAD, LED, RETROFIT PAY ITEM OF THE TYPE AND NUMBER OF SIGNAL HEADS, FACES, AND SECTIONS AS SPECIFIED IN THE PLANS.

PARTIAL PAYMENT AS DESCRIBED IN ARTICLE 109.07(b) OF THE STANDARD SPECIFICATIONS WILL NOT BE ALLOWED FOR ITEMS INCLUDED IN THIS CONTRACT.

FOR TS 2580 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE CITY OF OAK FOREST AND GATSO-USA PRIOR TO THE START OF CONSTRUCTION. THE CITY OF OAK FOREST AND GATSO-USA SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

CITY OF OAK FOREST
15440 SOUTH CENTRAL AVENUE
OAK FOREST, IL 60452
(708) 687-4050

GATSO-USA
900 CUMMINGS CTR. 410-T
BEVERLY, MA 01915

FOR TS 170 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE CITY OF OAK FOREST PRIOR TO THE START OF CONSTRUCTION. THE CITY OF OAK FOREST SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

CITY OF OAK FOREST
15440 SOUTH CENTRAL AVENUE
OAK FOREST, IL 60452
(708) 687-4050

FOR TS 165 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE VILLAGE OF ORLAND PARK AND REDFLEX TRAFFIC SYSTEMS PRIOR TO THE START OF CONSTRUCTION. THE VILLAGE OF ORLAND PARK OR REDFLEX TRAFFIC SYSTEMS SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

VILLAGE OF ORLAND PARK
14700 RAVINIA AVENUE
ORLAND PARK, IL 60462
(708) 403-6100

REDFLEX TRAFFIC SYSTEMS
15020 N 74TH STREET
SCOTTSDALE, AZ 85260
(480) 607-0705

FOR TS 2255 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE VILLAGE OF TINLEY PARK AND REDFLEX TRAFFIC SYSTEMS PRIOR TO THE START OF CONSTRUCTION. THE VILLAGE OF TINLEY PARK OR REDFLEX TRAFFIC SYSTEMS SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

VILLAGE OF TINLEY PARK
16250 OAK PARK AVENUE
TINLEY PARK, IL 60477
(708) 444-5000

REDFLEX TRAFFIC SYSTEMS
15020 N 74TH STREET
SCOTTSDALE, AZ 85260
(480) 607-0705

FOR TS 8920 LOCATION, DUE TO THE PRESENCE OF A RED LIGHT RUNNING (RLR) CAMERA WITHIN THE PROJECT LIMITS, CONTRACTOR SHALL NOTIFY THE VILLAGE OF TINLEY PARK PRIOR TO THE START OF CONSTRUCTION. THE VILLAGE OF TINLEY PARK SHALL MAKE THE RLR CAMERA INOPERATIVE FOR THE TIME OF CONSTRUCTION. ANY RLR CAMERA EQUIPMENT THAT IS IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED BY ITS RESPECTIVE OWNERS PRIOR TO THE START OF CONSTRUCTION.

VILLAGE OF TINLEY PARK
16250 OAK PARK AVENUE
TINLEY PARK, IL 60477
(708) 444-5000

FILE NAME # 0100763-shl-gennote.dgn	USER NAME # Brian Salfers	DESIGNED - BKS	REVISED - SVS 8/10/14	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS AND GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	PLOT SCALE # 40.0000 1/4 in.	DRAWN - SVJ	REVISED -			2013-07675	COOK	65	2	
	PLOT DATE # 3/12/2014	CHECKED - BKS	REVISED -			CONTRACT NO. 60X65				
		DATE -	REVISED -			ILLINOIS FEG. AID PROJECT				
SCALE:					SHEET	OF	SHEETS	STA.	TO	STA.