



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2014

SUBJECT: FAI Route74/280 (I-74/280)
Section (37-1-HBR) M
Henry County
Contract No.64E94
Item No. 26, April 25, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised Table of Contents to the Special Provisions
3. Added page 40 to the Special Provisions
4. Revised sheet 3 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Paul A. Loete, Region 2, District 2; Tim Kell; Estimates

MS/kp

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64E94

State Job # - C-92-091-09

Project Number
 *REVISED: APRIL 9, 2014

Route
 FAI 74
 FAI 280

County Name - HENRY - -

Code - 73 - -

District - 2 - -

Section Number - (37-1HBR)M

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD X7010410	SPEED DISPLAY TRAILER	CAL MO	3.000				
Z0012754	STR REP CON DP = < 5	SQ FT	1,470.000				
Z0012755	STR REP CON DP OVER 5	SQ FT	60.000				
*ADD Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
*REV Z0073200	TEMP SHORING & CRIB	EACH	3.000				
42001300	PROTECTIVE COAT	SQ YD	157.400				
50102400	CONC REM	CU YD	61.100				
50300255	CONC SUP-STR	CU YD	61.600				
50800205	REINF BARS, EPOXY CTD	POUND	7,640.000				
50800515	BAR SPLICERS	EACH	112.000				
52000110	PREF JT STRIP SEAL	FOOT	366.000				
67000400	ENGR FIELD OFFICE A	CAL MO	3.000				
67100100	MOBILIZATION	L SUM	1.000				
70100207	TRAF CONT-PROT 701402	EACH	2.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64E94

State Job # - C-92-091-09

Project Number
 *REVISED: APRIL 9, 2014

Route
 FAI 74
 FAI 280

County Name - HENRY - -

Code - 73 - -

District - 2 - -

Section Number - (37-1HBR)M

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70300220	TEMP PVT MK LINE 4	FOOT	17,600.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	5,866.000				
70400100	TEMP CONC BARRIER	FOOT	1,952.000				
70400200	REL TEMP CONC BARRIER	FOOT	1,774.000				
70600250	IMP ATTN TEMP NRD TL3	EACH	2.000				
70600350	IMP ATTN REL NRD TL3	EACH	2.000				
78300100	PAVT MARKING REMOVAL	SQ FT	1,850.000				

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT.....	1
TRAFFIC CONTROL PLAN.....	1
START DATE.....	4
IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE)	4
ENGINEER’S FIELD OFFICE TYPE A.....	5
WORK ZONE PAVEMENT MARKING AND REMOVAL	5
RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10) (BDE)	6
TEMPORARY SHORING AND CRIBBING	7
STRUCTURAL REPAIR OF CONCRETE	8
COARSE AGGREGATE IN BRIDGE APPROACH SLABS/FOOTINGS (BDE)	17
CONCRETE MIX DESIGN – DEPARTMENT PROVIDED (BDE)	18
CONTRACT CLAIMS (BDE).....	18
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	19
PAYROLLS AND PAYROLL RECORDS (BDE)	29
PORTLAND CEMENT CONCRETE EQUIPMENT (BDE).....	31
PROGRESS PAYMENTS (BDE)	31
QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE).....	32
REINFORCEMENT BARS (BDE).....	32
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	34
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE).....	38
TRACKING THE USE OF PESTICIDES (BDE).....	39
WEEKLY DBE TRUCKING REPORTS (BDE).....	39
WORKING DAYS (BDE).....	39
SPEED DISPLAY TRAILER (BDE).....	40

Revised 04/14/2014

SPEED DISPLAY TRAILER (BDE)

Effective: April 2, 2014

Add the following to Article 701.15(l) of the Standard Specifications:

“(l) Speed Display Trailer. A speed display trailer shall be utilized on freeways and expressways as part of Highway Standard 701400. The trailer shall be placed on the right hand side of the roadway adjacent to, or within 100 ft (30 m) beyond, the first work zone speed limit sign.

Whenever the speed display trailer is not in use, it shall be considered non-operating equipment and shall be stored according to Article 701.11.”

Add the following to Article 701.20 of the Standard Specifications:

“(k) Speed Display Trailer will be paid for at the contract unit price per calendar month or fraction thereof for each trailer as SPEED DISPLAY TRAILER.”

Add the following to Article 1106.02 of the Standard Specifications:

“(o) Speed Display Trailer. The speed display trailer shall consist of a LED speed indicator display with self-contained, one-direction radar mounted on an orange see-through trailer. The height of the display and radar shall be such that it will function and be visible when located behind concrete barrier.

The speed measurement shall be by radar and provide a minimum detection distance of 1000 ft. (300 m). The radar shall have an accuracy of ± 1 mile per hour.

The speed indicator display shall face approaching traffic and shall have a sign legend of “YOUR SPEED” immediately above or below the speed display. The digital speed display shall show two digits (00 to 99) in mph. The color of the changeable message legend shall be a yellow legend on a black background. The minimum height of the numerals shall be 18 in. (450 mm), and the nominal legibility distance shall be at least 750 ft. (250 m).

The speed indicator display shall be equipped with a violation alert that flashes the displayed detected speed when the posted limit is exceeded. The speed indicator shall have a maximum speed cutoff. The display shall include automatic dimming for nighttime operation.

The speed indicator measurement and display functions shall be equipped with the power supply capable of providing 24 hours of uninterrupted service.”

Added 04/14/2014