

BRIDGE MAINT

SUMMARY OF QUANTITIES					100% State Funds
					0014
Pay Item No.	Description	Units	Lee	Ogle	Total Quantity
67100100	MOBILIZATION	L SUM	0.5	0.5	1
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	1	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	0.5	0.5	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14,860	10,040	24,900
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,953	3,347	8,300
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,152.97		1,152.97
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,152.97		1,152.97
70600251	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
70600352	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		124.8	124.8
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	14,800	7,200	22,000
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT		1000	1000
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT		600	600
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT		20	20
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,467	2,740	5,207
Z0007114	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES	L SUM	0.5	0.5	1
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1		1
Z0010502	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM		1	1

*Specialty Items

DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DRAWN -	REVISED -			IL 2 D2 BRIDGE PAINTING 2014	LEE / OGLE	25	3	
CHECKED -	REVISED -			CONTRACT NO. 64J52				
DATE -	REVISED -			ILLINOIS				