

CONSTR. CODE

FEDERAL = 80%
STATE = 20%

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	
				0005	URBAN
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	368		368
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	366		366
△ 87300605	ELECTRIC CABLE IN TRENCH, COMMUNICATION, NO. 16 3 PAIR	FOOT	200		200
△ 88500100	INDUCTIVE LOOP DETECTOR	EACH	1		1
△ 88600100	DETECTOR LOOP, TYPE I	FOOT	1230		1230
△ 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1		1
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	34811		34811
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	242		242
X5619210	WATER VALVES TO BE ADJUSTED, SPECIAL	EACH	2		2
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	51		51
△ X8860100	LOOP DETECTOR TESTING	EACH	1		1
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	42		42
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1

B

△ SPECIALTY ITEMS

FILE NAME :	USER NAME : duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
01\p\work\p\sidat\duncanbd\0130229\036152.sht-500.dgn	DRAWN -	REVISED -	68					28RS-4	DEKALB	27	7	
PLOT SCALE * 100.0000 / / in.	CHECKED -	REVISED -	SCALE: SHEET NO. 5 OF 5 SHEETS STA. TO STA.					CONTRACT NO. 66952				
PLOT DATE * 12/6/2013	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									