PAVEMENT MARKINGS

STA. TO STA.	PAINT			THERMOPLASTIC									PREF PLAST	RAISED REFL	TEMPORARY						SHORT TERM
	4"		6"	4"		6"		8"	12"		24"	LETTERS &	"B" INLAID 6"	PAVT MARK	4"	6"	8"	12"	24"	LETTERS &	(3 APP)
	YELLOW	WHITE	YELLOW	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	WHITE	SYMBOLS			(2 APPLICATIONS)					SYMBOLS	
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT
30' TAPER																					
CENTERLINE			20											1		20					0
EDGELINE		60																			
0+00 AH - 20+06																					
CENTERLINE			980											25		980					0
EDGELINE		8024																			
20+06 - 25+00																					
CENTERLINE			260											6		260					0
NO PASSING ZONE	988														988						
EDGELINE		1976																			
RAILROAD												61.2								122.4	
STOPBAR											36								72		
25+00 - 29+91																					
CENTERLINE			240											6		240					0
NO PASSING ZONE	982														982						
EDGELINE		1964																			
RAILROAD												61.2								122.4	
STOPBAR											36								72		
HARVESTORE LT																					
STOPBAR											19										
29+91 - 42+59																					
CENTERLINE			640											16		640					0
EDGELINE		5072																			
42+59 - 47+59																					
CENTERLINE			240											7		240					0
NO PASSING ZONE	1000														1000						
ISLAND								47		77							94	154			0
TURN LANE								156				31.2		3			312			62.4	0
EDGELINE		2000																			
MANNING LT																					
STOPBAR											20										
47+59 - 53+19																					
MEDIAN				1804					214					24	3608			428			0
TURN LANE								234				62.4		6			468			124.8	0
STOPBAR											56										
CENTERLINE													40	2		80					
EDGELINE					1010																
MERGE												42								84	
FAIRVIEW RT																					
MEDIAN				80										4	160						0
TURN LANE								40				15.6		2			80			31.2	0
STOPBAR											42										
53+19 - 54+60																					
CENTERLINE													60	2		120					
MEDIAN				180										6	360						
TURN LANE								45				31.2		2			90				
STOPBAR											29										
54+60 - 73+38																					
CENTERLINE													940	48		1880					0
BIDIRECTIONAL				3756		940						187.2		48	7512	1880				374.4	0
SCHOOL CROSSING												54.6									
CROSSWALK							201			294											
MERGE												42								84	
BALL RT																					
CROSSWALK							70														
STOPBAR											14										
FAIRLANE RT																					
CROSSWALK							68														
STOPBAR											13										
BEST RT																					
CROSSWALK							72														
STOPBAR											14										
COLONIAL RT																					
CROSSWALK							76														
STOPBAR											15										

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -
o:\pw_work\pwidot\duncanbd\d0130229\D365952-sht-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/6/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: | SHEET 3 OF 5 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	28RS-4	DEKALB	27	11
		CONTRACT NO. 66952		
		ILLINOIS FED. AID PROJECT		