

PAVEMENT MARKINGS																					
STA. TO STA.	PAINT			THERMOPLASTIC								PREF PLAST "B" INLAID 6"	RAISED REFL PAVT MARK EACH	TEMPORARY					LETTERS & SYMBOLS SQ FT	SHORT TERM (3 APP) FOOT	
	4"		6"	4"		6"		8"	12"		24"			4"	6"	8"	12"	24"			
	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT			FOOT	FOOT	FOOT	FOOT	FOOT			
BARB LT																					
CROSSWALK							103														
MEDIAN				10																	
STOPBAR										24											
TURN LANE								4													
73+38 - 74+28																					
CENTERLINE												40	2		80			12			
MEDIAN				180									6					54			
TURN LANE								45					2					13.5			
KAREN RT																					
CROSSWALK							75														
STOPBAR										14											
74+70 - 77+39																					
CENTERLINE												140	8		280			42			
MEDIAN				538									16		1076			161.4			
SCHOOL CROSSING																					
TURN LANE								196									240	124.8			
SPRING RT																					
CROSSWALK							85														
STOPBAR										16											
78+08 - 79+02																					
CENTERLINE												60	2		120			18			
MEDIAN				188									6		376			56.4			
TURN LANE								45					2				90	301.5			
79+02 - 80+75 BK																					
CENTERLINE												80	6		160			24			
BIDIRECTIONAL				346		100							4					62.4			
35+23 AH - 15+38																					
CENTERLINE												1000	50		2000			103.8			
BIDIRECTIONAL				3970		980							52		7940	1960		499.2			
CHARTER RT																					
CROSSWALK							82														
STOPBAR										16											
TYLER RT																					
CROSSWALK							77														
STOPBAR										16											
SUNSET LT																					
CROSSWALK							74														
STOPBAR										16											
HARVEY RT																					
CROSSWALK							81														
STOPBAR										16											
CULVER RT																					
CROSSWALK							81														
STOPBAR										16											
LACAS LT																					
CROSSWALK							63														
TOTAL	2970	19096	2380	11052	1010	2020	1208	812	214	371	428	1017.6	2360	368	24362	10940	1464	582	144	1754.4	12553

NOTE: PAINT PAVEMENT MARKING QUANTITY DOUBLED PER SPECIAL PROVISION.

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\duncanbd\0130229\036	952-ah1-schedule.dgn	DRAWN -	REVISED -			68	2BRS-4	DEKALB	27	12	
	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -			SCALE:		SHEET NO. 4 OF 5 SHEETS		STA.	TO STA.
	PLOT DATE = 12/6/2013	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					