



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

04/15/2014

SUBJECT: FAU Route 6584/6585 (Allen Road)  
Project ACM-000S (983)  
Section 105 (72-7HB) BY  
Peoria County  
Contract No. 68683  
Item No. 036, April 25<sup>th</sup> 2014 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices
2. Revised Plans Sheet No. 26 & 32
3. Revised Table of Contents Page V
4. Added page ( 376 ) to Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: J. E. Crowe, Region 3, District 4; Tim Kell; D. Carl Puzey; Estimates

HM/kp

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA- -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2C025G5	T-CERCIS CANAD CG 5G	EACH	80.000				
A2C02910	T-CELTIS OCC 1-1/4 CG	EACH	80.000				
A2C040G5	T-PLAT OCCID SY CG 5G	EACH	80.000				
A2C050G5	T-QUER BICL SWO CG 5G	EACH	80.000				
A2C070G5	T-TAXODIUM DIS CG 5G	EACH	80.000				
A2C07800	T-TILIA AMER 1-1/4 CG	EACH	80.000				
D2C02136	E-PICEA PUNGENS 3'C	EACH	80.000				
XX002202	VEH CONT BOLLARDS	EACH	1.000				
X0322936	REMOV EX FLAR END SEC	EACH	2.000				
X0323569	STEEL POST REMOVAL	EACH	6.000				
X0323586	PIPE DRAIN REMOVAL	FOOT	20.000				
X0325279	CLASS SI CONC (MISC)	CU YD	1.300				
X0326884	TS WOOD POLE 45 CL 5	EACH	4.000				
X0326952	STEP-DOWN TRANSFORMER	EACH	1.000				
X0327303	REM EX SIGN LT UNT NS	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0327607	FIBER OPT SPL-MAINLN	EACH	1.000				
X0327719	8" DUCTILE IRON FIT	EACH	20.000				
X0327720	12" DUCTILE IRON FIT	EACH	4.000				
X0327721	16" DUCTILE IRON FIT	EACH	19.000				
X0327726	MEMBR WATERPR CULVERT	SQ YD	419.000				
X0488100	REM EX SEPTIC TANK	EACH	3.000				
X2020502	BRACED EXCAVATION	CU YD	119.000				
X5630008	CUT & CAP EX 8 WM	EACH	5.000				
X5630012	CUT & CAP EX 12 WM	EACH	1.000				
X5630016	CUT & CAP EX 16 WM	EACH	9.000				
X5630708	CONN TO EX W MAIN 8	EACH	4.000				
X5630712	CONN TO EX W MAIN 12	EACH	1.000				
X5630716	CONN TO EX W MAIN 16	EACH	3.000				
X5860110	GRANULAR BACKFILL STR	CU YD	335.000				
X6020065	INLETS TG-1 DBL (SPL)	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6020094	MAN TA 6D T1F CL R-P	EACH	1.000				
X6021065	INLETS TG-1 SPL	EACH	45.000				
X6021824	INL-MN G-1 4D SPL	EACH	6.000				
X6021825	INL-MN G-1 5D SPL	EACH	4.000				
X6022230	MAN TA 4 DIA SPL F&G	EACH	1.000				
X6023508	INLETS TA W/SPL F&G	EACH	1.000				
X6023831	INLET TA MI SP	EACH	4.000				
X6024240	INLETS SPL	EACH	1.000				
X6024502	INLETS TB W/SPL F&G	EACH	7.000				
X6061902	CONC MED TSM SPL	SQ FT	500.000				
X6062700	CONC GUTTER TA SPL	FOOT	41.000				
X6700410	ENGR FLD OFF A SPL	CAL MO	24.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
*ADD X7010410	SPEED DISPLAY TRAILER	CAL MO	12.000				
X7050167	TEMP TRBT T1 SPL TAN	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7830068	GRV RCSD PVT LT N SYM	SQ FT	385.000				
X7830070	GRV RCSD PVT MRKG 5	FOOT	9,479.000				
X7830074	GRV RCSD PVT MRKG 7	FOOT	2,005.000				
X7830076	GRV RCSD PVT MRKG 9	FOOT	3,841.000				
X7830078	GRV RCSD PVT MRKG 13	FOOT	973.000				
X7830090	GRV RCSD PVT MRKG 25	FOOT	457.000				
X8110522	CON AT ST 2 SS	FOOT	10.000				
X8211150	LUM LED CM 50W	EACH	8.000				
X8250505	LIGHT CONTROLLER SPL	EACH	1.000				
X8410102	TEMP LIGHTING SYSTEM	L SUM	1.000				
X8570226	FAC T4 CAB SPL	EACH	1.000				
X8800025	SH LED 1F 3S SWM	EACH	6.000				
Z0001002	GDRL AGG EROS CONT	TON	64.000				
Z0001899	JACK & REM EX BEARING	EACH	18.000				
Z0004552	APPROACH SLAB REM	SQ YD	1,672.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0007101	C&D LEAD PT CL RS N1	L SUM	1.000				
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0007602	BLDG REMOV NO 2	L SUM	1.000				
Z0007603	BLDG REMOV NO 3	L SUM	1.000				
Z0010501	CLEAN & PT STL BR N1	L SUM	1.000				
Z0012754	STR REP CON DP = < 5	SQ FT	121.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018004	DRAINAGE SCUPPR DS-12	EACH	19.000				
Z0022800	FENCE REMOVAL	FOOT	2,247.000				
Z0026407	TEMP SHT PILING	SQ FT	526.000				
Z0033068	TS BATT BACKUP SYSTEM	EACH	3.000				
Z0034105	MATL TRANSFER DEVICE	TON	690.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	709.000				
Z0049803	R&D FRIABL ASB BLD 3	L SUM	1.000				
Z0049902	R&D NON-FR ASB BLD 2	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0049903	R&D NON-FR ASB BLD 3	L SUM	1.000				
Z0056648	SS 1 WAT MN 12	FOOT	148.000				
Z0056650	SS 1 WAT MN 15	FOOT	444.000				
Z0056652	SS 1 WAT MN 18	FOOT	363.000				
Z0056654	SS 1 WAT MN 24	FOOT	304.000				
Z0062456	TEMP PAVEMENT	SQ YD	3,717.000				
Z0064540	SEEPAGE COLLAR	EACH	1.000				
Z0068200	STEEL CASINGS 30	FOOT	40.000				
Z0075505	TIMBER RETAIN WALL RM	FOOT	91.000				
Z0076600	TRAINEES	HOUR	1,000.000		0.800		800.000
Z0076604	TRAINEES TPG	HOUR	1,000.000		15.000		15,000.000
20100110	TREE REMOV 6-15	UNIT	67.000				
20100210	TREE REMOV OVER 15	UNIT	51.000				
20100500	TREE REMOV ACRES	ACRE	2.000				
20200100	EARTH EXCAVATION	CU YD	36,455.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20400800	FURNISHED EXCAVATION	CU YD	16,170.000				
20700220	POROUS GRAN EMBANK	CU YD	562.000				
20800150	TRENCH BACKFILL	CU YD	1,183.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	46,590.000				
21101615	TOPSOIL F & P 4	SQ YD	60,958.000				
25000210	SEEDING CL 2A	ACRE	12.500				
25000400	NITROGEN FERT NUTR	POUND	1,134.000				
25000500	PHOSPHORUS FERT NUTR	POUND	1,134.000				
25000600	POTASSIUM FERT NUTR	POUND	1,134.000				
25000750	MOWING	ACRE	26.500				
25100115	MULCH METHOD 2	ACRE	11.500				
25100635	HD EROS CONTR BLANKET	SQ YD	6,037.000				
25200110	SODDING SALT TOLERANT	SQ YD	179.000				
28000200	EARTH EXC - EROS CONT	CU YD	800.000				
28000250	TEMP EROS CONTR SEED	POUND	12,590.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000305	TEMP DITCH CHECKS	FOOT	3,770.000				
28000400	PERIMETER EROS BAR	FOOT	3,483.000				
28000500	INLET & PIPE PROTECT	EACH	91.000				
28000510	INLET FILTERS	EACH	81.000				
28100107	STONE RIPRAP CL A4	SQ YD	2,576.000				
28100125	STONE RIPRAP CL B3	SQ YD	631.000				
28200200	FILTER FABRIC	SQ YD	3,207.000				
30300106	AGG SUBGRADE IMPR 6	SQ YD	4,986.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	41,742.000				
35300300	PCC BSE CSE 8	SQ YD	448.000				
35501310	HMA BASE CSE 6 1/2	SQ YD	268.000				
40200800	AGG SURF CSE B	TON	886.000				
40201000	AGGREGATE-TEMP ACCESS	TON	250.000				
40600100	BIT MATLS PR CT	GALLON	2,434.000				
40600115	P BIT MATLS PR CT	GALLON	1,601.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600827	P LB MM IL-4.75 N50	TON	97.000				
40600982	HMA SURF REM BUTT JT	SQ YD	421.000				
40600990	TEMPORARY RAMP	SQ YD	204.000				
40603212	P HMA BC IL12.5 N50	TON	349.000				
40603305	HMA SC "C" N30	TON	825.000				
40603560	P HMA SC "E" N50	TON	76.000				
40603565	P HMA SC "E" N70	TON	169.000				
40800050	INCIDENTAL HMA SURF	TON	57.000				
42000301	PCC PVT 8 JOINTED	SQ YD	15,518.000				
42000316	PCC PVT 8 3/4 JOINTD	SQ YD	18,975.000				
42001300	PROTECTIVE COAT	SQ YD	34,582.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	88.000				
42300400	PCC DRIVEWAY PAVT 8	SQ YD	348.000				
42400100	PC CONC SIDEWALK 4	SQ FT	2,725.000				
42400300	PC CONC SIDEWALK 6	SQ FT	1,819.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42400800	DETECTABLE WARNINGS	SQ FT	148.000				
44000100	PAVEMENT REM	SQ YD	29,347.000				
44000200	DRIVE PAVEMENT REM	SQ YD	924.000				
44000400	GUTTER REM	FOOT	853.000				
44000500	COMB CURB GUTTER REM	FOOT	2,842.000				
44000600	SIDEWALK REM	SQ FT	1,221.000				
44003100	MEDIAN REMOVAL	SQ FT	7,344.000				
44004250	PAVED SHLD REMOVAL	SQ YD	5,110.000				
44200970	CL B PATCH T2 10	SQ YD	30.000				
44201299	DOWEL BARS 1 1/2	EACH	84.000				
44213200	SAW CUTS	FOOT	144.000				
48101200	AGGREGATE SHLDS B	TON	561.000				
48203100	HMA SHOULDERS	TON	402.000				
50102400	CONC REM	CU YD	23.200				
50104650	SLOPE WALL REMOV	SQ YD	472.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50104720	REM EXIST CONC DECK	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	791.000				
50157300	PROTECTIVE SHIELD	SQ YD	847.000				
50200100	STRUCTURE EXCAVATION	CU YD	1,122.000				
50300225	CONC STRUCT	CU YD	360.600				
50300255	CONC SUP-STR	CU YD	1,095.000				
50300260	BR DECK GROOVING	SQ YD	2,243.000				
50300300	PROTECTIVE COAT	SQ YD	3,517.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	2,574.000				
50800105	REINFORCEMENT BARS	POUND	128.000				
50800205	REINF BARS, EPOXY CTD	POUND	362,710.000				
50800515	BAR SPLICERS	EACH	999.000				
50901720	BICYCLE RAILING	FOOT	138.000				
50901730	BRIDGE FENCE RAILING	FOOT	265.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50901750	PARAPET RAILING	FOOT	321.000				
51100100	SLOPE WALL 4	SQ YD	737.000				
51200957	FUR M S PILE 12X0.250	FOOT	969.000				
51200959	FUR M S PILE 14X0.312	FOOT	441.000				
51202305	DRIVING PILES	FOOT	1,410.000				
51203200	TEST PILE MET SHELLS	EACH	2.000				
51500100	NAME PLATES	EACH	2.000				
52000110	PREF JT STRIP SEAL	FOOT	174.000				
52100010	ELAST BEARING ASSY T1	EACH	24.000				
52100520	ANCHOR BOLTS 1	EACH	48.000				
52100530	ANCHOR BOLTS 1 1/4	EACH	6.000				
54001001	BOX CUL END SEC C1	EACH	2.000				
54003000	CONC BOX CUL	CU YD	400.300				
54010303	PCBC 3X3	FOOT	7.000				
542A0223	P CUL CL A 1 18	FOOT	49.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A1069	P CUL CL A 2 24	FOOT	138.000				
5421D012	P CUL CL D 1 12 TEMP	FOOT	105.000				
5421D015	P CUL CL D 1 15 TEMP	FOOT	156.000				
5421D024	P CUL CL D 1 24 TEMP	FOOT	65.000				
54213657	PRC FLAR END SEC 12	EACH	18.000				
54213660	PRC FLAR END SEC 15	EACH	12.000				
54213663	PRC FLAR END SEC 18	EACH	6.000				
54213669	PRC FLAR END SEC 24	EACH	4.000				
54213675	PRC FLAR END SEC 30	EACH	1.000				
54215547	MET END SEC 12	EACH	2.000				
5422D018	P CUL CL D 2 18 TEMP	FOOT	22.000				
54248510	CONCRETE COLLAR	CU YD	3.000				
550A0050	STORM SEW CL A 1 12	FOOT	880.000				
550A0070	STORM SEW CL A 1 15	FOOT	620.000				
550A0090	STORM SEW CL A 1 18	FOOT	103.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0140	STORM SEW CL A 1 30	FOOT	68.000				
550A0210	STORM SEW CL A 1 60	FOOT	35.000				
550A0340	STORM SEW CL A 2 12	FOOT	177.000				
550A0360	STORM SEW CL A 2 15	FOOT	1,129.000				
550A0380	STORM SEW CL A 2 18	FOOT	40.000				
550A0660	STORM SEW CL A 3 15	FOOT	217.000				
550A0700	STORM SEW CL A 3 21	FOOT	91.000				
55100900	STORM SEWER REM 18	FOOT	104.000				
55101200	STORM SEWER REM 24	FOOT	79.000				
56103100	D I WATER MAIN 8	FOOT	439.000				
56103300	D I WATER MAIN 12	FOOT	29.000				
56103400	D I WATER MAIN 16	FOOT	3,230.000				
56105000	WATER VALVES 8	EACH	5.000				
56105200	WATER VALVES 12	EACH	1.000				
56105760	BUTTERFLY VALVES 16	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
56109200	TAP VALVE & SLEEVE 16	EACH	3.000				
58700300	CONCRETE SEALER	SQ FT	1,223.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	664.000				
60100945	PIPE DRAINS 12	FOOT	26.000				
60107600	PIPE UNDERDRAINS 4	FOOT	210.000				
60221100	MAN TA 5 DIA T1F CL	EACH	4.000				
60224458	MAN TA 8 DIA T8G	EACH	1.000				
60258100	MAN RECON NEW T1F OL	EACH	1.000				
60260100	INLETS ADJUST	EACH	2.000				
60500040	REMOV MANHOLES	EACH	2.000				
60500060	REMOV INLETS	EACH	3.000				
60600095	CLASS SI CONC OUTLET	CU YD	12.000				
60604400	COMB CC&G TB6.18	FOOT	606.000				
60605000	COMB CC&G TB6.24	FOOT	9,819.000				
60605500	COMB CC&G TB6.24 VWGF	FOOT	161.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60611811	COMB CC&G TM MOD	FOOT	44.000				
60619600	CONC MED TSB6.12	SQ FT	22,977.000				
60623745	CONC MEDIAN TRANS	SQ FT	120.000				
60625610	ISLAND PAVEMENT 8	SQ YD	416.000				
60900140	TY B INLET BOX 609006	EACH	2.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	62.500				
63100085	TRAF BAR TERM T6	EACH	1.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	1.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	2.000				
63200310	GUARDRAIL REMOV	FOOT	884.000				
64300260	IMP ATTEN FRD NAR TL3	EACH	3.000				
64300450	IMP ATTEN NRD TL3	EACH	2.000				
64301090	ATTENUATOR BASE	SQ YD	94.000				
66400305	CH LK FENCE 6	FOOT	2,045.000				
66600105	FUR ERECT ROW MARKERS	EACH	30.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -

Code - 143 - -

District - 4 - -

Section Number - 105;(72-7HB)BY

Project Number

ACM-000S/983/

\*REVISED: APRIL 11, 2014

Route

FAU 6584

FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
66700205	PERM SURV MKRS T1	EACH	12.000				
67000600	ENGR FIELD LAB	CAL MO	24.000				
67100100	MOBILIZATION	L SUM	1.000				
67201000	SEAL ABAN WATER WELLS	EACH	1.000				
70100207	TRAF CONT-PROT 701402	EACH	2.000				
70100420	TRAF CONT-PROT 701411	EACH	2.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70100820	TRAF CONT-PROT 701451	L SUM	1.000				
70100825	TRAF CONT-PROT 701456	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	250.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	12.000				
70300100	SHORT TERM PAVT MKING	FOOT	424.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	1,466.000				
70300220	TEMP PVT MK LINE 4	FOOT	101,564.000				
70300240	TEMP PVT MK LINE 6	FOOT	435.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA- -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300250	TEMP PVT MK LINE 8	FOOT	13,529.000				
70300260	TEMP PVT MK LINE 12	FOOT	2,411.000				
70300280	TEMP PVT MK LINE 24	FOOT	1,391.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	27,407.000				
70400100	TEMP CONC BARRIER	FOOT	850.000				
70400200	REL TEMP CONC BARRIER	FOOT	475.000				
70600251	IMP ATTN TEMP NRN TL3	EACH	4.000				
70600352	IMP ATTN REL NRN TL3	EACH	2.000				
70800105	TEMP WAT FILL BARRIER	FOOT	912.000				
72000100	SIGN PANEL T1	SQ FT	239.000				
72000300	SIGN PANEL T3	SQ FT	1,131.000				
72400100	REMOV SIN PAN ASSY TA	EACH	20.000				
72400310	REMOV SIGN PANEL T1	SQ FT	33.000				
72700100	STR STL SIN SUP BA	POUND	4,224.000				
72800100	TELES STL SIN SUPPORT	FOOT	389.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
73301810	OSS WALKWAY TY A	FOOT	17.000				
73302110	OSS CANT 1CA 2-0X4-6	FOOT	18.000				
73304000	OVHD SIN STR BR MT	FOOT	15.000				
73400100	CONC FOUNDATION	CU YD	11.100				
73400200	DRILL SHAFT CONC FDN	CU YD	4.700				
73600100	REMOV OH SIN STR-SPAN	EACH	1.000				
73600200	REMOV OH SIN STR-CANT	EACH	2.000				
73602000	REM OVHD SN STR-BR MT	EACH	1.000				
73700100	REM GR MT SIN SUPPORT	EACH	2.000				
73700200	REM CONC FDN-GR MT	EACH	2.000				
73700300	REM CONC FDN-OVHD	EACH	6.000				
78009000	MOD URETH PM LTR-SYM	SQ FT	1,098.000				
78009004	MOD URETH PM LINE 4	FOOT	29,581.000				
78009006	MOD URETH PM LINE 6	FOOT	2,681.000				
78009008	MOD URETH PM LINE 8	FOOT	8,189.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78009012	MOD URETH PM LINE 12	FOOT	1,885.000				
78009024	MOD URETH PM LINE 24	FOOT	612.000				
78100100	RAISED REFL PAVT MKR	EACH	143.000				
78100200	TEMP RAIS REF PVT MKR	EACH	249.000				
78200410	GUARDRAIL MKR TYPE A	EACH	5.000				
78200530	BAR WALL MKR TYPE C	EACH	8.000				
78201000	TERMINAL MARKER - DA	EACH	3.000				
78300100	PAVT MARKING REMOVAL	SQ FT	7,480.000				
80400100	ELECT SERV INSTALL	EACH	2.000				
80500200	SERV INSTALL TY B	EACH	1.000				
81028320	UNDRGRD C PVC 1	FOOT	11.000				
81028350	UNDRGRD C PVC 2	FOOT	7,546.000				
81028360	UNDRGRD C PVC 2 1/2	FOOT	490.000				
81028370	UNDRGRD C PVC 3	FOOT	824.000				
81028380	UNDRGRD C PVC 3 1/2	FOOT	578.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81028390	UNDRGRD C PVC 4	FOOT	115.000				
81100800	CON AT ST 3 GALVS	FOOT	20.000				
81200210	CON EMB STR 1 PVC	FOOT	175.000				
81200230	CON EMB STR 2 PVC	FOOT	591.000				
81300420	JUN BX SS AS 10X8X6	EACH	1.000				
81300530	JUN BX SS AS 12X10X6	EACH	5.000				
81400700	HANDHOLE PCC	EACH	24.000				
81400720	DBL HANDHOLE PCC	EACH	1.000				
81603000	UD 2#8 #8G XLP USE 3/4	FOOT	345.000				
81603030	UD 2#4 #6G XLP USE 1	FOOT	14,000.000				
81702110	EC C XLP USE 1C 10	FOOT	848.000				
81702130	EC C XLP USE 1C 6	FOOT	24,155.000				
81702140	EC C XLP USE 1C 4	FOOT	547.000				
82102250	LUM SV HOR MT 250W	EACH	33.000				
82102400	LUM SV HOR MT 400W	EACH	45.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
82107300	UNDERPAS LUM 150W HPS	EACH	4.000				
82500360	LT CONT BASEM 480V100	EACH	1.000				
83060450	LT P GS 45MH 15MA	EACH	34.000				
83060550	LT P GS 50MH 15MA	EACH	40.000				
83600300	LIGHT POLE FDN 30D	FOOT	511.000				
*REV 83800205	BKWY DEV TR B 15BC	EACH	34.000				
*ADD 83800505	BKWY DEV COU AL SKIRT	EACH	160.000				
84200500	REM LT UNIT SALV	EACH	1.000				
84200600	REM LT U NO SALV	EACH	11.000				
84200804	REM POLE FDN	EACH	12.000				
84500110	REMOV LIGHTING CONTR	EACH	1.000				
84500120	REMOV ELECT SERV INST	EACH	1.000				
84500130	REMOV LTG CONTR FDN	EACH	1.000				
87100020	FOCC62.5/125 MM12SM12	FOOT	3,390.000				
87200400	SPAN WIRE	FOOT	360.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87200500	TETHER WIRE	FOOT	360.000				
87300010	GROUND HH FR & COVER	EACH	3.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	497.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	5,113.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	2,310.000				
87301515	ELCBL C LEAD 18 3PR	FOOT	5,870.000				
87302145	ELCBL AS SIGL 12 5C	FOOT	810.000				
87502490	TS POST GALVS 15	EACH	2.000				
87502520	TS POST GALVS 18	EACH	1.000				
87600100	PED PUSH-BUT POST T1	EACH	3.000				
87702920	STL COMB MAA&P 38	EACH	1.000				
87702970	STL COMB MAA&P 48	EACH	1.000				
87704344	S C MAA&P DMA 28 & 60	EACH	1.000				
87704560	S C MAA&P DMA 60 & 36	EACH	1.000				
87800100	CONC FDN TY A	FOOT	9.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

68683

State Job # - C-94-014-07

County Name - PEORIA - -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87800200	CONC FDN TY D	FOOT	7.000				
87800415	CONC FDN TY E 36D	FOOT	54.000				
87800420	CONC FDN TY E 42D	FOOT	42.000				
87900200	DRILL EX HANDHOLE	EACH	18.000				
88030020	SH LED 1F 3S MAM	EACH	12.000				
88030050	SH LED 1F 3S BM	EACH	7.000				
88030070	SH LED 1F 4S BM	EACH	2.000				
88030080	SH LED 1F 4S MAM	EACH	2.000				
88200310	TS BACKPLATE LOU PLAS	EACH	25.000				
88500100	INDUCTIVE LOOP DETECT	EACH	31.000				
88600100	DET LOOP T1	FOOT	3,249.000				
89000100	TEMP TR SIG INSTALL	EACH	3.000				
89500100	RELOC EX SIG HEAD	EACH	3.000				
89500400	RELOC EX PED PUSH-BUT	EACH	5.000				
89501100	RELOC EX TS CONT	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 68683

State Job # - C-94-014-07

County Name - PEORIA- -  
 Code - 143 - -  
 District - 4 - -  
 Section Number - 105;(72-7HB)BY

Project Number  
 ACM-000S/983/  
 \*REVISED: APRIL 11, 2014

Route  
 FAU 6584  
 FAU 6585

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89501300	RELOC EX MAA & POLE	EACH	2.000				
89502105	REBUILD EX SIG HD LED	EACH	4.000				
89502210	MOD EX CONTR CAB	EACH	3.000				
89502375	REMOV EX TS EQUIP	EACH	2.000				
89502380	REMOV EX HANDHOLE	EACH	12.000				
89502382	REMOV EX DBL HANDHOLE	EACH	1.000				
89502385	REMOV EX CONC FDN	EACH	13.000				

CONCRETE BOX CULVERTS WITH SKEWS $\leq$ 30 DEGREES REGARDLESS OF DESIGN FILL AND SKEWS > 30 DEGREES WITH DESIGN FILLS > 5 FEET (BDE) .....	274
CONCRETE GUTTER, CURB, MEDIAN, AND PAVED DITCH (BDE).....	274
CONCRETE MIX DESIGN – DEPARTMENT PROVIDED (BDE).....	275
CONTRACT CLAIMS (BDE).....	275
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	276
FRICTION AGGREGATE (BDE) .....	285
GRANULAR MATERIALS (BDE).....	288
GROOVING FOR RECESSED PAVEMENT MARKINGS (BDE).....	289
HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) .....	291
LRFD PIPE CULVERT BURIAL TABLES (BDE).....	292
LRFD STORM SEWER BURIAL TABLES (BDE).....	311
PAVED SHOULDER REMOVAL (BDE) .....	319
PAYROLLS AND PAYROLL RECORDS (BDE).....	320
PORTLAND CEMENT CONCRETE – CURING OF ABUTMENTS AND PIERS (BDE).....	321
PORTLAND CEMENT CONCRETE EQUIPMENT (BDE).....	322
PROGRESS PAYMENTS (BDE).....	322
QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE) .....	323
REINFORCEMENT BARS (BDE).....	323
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) .....	325
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE) .....	328
TRACKING THE USE OF PESTICIDES (BDE).....	329
TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/EXPRESSWAY (BDE).....	329
TRAINING SPECIAL PROVISIONS (BDE) .....	330
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION (TPG).....	332
WARM MIX ASPHALT (BDE).....	334
WEEKLY DBE TRUCKING REPORTS (BDE).....	339
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID).....	339
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) .....	342
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) .....	346
PROJECT LABOR AGREEMENT - QUARTERLY EMPLOYMENT REPORT .....	350
PROJECT LABOR AGREEMEN .....	350
SWPPP .....	368
SPEED DISPLAY TRAILER (BDE).....	376

## **SPEED DISPLAY TRAILER (BDE)**

Effective: April 2, 2014

Add the following to Article 701.15(l) of the Standard Specifications:

- “ (l) Speed Display Trailer. A speed display trailer shall be utilized on freeways and expressways as part of Highway Standard 701400. The trailer shall be placed on the right hand side of the roadway adjacent to, or within 100 ft (30 m) beyond, the first work zone speed limit sign.

Whenever the speed display trailer is not in use, it shall be considered non-operating equipment and shall be stored according to Article 701.11.”

Add the following to Article 701.20 of the Standard Specifications:

- “ (k) Speed Display Trailer will be paid for at the contract unit price per calendar month or fraction thereof for each trailer as SPEED DISPLAY TRAILER.”

Add the following to Article 1106.02 of the Standard Specifications:

- “ (o) Speed Display Trailer. The speed display trailer shall consist of a LED speed indicator display with self-contained, one-direction radar mounted on an orange see-through trailer. The height of the display and radar shall be such that it will function and be visible when located behind concrete barrier.

The speed measurement shall be by radar and provide a minimum detection distance of 1000 ft (300 m). The radar shall have an accuracy of  $\pm 1$  mile per hour.

The speed indicator display shall face approaching traffic and shall have a sign legend of “YOUR SPEED” immediately above or below the speed display. The digital speed display shall show two digits (00 to 99) in mph. The color of the changeable message legend shall be a yellow legend on a black background. The minimum height of the numerals shall be 18 in. (450 mm), and the nominal legibility distance shall be at least 750 ft (250 m).

The speed indicator display shall be equipped with a violation alert that flashes the displayed detected speed when the posted limit is exceeded. The speed indicator shall have a maximum speed cutoff. The display shall include automatic dimming for nighttime operation.

The speed indicator measurement and display functions shall be equipped with the power supply capable of providing 24 hours of uninterrupted service.”

Added 04/15/2014