

AGGREGATE SUBGRADE IMPROVEMENT 12"				
LOCATION			SQ YD	REMARKS
46+00.00	TO	56+89.40	8378.24	ALLEN RD
60+15.40	TO	95+67.00	28267.90	ALLEN RD/VAN WINKLE WAY
19+70.60	TO	23+49.24	444.38	RAMP B WIDENING
113+00.00	TO	118+33.09	3016.45	ALTA LN
118+79.41	TO	BROMPTON CT EXTENSION	1635.14	ALTA LN
TOTAL			41742.1	ROUND TO 41743

PORTLAND CEMENT CONCRETE BASE COURSE 8"				
LOCATION			SQ YD	REMARKS
19+85.43	TO	23+49.24	447.5	RAMP B
TOTAL			447.5	ROUND TO 448

HOT-MIX ASPHALT BASE COURSE, 6 1/2"				
LOCATION			SQ YD	REMARKS
113+98.50	TO	114+33.49	29.87	ALTA LN
120+11.11			238.44	EMERGENCY RD ACCESS
TOTAL			268.3	ROUND TO 269

AGGREGATE SURFACE COURSE, TYPE B				
LOCATION			TON	REMARKS
114+12.47			5.7	ALTA LN
78+62.00	TO	80+34.00	204.0	PRE-STAGE
91+45.00	TO	96+48.00	676.0	STAGE 1
TOTAL			885.7	ROUND TO 886

BITUMINOUS MATERIALS (PRIME COAT)				
LOCATION			GALLON	REMARKS
45+28.65	TO	56+89.40	661.0	ALLEN ROAD
60+15.40	TO	72+19.67	685.9	ALLEN ROAD
73+52.37	TO	78+13.50	262.5	ALLEN ROAD
78+38.23	TO	85+59.31	411.2	ALLEN ROAD
503+90.00	TO	504+95.60	59.7	ROCK ISLAND TRAIL
506+85.60	TO	508+40.01	87.3	ROCK ISLAND TRAIL
600+00.00	TO	604+53.88	266.2	TRAIL SPUR
TOTAL			2433.9	ROUND TO 2434

POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)				
LOCATION			GALLON	REMARKS
95+67.00	TO	97+75.64	386.08	ALLEN RD ON AGGREGATE
1+26.09	TO	2+00.00	120.00	RAMP A ON AGGREGATE
19+70.60	TO	23+49.24	720.51	RAMP B ON AGGREGATE
22+67.99	TO	23+17.99	77.73	RAMP C ON AGGREGATE
2+41.62	TO	2+91.62	84.72	RAMP C ON AGGREGATE
112+50.00	TO	113+00.00	66.67	ALTA LN ON AGGREGATE
95+67.00	TO	97+75.64	38.61	ALLEN RD FOG COAT
1+26.09	TO	2+00.00	12.00	RAMP A FOG COAT
19+70.60	TO	23+49.24	72.05	RAMP B FOG COAT
22+67.99	TO	23+17.99	7.77	RAMP C FOG COAT
2+41.62	TO	2+91.62	8.47	RAMP C FOG COAT
112+50.00	TO	113+00.00	6.67	ALTA LN FOG COAT
TOTAL			1601.3	ROUND TO 1602

POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50				
LOCATION			TON	REMARKS
20+00.62	TO	23+49.24	78.14	RAMP B
1+29.09	TO	1+70.00	8.23	RAMP A
22+98.00	TO	23+17.98	3.51	RAMP C
2+41.62	TO	2+61.62	3.97	RAMP D
112+80.00	TO	113+00.00	3.01	ALTA LN
TOTAL			96.9	ROUND TO 97

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT				
LOCATION			SQ YD	REMARKS
01+70.00	TO	02+00.00	94.04	RAMP A
19+70.10	TO	20+00.59	54.36	RAMP B
22+68.00	TO	22+98.00	93.22	RAMP C
02+61.62	TO	02+91.62	98.92	RAMP D
112+50.00	TO	112+80.00	80.00	ALTA LN
TOTAL			420.5	ROUND TO 421

POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50				
LOCATION			TON	REMARKS
95+67.00	TO	97+50.00	348.5	ALLEN ROAD
TOTAL			348.5	ROUND TO 349

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30				
LOCATION			TON	REMARKS
45+28.65	TO	56+89.40	222.11	ALLEN ROAD
60+15.40	TO	72+11.84	230.47	ALLEN ROAD
73+52.37	TO	78+13.50	88.22	ALLEN ROAD
78+38.24	TO	85+49.71	138.16	ALLEN ROAD
503+90.00	TO	504+95.60	20.04	ROCK ISLAND TRAIL
506+85.60	TO	508+40.01	29.35	ROCK ISLAND TRAIL
600+00.00	TO	604+53.88	89.44	TRAIL SPUR
11+36.39	TO	12+13.88	6.90	VAN WINKLE WAY
TOTAL			824.7	ROUND TO 825

POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50				
LOCATION			TON	REMARKS
95+67.00	TO	97+75.66	65.08	ALLEN RD
112+50.00	TO	113+00.00	11.27	ALTA LN
TOTAL			76.4	ROUND TO 77

POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70				
LOCATION			TON	REMARKS
1+26.09	TO	1+98.12	20.26	RAMP A
19+70.60	TO	23+49.24	121.50	RAMP B
21+43.12	TO	23+17.99	13.13	RAMP C
2+41.62	TO	4+02.68	14.29	RAMP D
TOTAL			169.2	ROUND TO 170

INCIDENTAL HOT-MIX ASPHALT SURFACING				
LOCATION			TON	REMARKS
113+98.50	TO	114+33.49	2.51	ALTA LN
120+11.11			19.45	EMERGENCY ACCESS RD
VARIOUS			35	SEE STAGING DETAILS
TOTAL			57	

PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)				
LOCATION			SQ YD	REMARKS
74+00	TO	95+67	11614.8	ALLEN RD
113+00	TO	ALLEN RD	2452.5	ALTA LN
ALLEN RD	TO	BROMPTON CT. EXTENSION	1450.6	ALTA LN
TOTAL			15517.8	ROUND TO 15518

PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)				
LOCATION			SQ YD	REMARKS
46+95.50	TO	48+90.00	239.0	ALLEN RD
48+33.00	TO	48+90.00	20.2	ALLEN RD
48+90.00	TO	56+83.40	6155.2	ALLEN RD
60+21.40	TO	74+00.00	12560.9	ALLEN RD
TOTAL			18975.3	ROUND TO 18976

BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)				
LOCATION			SQ YD	REMARKS
56+83.40	TO	56+89.40	44.00	ALLEN RD
60+15.40	TO	60+21.40	44.00	ALLEN RD
TOTAL			88.0	ROUND TO 88

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH				
LOCATION			SQ YD	REMARKS
78+26.40		RT	134.96	ALLEN ROAD
78+69.94		LT	186.79	ALLEN ROAD
120+11.11		RT	25.76	ALTA LANE
TOTAL			347.5	ROUND TO 348

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH				
LOCATION			SQ FT	REMARKS
119+03.86	TO	121+32.91	1517.97	ALTA LANE
119+04.39	TO	119+94.44	626.45	ALTA LANE
120+29.38	TO	121+33.54	580.87	ALTA LANE
TOTAL			2725.3	ROUND TO 2726

PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH				
LOCATION			SQ FT	REMARKS
45+08.04	TO	45+28.66	176.38	NE QUAD TOWNLINE
72+11.84	TO	72+49.15	708.45	SE QUAD VAN WINKLE
73+32.38	TO	73+52.37	166.70	NE QUAD VAN WINKLE
73+40.12	TO	73+51.47	55.17	NW QUAD VAN WINKLE
85+49.72	TO	85+77.88	353.68	SE QUAD ALTA LN
86+22.56	TO	86+50.45	358.96	NE QUAD ALTA LN
TOTAL			1819.3	ROUND TO 1820

DETECTABLE WARNINGS				
LOCATION			SQ FT	REMARKS
45+08.36	TO	45+17.63	27.45	NE QUAD TOWNLINE
72+36.84	TO	72+48.70	32.41	SE QUAD VAN WINKLE
73+32.76	TO	73+42.37	27.63	NE QUAD VAN WINKLE
73+40.37	TO	73+44.73	9.76	NW QUAD VAN WINKLE
85+69.71	TO	85+77.62	25.63	SE QUAD ALTA LN
86+22.80	TO	86+30.45	25.53	NE QUAD ALTA LN
TOTAL			148.4	ROUND TO 149