

PAVEMENT REMOVAL					
LOCATION				SQ YD	REMARKS
46+95.50	TO	48+90.00	LT	159.57	ALLEN RD, LT OF MEDIAN
47+45.49	TO	48+90.00	RT	98.71	ALLEN RD, RT OF MEDIAN
48+90.00	TO	50+24.27	LT	395.70	ALLEN RD, LT OF MEDIAN
48+90.00	TO	50+24.27	RT	567.80	ALLEN RD, RT OF MEDIAN
50+24.27	TO	52+78.19	LT/RT	2790.78	ALLEN RD/IL 6 NB
52+78.19	TO	56+19.36	LT	998.00	ALLEN RD
52+78.19	TO	56+19.36	RT	1007.31	ALLEN RD
60+85.42	TO	64+61.02	LT	710.97	ALLEN RD
60+85.42	TO	64+61.02	RT	1541.48	ALLEN RD
64+61.02	TO	67+14.16	LT/RT	2702.21	ALLEN RD/IL 6 SB
67+14.16	TO	72+21.05	LT/RT	2929.29	ALLEN RD
72+21.05	TO	74+00.00	LT/RT	1849.17	VAN WINKLE INTERSECTION
74+00.00	TO	81+75.62	LT/RT	3086.53	ALLEN RD
81+75.62	TO	83+93.77	LT	1050.31	ALLEN RD, ALTA 'Y'
83+93.77	TO	113+00.00	LT	1841.96	ALLEN RD TO ALTA LANE
83+93.77	TO	95+66.78	LT/RT	3173.91	ALLEN RD
91+32.54			RT	411.20	BROMPTON CT ACCESS
503+90.00	TO	505+53.24		151.98	ROCK ISLAND TRAIL
506+65.16	TO	508+40.00		163.26	ROCK ISLAND TRAIL
VARIOUS (TEMP. PAVT. LOCATIONS)				3717	SEE TEMP. PAVT. SCHED.
TOTAL				29347	

DRIVEWAY PAVEMENT REMOVAL					
LOCATION				SQ YD	REMARKS
78+25.99			RT	203.77	CE/ALLEN RD
78+45.04			LT	259.83	CE/ALLEN RD
82+37.27			RT	111.36	CE/ALLEN RD
83+59.06			RT	46.88	PE/ALLEN RD
89+74.98			LT	132.49	PE/ALLEN RD
16+06.34			RT	132.17	CE/VAN WINKLE
114+12.09			RT	37.19	PE/ALTA LN
TOTAL				923.7	ROUND TO 924

GUTTER REMOVAL					
LOCATION				FOOT	REMARKS
56+51.69	TO	57+19.16	LT	71.59	ALLEN RD
59+85.38	TO	60+48.85	RT	66.25	ALLEN RD
81+65.48	TO	84+65.93	LT	316.28	ALLEN RD
114+35.47	TO	117+70.58	RT	397.94	ALTA LN
TOTAL				852.1	ROUND TO 853

COMBINATION CURB AND GUTTER REMOVAL						
LOCATION					FOOT	REMARKS
45+09.09	TO	45+18.25	RT		15.03	AT TOWNLINE
52+11.46	TO	57+19.34	LT/RT		1024.60	ALLEN ROAD
59+85.42	TO	62+36.93	RT		251.56	ALLEN ROAD
59+85.44	TO	62+37.00	LT		251.56	ALLEN ROAD
66+08.78	TO	69+22.60	LT		636.35	ALLEN ROAD
10+32.71	TO	12+13.74	RT		207.31	SE QUAD ALLEN/VW
10+86.71	TO	11+24.34	LT		37.77	NE QUAD ALLEN/VW
15+51.44	TO	17+10.79	LT		175.18	NW QUAD ALLEN/VW
15+79.49	TO	17+15.94	RT		169.40	SW QUAD ALLEN/VW
16+14.65	TO	16+61.68	RT		72.58	SW QUAD ALLEN/VW
TOTAL				2841.3	ROUND TO 2842	

SIDEWALK REMOVAL					
LOCATION				SQ FT	REMARKS
72+49.60			LT	118.14	SW QUAD ALLEN/VW
72+42.38			RT	784.98	SE QUAD ALLEN/VW
73+45.82			LT	116.01	NW QUAD ALLEN/VW
73+59.36			RT	201.13	NE QUAD ALLEN/VW
TOTAL				1220.3	ROUND TO 1221

MEDIAN REMOVAL					
LOCATION				SQ FT	REMARKS
46+00.00	TO	51+25.00	LT/RT	3194.70	ALLEN ROAD
62+36.93	TO	65+21.37	LT	1788.82	ALLEN ROAD
24+19.19	TO	24+35.76		205.78	RAMP B ISLAND
23+82.03	TO	24+07.61		459.59	RAMP C ISLAND
14+10.45	TO	16+83.21	LT	1695.56	VAN WINKLE WAY
TOTAL				7344.5	ROUND TO 7345

PAVED SHOULDER REMOVAL					
LOCATION				SQ YD	REMARKS
47+90.00	TO	56+19.37	RT	865.39	ALLEN RD
48+45.22	TO	51+13.64	LT	304.44	ALLEN RD
52+25.61	TO	56+19.37	LT	459.00	ALLEN RD
60+85.15	TO	72+20.94	RT	1010.55	ALLEN RD
60+85.15	TO	65+12.39	LT	371.72	ALLEN RD
66+22.05	TO	72+14.88	LT	418.21	ALLEN RD
73+18.61	TO	78+06.06	RT	279.31	ALLEN RD
73+60.71	TO	78+15.17	LT	212.26	ALLEN RD
78+51.07	TO	81+49.07	RT	159.40	ALLEN RD
78+84.13	TO	81+46.65	LT	141.11	ALLEN RD
19+70.59	TO	23+49.24	RT	265.41	RAMP B
19+70.60	TO	23+49.25	LT	187.85	RAMP B
23+49.25	TO	1+26.09		115.72	INSIDE RAMP A/B
1+26.09	TO	2+00.00	LT	37.94	RAMP A
1+26.10	TO	2+00.01	RT	49.56	RAMP A
22+67.99	TO	23+17.99	RT	34.22	RAMP C
22+67.99	TO	23+17.99	LT	26.12	RAMP C
23+17.99	TO	2+41.62		112.06	INSIDE RAMP C/D
2+41.62	TO	2+91.62	LT	24.66	RAMP D
2+41.62	TO	2+91.62	RT	34.24	RAMP D
TOTAL				5109.2	ROUND TO 5110

AGGREGATE SHOULDERS, TYPE B					
LOCATION				TON	REMARKS
95+67.38	TO	96+36.50	LT	8.35	ALLEN RD
95+66.05	TO	97+76.12	RT	44.85	ALLEN RD
112+50.00	TO	115+89.59	LT	54.62	ALTA LN
112+50.00	TO	113+98.50	RT	23.96	ALTA LN
73+88.00	TO	82+03.00	RT	249.60	PRE-STAGE
77+78.00	TO	84+92.74	LT	179.20	STAGE 1
TOTAL				560.6	ROUND TO 561

HOT-MIX ASPHALT SHOULDERS					
LOCATION				TON	REMARKS
47+89.99	TO	48+65.91	RT	21.13	ALLEN RD
48+45.22	TO	49+17.11	LT	19.21	ALLEN RD
97+10.40	TO	97+75.45	LT	8.64	ALLEN RD
0+97.28	TO	2+00.00	LT	22.16	RAMP A
1+32.28	TO	2+00.00	RT	18.46	RAMP A
17+50.00	TO	19+70.60	LT	44.00	RAMP B
19+70.59	TO	23+70.78	RT	126.31	RAMP B
19+70.60	TO	23+77.11	LT	87.13	RAMP B
22+67.99	TO	23+16.67	LT	11.51	RAMP C
22+67.99	TO	23+19.02	RT	13.73	RAMP C
2+11.91	TO	2+91.62	LT	18.36	RAMP D
2+46.20	TO	2+91.79	RT	11.35	RAMP D
TOTAL				402.0	ROUND TO 402

PIPE CULVERT REMOVAL					
LOCATION				FOOT	REMARKS
48+90.99	TO	48+91.19	RT	26.32	ACROSS MULTI-USE PATH
72+01.60	TO	73+94.32	RT	193.75	ACROSS VAN WINKLE
77+48.92	TO	78+70.15	RT	121.72	ENTRANCE/ALLEN RD
78+17.15	TO	78+81.31	LT	64.30	ENTRANCE/ALLEN RD
83+46.59	TO	83+71.02	RT	24.49	ENTRANCE/ALLEN RD
84+79.16	TO	85+01.12	LT	50.39	ACROSS ALTA LN
89+61.29	TO	89+87.75	LT	26.46	ENTRANCE/ALLEN RD
90+95.64	TO	91+71.80	RT	76.18	ENTRANCE/ALLEN RD
96+29.71	TO	96+92.56	RT	62.73	ALONG ALLEN RD
96+30.03	TO	96+32.70		45.79	ACROSS ALLEN RD
96+95.74	TO	97+06.66		42.53	ACROSS ALLEN RD
114+00.24	TO	114+23.95	RT	23.71	ENTRANCE/ALTA LN
506+87.91	TO	507+08.64		32.37	ACROSS RI TRAIL
TOTAL				790.7	ROUND TO 791

REINFORCEMENT BARS					
LOCATION				POUND	REMARKS
77+03.00		63.00'	RT	66.0	ALLEN RD (60" PIPE)
11+41.00		21.50'	RT	27.0	VAN WINKLE (15" PIPE)
16+70.70		29.00'	RT	35.0	VAN WINKLE (24" PIPE)
TOTAL				128.0	ROUND TO 128